



Superior NW Enterprises

April 10, 2025

**RE: Tree Protection Addendum to March 25, 2025 arborist report for Zimmer
PN 4045000065**

To Whom It May Concern:

I have reviewed the Tree Removal and Replacement plan (Sheet A 1.3) supplied by the architect.

There is a tentative plan shown for a gabion wall stretching north from tree #14 that passes between trees #16 and #18 and over the top of #17. If the wall has to be built in the location shown it will require the removal of the #16-18 trees.

The protection fencing design shown on the plan sheet is adequate and laid out as discussed in the original arborist report. It may be able to be simplified by tying the sections protecting the trees south of the driveway together and fencing off the entire area. The SE corner of this fence may have to be put in place after the #29 tree is removed.

The fencing for tree #21 will likely have to be set after the #19 and #20 cottonwoods are removed as its full extent encompasses the bases of those trees.

Please let me know if you have any questions.

Anthony Moran
ISA Certified Arborist
PN-5847A