



**MULHERN+KULP**  
RESIDENTIAL STRUCTURAL ENGINEERING

7220 Trade Street, Suite 295, San Diego, CA 92121 ▶ p 619-650-0010 ▶ [mulhernkulp.com](http://mulhernkulp.com)

# CALCULATION PACKAGE

---

Revised December 31, 2024

Design Built Homes

86<sup>th</sup> Ave SE  
Lot 2

Mercer Island,  
Washington

---

MULHERN & KULP STRUCTURAL ENGINEERING, INC.

Prepared By:

Ryan Chan, E.I.T.

*Staff Engineer*

Nicholas J. Martignetti, P.E.

*Associate Owner + San Diego Office Director*




---

*Signature, Seal & Date*

**BEAM & HEADER CALCULATIONS**

Description - Roof Framing - H3-1 - Header



Uniform 1 = 0.39 klf (0.0'-6.0')

Controlling Load Combination/ Cd

$V = (D + S) \quad Cd=1.15$

$M = (D + S) \quad Cd=1.15$

$\Delta = (D + S)$

V = 1.18k	Vall = 4.47k	Ratio = 0.26
-----------	--------------	--------------

M = 1.77k-ft	Mall = 5.17k-ft	Ratio = 0.34
--------------	-----------------	--------------

Deflection


TL = 0.03" L/999+ > L/240 min

DL = 0.01"

L = 0.00" L/999+ > L/360 min

4x10 DF #2

Description - Roof Framing - H3-2 - Header



Uniform 1 = 0.25 klf (0.0'-6.0')

Controlling Load Combination/ Cd

$V = (D + S) \quad Cd=1.15$

$M = (D + S) \quad Cd=1.15$

$\Delta = (D + S)$

V = 0.76k	Vall = 4.47k	Ratio = 0.17
-----------	--------------	--------------

M = 1.14k-ft	Mall = 5.17k-ft	Ratio = 0.22
--------------	-----------------	--------------

Deflection


TL = 0.02" L/999+ > L/240 min

DL = 0.01"

L = 0.00" L/999+ > L/360 min

4x10 DF #2

Description - Roof Framing - H3-3 - Header



Uniform 1 = 0.07 klf (0.0'-2.0')

Controlling Load Combination/ Cd

$V = (D + S) \quad Cd=1.15$

$M = (D + S) \quad Cd=1.15$

$\Delta = (D + S)$

V = 0.07k	Vall = 4.47k	Ratio = 0.02
-----------	--------------	--------------

M = 0.04k-ft	Mall = 5.17k-ft	Ratio = 0.01
--------------	-----------------	--------------

Deflection


TL = 0.00" L/999+ > L/240 min

DL = 0.00"

L = 0.00" L/999+ > L/360 min

4x10 DF #2

Description - Roof Framing - H3-4 - Header



Uniform 1 = 0.31 klf (0.0'-5.0')

Controlling Load Combination/ Cd

$V = (D + S) \quad Cd=1.15$

$M = (D + S) \quad Cd=1.15$

$\Delta = (D + S)$

V = 0.78k	Vall = 4.47k	Ratio = 0.17
-----------	--------------	--------------

M = 0.97k-ft	Mall = 5.17k-ft	Ratio = 0.19
--------------	-----------------	--------------

Deflection

TL = 0.01" L/999+ > L/240 min


DL = 0.00"

L = 0.00" L/999+ > L/360 min

4x10 DF #2



**Description - Roof Framing - H3-5 - Header**




Uniform 1 = 0.39 klf (0.0'-3.2')  
Uniform 2 = 0.31 klf (3.2'-5.0')

Controlling Load Combination/ Cd  
V = (D + S) Cd=1.15  
M = (D + S) Cd=1.15  
 $\Delta = (D + S)$

V = 0.95k	Vall = 4.47k	Ratio = 0.21
M = 1.16k-ft	Mall = 5.17k-ft	Ratio = 0.22
Deflection		
TL = 0.01" L/999+ > L/240 min		
DL = 0.00"		
L = 0.00" L/999+ > L/360 min		

4x10 DF #2

**Description - Roof Framing - H3-6 - Header**




Uniform 1 = 0.40 klf (0.0'-2.9')      P1 = 0.60 K (3.0')  
Uniform 2 = 0.49 klf (2.9'-4.0')

Controlling Load Combination/ Cd  
V = (D + S) Cd=1.15  
M = (D + S) Cd=1.15  
 $\Delta = (D + S)$

V = 1.33k	Vall = 4.47k	Ratio = 0.30
M = 1.18k-ft	Mall = 5.17k-ft	Ratio = 0.23
Deflection		
TL = 0.01" L/999+ > L/240 min		
DL = 0.00"		
L = 0.00" L/999+ > L/360 min		

4x10 DF #2

**Description - Roof Framing - H3-7 - Header**




Uniform 1 = 0.49 klf (0.0'-3.6')      P1 = 0.60 K (3.6')  
Uniform 2 = 0.40 klf (3.6'-4.0')

Controlling Load Combination/ Cd  
V = (D + S) Cd=1.15  
M = (D + S) Cd=1.15  
 $\Delta = (D + S)$

V = 1.48k	Vall = 4.47k	Ratio = 0.33
M = 1.11k-ft	Mall = 5.17k-ft	Ratio = 0.21
Deflection		
TL = 0.01" L/999+ > L/240 min		
DL = 0.00"		
L = 0.00" L/999+ > L/360 min		

4x10 DF #2

**Description - Roof Framing - H3-8 - Header**




Uniform 1 = 0.49 klf (0.0'-4.0')

Controlling Load Combination/ Cd  
V = (D + S) Cd=1.15  
M = (D + S) Cd=1.15  
 $\Delta = (D + S)$

V = 0.97k	Vall = 4.47k	Ratio = 0.22
M = 0.97k-ft	Mall = 5.17k-ft	Ratio = 0.19
Deflection		
TL = 0.01" L/999+ > L/240 min		
DL = 0.00"		
L = 0.00" L/999+ > L/360 min		

4x10 DF #2

Description - Roof Framing - H3-9 - Header



Uniform 1 = 0.49 klf (0.0'-4.0')

Controlling Load Combination/ Cd

$V = (D + S) \quad Cd=1.15$


$M = (D + S) \quad Cd=1.15$

$\Delta = (D + S)$

V = 0.97k	Vall = 4.47k	Ratio = 0.22
M = 0.97k-ft	Mall = 5.17k-ft	Ratio = 0.19
Deflection		
TL = 0.01"	L/999+ > L/240 min	
DL = 0.00"		
L = 0.00"	L/999+ > L/360 min	

4x10 DF #2

Description - Roof Framing - H3-10 - Header



Uniform 1 = 0.50 klf (0.0'-2.3')

Controlling Load Combination/ Cd

$V = (D + S) \quad Cd=1.15$


$M = (D + S) \quad Cd=1.15$

$\Delta = (D + S)$

V = 0.58k	Vall = 4.47k	Ratio = 0.13
M = 0.34k-ft	Mall = 5.17k-ft	Ratio = 0.07
Deflection		
TL = 0.00"	L/999+ > L/240 min	
DL = 0.00"		
L = 0.00"	L/999+ > L/360 min	

4x10 DF #2

Description - Roof Framing - H3-11 - Header



Uniform 1 = 0.42 klf (0.0'-2.7')

Controlling Load Combination/ Cd

$V = (D + S) \quad Cd=1.15$


$M = (D + S) \quad Cd=1.15$

$\Delta = (D + S)$

V = 0.56k	Vall = 4.47k	Ratio = 0.13
M = 0.37k-ft	Mall = 5.17k-ft	Ratio = 0.07
Deflection		
TL = 0.00"	L/999+ > L/240 min	
DL = 0.00"		
L = 0.00"	L/999+ > L/360 min	

4x10 DF #2

Description - Roof Framing - H3-12 - Header



Uniform 1 = 0.44 klf (0.0'-2.7')

Controlling Load Combination/ Cd

$V = (D + S) \quad Cd=1.15$

$M = (D + S) \quad Cd=1.15$


$\Delta = (D + S)$

V = 0.58k	Vall = 4.47k	Ratio = 0.13
M = 0.39k-ft	Mall = 5.17k-ft	Ratio = 0.07
Deflection		
TL = 0.00"	L/999+ > L/240 min	
DL = 0.00"		
L = 0.00"	L/999+ > L/360 min	

4x10 DF #2



Description - Roof Framing - H3-13 - Header



Uniform 1 = 0.52 klf (0.0'-2.3')

Controlling Load Combination/ Cd

$V = (D + S) \quad Cd=1.15$


$M = (D + S) \quad Cd=1.15$

$\Delta = (D + S)$

V = 0.60k	Vall = 4.47k	Ratio = 0.13
M = 0.35k-ft	Mall = 5.17k-ft	Ratio = 0.07
Deflection		
TL = 0.00"	L/999+ > L/240 min	
DL = 0.00"		
L = 0.00"	L/999+ > L/360 min	

4x10 DF #2

Description - Roof Framing - H3-14 - Header



Uniform 1 = 0.07 klf (0.0'-3.8')

Controlling Load Combination/ Cd

$V = (D + S) \quad Cd=1.15$


$M = (D + S) \quad Cd=1.15$

$\Delta = (D + S)$

V = 0.13k	Vall = 4.47k	Ratio = 0.03
M = 0.12k-ft	Mall = 5.17k-ft	Ratio = 0.02
Deflection		
TL = 0.00"	L/999+ > L/240 min	
DL = 0.00"		
L = 0.00"	L/999+ > L/360 min	

4x10 DF #2

Description - Roof Framing - H3-15 - Header



Uniform 1 = 0.07 klf (0.0'-3.8')

Controlling Load Combination/ Cd

$V = (D + S) \quad Cd=1.15$


$M = (D + S) \quad Cd=1.15$

$\Delta = (D + S)$

V = 0.13k	Vall = 4.47k	Ratio = 0.03
M = 0.12k-ft	Mall = 5.17k-ft	Ratio = 0.02
Deflection		
TL = 0.00"	L/999+ > L/240 min	
DL = 0.00"		
L = 0.00"	L/999+ > L/360 min	

4x10 DF #2

Description - Roof Framing - H3-16 - Header



Uniform 1 = 0.34 klf (0.0'-8.0')

Controlling Load Combination/ Cd

$V = (D + S) \quad Cd=1.15$

$M = (D + S) \quad Cd=1.15$


$\Delta = (D + S)$

V = 1.37k	Vall = 4.47k	Ratio = 0.31
M = 2.74k-ft	Mall = 5.17k-ft	Ratio = 0.53
Deflection		
TL = 0.09"	L/999+ > L/240 min	
DL = 0.02"		
L = 0.00"	L/999+ > L/360 min	

4x10 DF #2



**Description - Roof Framing - H3-17 - Header**



Uniform 1 = 0.34 klf (0.0'-8.0')

Controlling Load Combination/ Cd

$V = (D + S) \quad Cd=1.15$

$M = (D + S) \quad Cd=1.15$

$\Delta = (D + S)$

V = 1.37k	Vall = 4.47k	Ratio = 0.31
M = 2.74k-ft	Mall = 5.17k-ft	Ratio = 0.53

Deflection


TL = 0.09" L/999+ > L/240 min

DL = 0.02"

L = 0.00" L/999+ > L/360 min

4x10 DF #2

**Description - Roof Framing - H3-18 - Header**



Uniform 1 = 0.34 klf (0.0'-5.0')

Controlling Load Combination/ Cd

$V = (D + S) \quad Cd=1.15$

$M = (D + S) \quad Cd=1.15$

$\Delta = (D + S)$

V = 0.85k	Vall = 4.47k	Ratio = 0.19
M = 1.07k-ft	Mall = 5.17k-ft	Ratio = 0.21

Deflection


TL = 0.01" L/999+ > L/240 min

DL = 0.00"

L = 0.00" L/999+ > L/360 min

4x10 DF #2

**Description - Roof Framing - H3-19 - Header**



Uniform 1 = 0.34 klf (0.0'-1.0')

Uniform 2 = 0.26 klf (1.0'-6.0')

Controlling Load Combination/ Cd

$V = (D + S) \quad Cd=1.15$

$M = (D + S) \quad Cd=1.15$

$\Delta = (D + S)$

V = 0.86k	Vall = 4.47k	Ratio = 0.19
M = 1.19k-ft	Mall = 5.17k-ft	Ratio = 0.23

Deflection


TL = 0.02" L/999+ > L/240 min

DL = 0.01"

L = 0.00" L/999+ > L/360 min

4x10 DF #2

**Description - Roof Framing - H3-20 - Header**



Uniform 1 = 0.67 klf (0.0'-3.0')

Controlling Load Combination/ Cd

$V = (D + S) \quad Cd=1.15$

$M = (D + S) \quad Cd=1.15$

$\Delta = (D + S)$

V = 1.01k	Vall = 4.47k	Ratio = 0.23
M = 0.76k-ft	Mall = 5.17k-ft	Ratio = 0.15

Deflection

TL = 0.00" L/999+ > L/240 min


DL = 0.00"

L = 0.00" L/999+ > L/360 min

4x10 DF #2



Description - Roof Framing - B3-1 - Refer to External Design



Uniform 1 = 0.25 klf (0.0'-8.0')

Controlling Load Combination/ Cd

V = (D + S) Cd=1.15


M = (D + S) Cd=1.15

$\Delta$  = NA

V = 1.01k	Vall = 0 k	Ratio = 0
M = 1.86k-ft	Mall = 0 k-ft	Ratio = 0
Deflection		
TL = NA	L/ NA > L/240 min	
DL = NA		
L = NA	L/ NA > L/360 min	

Refer to External Design

Description - Roof Framing - B3-2 - Refer to External Design



Uniform 1 = 0.39 klf (0.0'-8.0')

Controlling Load Combination/ Cd

V = (D + S) Cd=1.15


M = (D + S) Cd=1.15

$\Delta$  = NA

V = 1.57k	Vall = 0 k	Ratio = 0
M = 2.17k-ft	Mall = 0 k-ft	Ratio = 0
Deflection		
TL = NA	L/ NA > L/240 min	
DL = NA		
L = NA	L/ NA > L/360 min	

Refer to External Design

Description - Roof Framing - B3-3 - Refer to External Design



Controlling Load Combination/ Cd

V = NA Cd=1

M = NA Cd=1


$\Delta$  = NA

V = 0.00k	Vall = 0 k	Ratio = 0
M = 0.00k-ft	Mall = 0 k-ft	Ratio = 0
Deflection		
TL = NA	L/ NA > L/240 min	
DL = NA		
L = NA	L/ NA > L/360 min	

Refer to External Design



Description - Roof Framing - B3-4 - Flush




Uniform 1 = 0.14 klf (0.0'-6.5')  
Uniform 2 = 0.14 klf (6.5'-14.5')  
Uniform 3 = 0.14 klf (14.5'-17.5')

Controlling Load Combination/ Cd  
V = (D + S) Cd=1.15  
M = (D + S) Cd=1.15  
 $\Delta$  = (D + S)

V = 1.23k	Vall = 9.08k	Ratio = 0.14
M = 5.39k-ft	Mall = 20.50k-ft	Ratio = 0.26
Deflection		
TL = 0.32" L/657 > L/240 min		
DL = 0.09"		
L = 0.00" L/999+ > L/360 min		

(2)1-3/4x11-7/8 LVL

Description - Roof Framing - B3-5 - Refer to External Design




Uniform 1 = 0.05 klf (0.0'-19.0')

Controlling Load Combination/ Cd  
V = (D + S) Cd=1.15  
M = D Cd=0.9  
 $\Delta$  = NA

V = 0.49k	Vall = 0 k	Ratio = 0
M = 3.51k-ft	Mall = 0 k-ft	Ratio = 0
Deflection		
TL = NA L/NA > L/240 min		
DL = NA		
L = NA L/NA > L/360 min		

Refer to External Design

Description - Roof Framing - B3-6 - Refer to External Design




Controlling Load Combination/ Cd  
V = NA Cd=1  
M = NA Cd=1  
 $\Delta$  = NA

V = 0.00k	Vall = 0 k	Ratio = 0
M = 0.00k-ft	Mall = 0 k-ft	Ratio = 0
Deflection		
TL = NA L/NA > L/240 min		
DL = NA		
L = NA L/NA > L/360 min		

Refer to External Design

Description - Roof Framing - B3-7 - Refer to External Design




Controlling Load Combination/ Cd  
V = NA Cd=1  
M = NA Cd=1  
 $\Delta$  = NA

V = 0.00k	Vall = 0 k	Ratio = 0
M = 0.00k-ft	Mall = 0 k-ft	Ratio = 0
Deflection		
TL = NA L/NA > L/240 min		
DL = NA		
L = NA L/NA > L/360 min		

Refer to External Design



**Description - Roof Framing - B3-8 - Refer to External Design**



Uniform 1 = 0.15 klf (0.0'-19.4')

Controlling Load Combination/ Cd

$V = (D + S) \quad Cd=1.15$

$M = (D + S) \quad Cd=1.15$

$\Delta = NA$

V = 1.48k	Vall = 0 k	Ratio = 0
M = 7.22k-ft	Mall = 0 k-ft	Ratio = 0

Deflection


TL = NA L/NA > L/240 min

DL = NA

L = NA L/NA > L/360 min

Refer to External Design

**Description - Roof Framing - B3-9 - Flush**



Uniform 1 = 0.07 klf (0.0'-12.5')

Controlling Load Combination/ Cd

$V = (D + S) \quad Cd=1.15$

$M = (D + S) \quad Cd=1.15$

$\Delta = (D + S)$

V = 0.41k	Vall = 4.54k	Ratio = 0.09
M = 1.29k-ft	Mall = 10.25k-ft	Ratio = 0.13

Deflection


TL = 0.08" L/999+ > L/240 min

DL = 0.02"

L = 0.00" L/999+ > L/360 min

1-3/4x11-7/8 LVL

**Description - Roof Framing - B3-10 - Flush**



Uniform 1 = 0.05 klf (0.0'-19.0')

Uniform 2 = 0.05 klf (19.0'-27.7')

Controlling Load Combination/ Cd

$V = (D + S) \quad Cd=1.15$

$M = (D + S) \quad Cd=1.15$

$\Delta = (D + S)$

V = 0.73k	Vall = 13.62k	Ratio = 0.05
M = 5.05k-ft	Mall = 30.74k-ft	Ratio = 0.16

Deflection


TL = 0.51" L/660 > L/240 min

DL = 0.14"

L = 0.00" L/999+ > L/360 min

(3)1-3/4x11-7/8 LVL

Description - Roof Framing - B3-19 - Flush




Uniform 1 = 0.05 klf (0.0'-19.0')      P1 = 0.17 K (0.4')  
P2 = 0.65 K (4.6')

Controlling Load Combination/ Cd  
V = (D + S) Cd=1.15  
M = (D + S) Cd=1.15  
 $\Delta = (D + S)$

V = 1.09k	Vall = 4.54k	Ratio = 0.24
M = 3.89k-ft	Mall = 10.25k-ft	Ratio = 0.38
Deflection		
TL = 0.54" L/420 > L/240 min		
DL = 0.15"		
L = 0.00" L/999+ > L/360 min		

1-3/4x11-7/8 LVL

Description - Roof Framing - B3-20 - Flush



Uniform 1 = 0.05 klf (0.0'-19.0')      P1 = 0.17 K (0.4')  
P2 = 0.65 K (4.6')

Controlling Load Combination/ Cd  
V = (D + S) Cd=1.15  
M = (D + S) Cd=1.15  
 $\Delta = (D + S)$

V = 1.09k	Vall = 4.54k	Ratio = 0.24
M = 3.89k-ft	Mall = 10.25k-ft	Ratio = 0.38
Deflection		
TL = 0.54" L/420 > L/240 min		
DL = 0.15"		
L = 0.00" L/999+ > L/360 min		

1-3/4x11-7/8 LVL

Description - Roof Framing - B3-21 - Flush




Uniform 1 = 0.08 klf (0.0'-4.0')

Controlling Load Combination/ Cd  
V = (D + S) Cd=1.15  
M = (D + S) Cd=1.15  
 $\Delta = (D + S)$

V = 0.17k	Vall = 4.54k	Ratio = 0.04
M = 0.17k-ft	Mall = 10.25k-ft	Ratio = 0.02
Deflection		
TL = 0.00" L/999+ > L/240 min		
DL = 0.00"		
L = 0.00" L/999+ > L/360 min		

1-3/4x11-7/8 LVL

Description - Roof Framing - B3-22 - Flush




Uniform 1 = 0.32 klf (0.0'-4.0')

Controlling Load Combination/ Cd  
V = (D + S) Cd=1.15  
M = (D + S) Cd=1.15  
 $\Delta = (D + S)$

V = 0.65k	Vall = 4.54k	Ratio = 0.14
M = 0.65k-ft	Mall = 10.25k-ft	Ratio = 0.06
Deflection		
TL = 0.00" L/999+ > L/240 min		
DL = 0.00"		
L = 0.00" L/999+ > L/360 min		

1-3/4x11-7/8 LVL

Description - Roof Framing - B3-23 - Flush



Uniform 1 = 0.05 klf (0.0'-19.3')  
P1 = 0.24 K (2.5')  
P2 = 0.59 K (6.6')


Controlling Load Combination/ Cd  
V = (D + S) Cd=1.15  
M = (D + S) Cd=1.15  
 $\Delta$  = (D + S)

V = 1.04k	Vall = 9.08k	Ratio = 0.11
M = 4.88k-ft	Mall = 20.50k-ft	Ratio = 0.24

Deflection  
TL = 0.35" L/657 > L/240 min  
DL = 0.10"  
L = 0.00" L/999+ > L/360 min

(2)1-3/4x11-7/8 LVL

Description - Roof Framing - B3-24 - Flush



Uniform 1 = 0.05 klf (0.0'-19.3')  
P1 = 0.24 K (2.5')  
P2 = 0.59 K (6.6')

Controlling Load Combination/ Cd  
V = (D + S) Cd=1.15  
M = (D + S) Cd=1.15  
 $\Delta$  = (D + S)

V = 1.04k	Vall = 9.08k	Ratio = 0.11
M = 4.88k-ft	Mall = 20.50k-ft	Ratio = 0.24

Deflection  
TL = 0.35" L/657 > L/240 min  
DL = 0.10"  
L = 0.00" L/999+ > L/360 min

(2)1-3/4x11-7/8 LVL

Description - Roof Framing - B3-25 - Flush



Uniform 1 = 0.12 klf (0.0'-4.0')


Controlling Load Combination/ Cd  
V = (D + S) Cd=1.15  
M = (D + S) Cd=1.15  
 $\Delta$  = (D + S)

V = 0.24k	Vall = 9.08k	Ratio = 0.03
M = 0.24k-ft	Mall = 20.50k-ft	Ratio = 0.01

Deflection  
TL = 0.00" L/999+ > L/240 min  
DL = 0.00"  
L = 0.00" L/999+ > L/360 min

(2)1-3/4x11-7/8 LVL

Description - Roof Framing - B3-26 - Flush



Uniform 1 = 0.29 klf (0.0'-4.0')

Controlling Load Combination/ Cd  
V = (D + S) Cd=1.15  
M = (D + S) Cd=1.15  
 $\Delta$  = (D + S)


V = 0.59k	Vall = 9.08k	Ratio = 0.06
M = 0.59k-ft	Mall = 20.50k-ft	Ratio = 0.03

Deflection  
TL = 0.00" L/999+ > L/240 min  
DL = 0.00"  
L = 0.00" L/999+ > L/360 min

(2)1-3/4x11-7/8 LVL



Description - Upper Floor Framing - H2-1 - Header



Uniform 1 = 0.07 klf (0.0'-6.0')

Controlling Load Combination/ Cd

$V = (D + S) \quad Cd=1.15$


$M = (D + S) \quad Cd=1.15$

$\Delta = (D + S)$

V = 0.21k	Vall = 4.54k	Ratio = 0.05
M = 0.32k-ft	Mall = 10.25k-ft	Ratio = 0.03
Deflection		
TL = 0.00" L/999+ > L/240 min		
DL = 0.00"		
L = 0.00" L/999+ > L/360 min		

1-3/4x11-7/8 LVL

Description - Upper Floor Framing - H2-2 - Header



Uniform 1 = 0.07 klf (0.0'-6.0')

Controlling Load Combination/ Cd

$V = (D + S) \quad Cd=1.15$


$M = (D + S) \quad Cd=1.15$

$\Delta = (D + S)$

V = 0.21k	Vall = 4.54k	Ratio = 0.05
M = 0.31k-ft	Mall = 10.25k-ft	Ratio = 0.03
Deflection		
TL = 0.00" L/999+ > L/240 min		
DL = 0.00"		
L = 0.00" L/999+ > L/360 min		

1-3/4x11-7/8 LVL

Description - Upper Floor Framing - H2-3 - Header



Uniform 1 = 0.57 klf (0.0'-1.6')

Uniform 2 = 0.57 klf (1.6'-3.3')

Uniform 3 = 0.57 klf (3.3'-5.0')

Controlling Load Combination/ Cd

$V = (D + L) \quad Cd=1$


$M = (D + L) \quad Cd=1$

$\Delta = (D + L)$

V = 1.30k	Vall = 9.28k	Ratio = 0.14
M = 1.62k-ft	Mall = 26.25k-ft	Ratio = 0.06
Deflection		
TL = 0.00" L/999+ > L/240 min		
DL = 0.00"		
L = 0.00" L/999+ > L/360 min		

3-1/2x15 GLB

Description - Upper Floor Framing - H2-4 - Header



Uniform 1 = 0.57 klf (0.0'-5.0')

Controlling Load Combination/ Cd

$V = (D + L) \quad Cd=1$

$M = (D + L) \quad Cd=1$


$\Delta = (D + L)$

V = 1.29k	Vall = 9.28k	Ratio = 0.14
M = 1.62k-ft	Mall = 26.25k-ft	Ratio = 0.06
Deflection		
TL = 0.00" L/999+ > L/240 min		
DL = 0.00"		
L = 0.00" L/999+ > L/360 min		

3-1/2x15 GLB



Description - Upper Floor Framing - H2-5 - Header



Uniform 1 = 0.71 klf (0.0'-4.0')

Controlling Load Combination/ Cd

$V = (D + L) \quad Cd=1$


$M = (D + L) \quad Cd=1$

$\Delta = (D + 0.75 * (L + S))$

V = 1.20k	Vall = 9.28k	Ratio = 0.13
M = 1.20k-ft	Mall = 26.25k-ft	Ratio = 0.05
Deflection		
TL = 0.00" L/999+ > L/240 min		
DL = 0.00"		
L = 0.00" L/999+ > L/360 min		

3-1/2x15 GLB

Description - Upper Floor Framing - H2-6 - Header



Uniform 1 = 0.71 klf (0.0'-4.0')

Controlling Load Combination/ Cd

$V = (D + L) \quad Cd=1$


$M = (D + L) \quad Cd=1$

$\Delta = (D + 0.75 * (L + S))$

V = 1.20k	Vall = 9.28k	Ratio = 0.13
M = 1.20k-ft	Mall = 26.25k-ft	Ratio = 0.05
Deflection		
TL = 0.00" L/999+ > L/240 min		
DL = 0.00"		
L = 0.00" L/999+ > L/360 min		

3-1/2x15 GLB

Description - Upper Floor Framing - H2-7 - Header



Uniform 1 = 1.12 klf (0.0'-0.6')

Uniform 2 = 0.10 klf (0.0'-0.6')

Uniform 3 = 0.26 klf (0.6'-3.6')

Uniform 4 = 0.26 klf (3.6'-4.0')

Controlling Load Combination/ Cd

$V = (D + 0.75 * (L + S)) \quad Cd=1.15$

$M = (D + S) \quad Cd=1.15$


$\Delta = (D + S)$

V = 0.89k	Vall = 10.67k	Ratio = 0.08
M = 0.57k-ft	Mall = 30.19k-ft	Ratio = 0.02
Deflection		
TL = 0.00" L/999+ > L/240 min		
DL = 0.00"		
L = 0.00" L/999+ > L/360 min		

3-1/2x15 GLB



Description - Upper Floor Framing - H2-8 - Header




Uniform 1 = 0.26 klf (0.0'-2.9')  
Uniform 2 = 0.26 klf (2.9'-3.9')

Controlling Load Combination/ Cd  
V = (D + S) Cd=1.15  
M = (D + S) Cd=1.15  
 $\Delta$  = (D + S)

V = 0.51k	Vall = 10.67k	Ratio = 0.05
M = 0.51k-ft	Mall = 30.19k-ft	Ratio = 0.02
Deflection		
TL = 0.00" L/999+ > L/240 min		
DL = 0.00"		
L = 0.00" L/999+ > L/360 min		

3-1/2x15 GLB

Description - Upper Floor Framing - H2-9 - Header



Uniform 1 = 0.70 klf (0.0'-1.0')      P1 = 2.00 K (1.7')  
Uniform 2 = 0.84 klf (1.0'-1.7')  
Uniform 3 = 0.55 klf (1.7'-2.7')  
Uniform 4 = 0.33 klf (2.7'-16.3')

Controlling Load Combination/ Cd  
V = (D + S) Cd=1.15  
M = (D + S) Cd=1.15  
 $\Delta$  = NA

V = 4.82k	Vall = 0 k	Ratio = 0
M = 12.93k-ft	Mall = 0 k-ft	Ratio = 0
Deflection		
TL = NA L/NA > L/240 min		
DL = NA		
L = NA L/NA > L/360 min		

Refer to External Design

Description - Upper Floor Framing - H2-10 - Header



Uniform 1 = 0.19 klf (0.0'-8.3')


Controlling Load Combination/ Cd  
V = (D + S) Cd=1.15  
M = (D + S) Cd=1.15  
 $\Delta$  = (D + S)

V = 0.80k	Vall = 8.24k	Ratio = 0.10
M = 1.65k-ft	Mall = 10.17k-ft	Ratio = 0.16
Deflection		
TL = 0.02" L/999+ > L/240 min		
DL = 0.01"		
L = 0.00" L/999+ > L/360 min		

6x12 DF #2



**Description - Upper Floor Framing - H2-11 - Header**




Uniform 1 = 0.32 klf (0.0'-0.5')  
Uniform 2 = 0.32 klf (2.2'-6.0')

Controlling Load Combination/ Cd  
V = (D + S) Cd=1.15  
M = (D + S) Cd=1.15  
 $\Delta$  = (D + S)

V = 0.85k	Vall = 4.54k	Ratio = 0.19
M = 1.12k-ft	Mall = 10.25k-ft	Ratio = 0.11
Deflection		
TL = 0.02" L/999+ > L/240 min		
DL = 0.00"		
L = 0.00" L/999+ > L/360 min		

1-3/4x11-7/8 LVL

**Description - Upper Floor Framing - H2-12 - Header**




Uniform 1 = 0.32 klf (0.0'-7.0')

Controlling Load Combination/ Cd  
V = (D + S) Cd=1.15  
M = (D + S) Cd=1.15  
 $\Delta$  = (D + S)

V = 1.13k	Vall = 4.54k	Ratio = 0.25
M = 1.98k-ft	Mall = 10.25k-ft	Ratio = 0.19
Deflection		
TL = 0.04" L/999+ > L/240 min		
DL = 0.01"		
L = 0.00" L/999+ > L/360 min		

1-3/4x11-7/8 LVL

**Description - Upper Floor Framing - H2-13 - Header**




Uniform 1 = 0.32 klf (0.0'-6.0')

Controlling Load Combination/ Cd  
V = (D + S) Cd=1.15  
M = (D + S) Cd=1.15  
 $\Delta$  = (D + S)

V = 0.97k	Vall = 4.54k	Ratio = 0.21
M = 1.45k-ft	Mall = 10.25k-ft	Ratio = 0.14
Deflection		
TL = 0.02" L/999+ > L/240 min		
DL = 0.01"		
L = 0.00" L/999+ > L/360 min		

1-3/4x11-7/8 LVL

**Description - Upper Floor Framing - H2-14 - Header**




Uniform 1 = 0.11 klf (0.0'-12.0')

Controlling Load Combination/ Cd  
V = (D + L) Cd=1  
M = (D + L) Cd=1  
 $\Delta$  = (D + L)

V = 0.66k	Vall = 9.28k	Ratio = 0.07
M = 1.98k-ft	Mall = 26.25k-ft	Ratio = 0.08
Deflection		
TL = 0.03" L/999+ > L/240 min		
DL = 0.01"		
L = 0.02" L/999+ > L/360 min		

3-1/2x15 GLB

**Description - Upper Floor Framing - H2-15 - Header**




Uniform 1 = 1.04 klf (0.0'-3.1')      P1 = 1.23 K (3.2')  
 Uniform 2 = 0.82 klf (3.1'-7.1')      P2 = 1.12 K (7.0')  
 Uniform 3 = 1.04 klf (7.1'-8.0')

Controlling Load Combination/ Cd  
 $V = (D + 0.75 * (L + S))$  Cd=1.15  
 $M = (D + 0.75 * (L + S))$  Cd=1.15  
 $\Delta = (D + 0.75 * (L + S))$

V = 4.24k	Vall = 10.67k	Ratio = 0.40
M = 8.18k-ft	Mall = 30.19k-ft	Ratio = 0.27
Deflection		
TL = 0.05"	L/999+ > L/240 min	
DL = 0.02"		
L = 0.02"	L/999+ > L/360 min	

3-1/2x15 GLB

**Description - Upper Floor Framing - H2-16 - Header**




Uniform 1 = 0.34 klf (0.0'-3.0')

Controlling Load Combination/ Cd  
 $V = (D + L)$  Cd=1  
 $M = (D + L)$  Cd=1  
 $\Delta = (D + L)$

V = 0.51k	Vall = 9.28k	Ratio = 0.05
M = 0.38k-ft	Mall = 26.25k-ft	Ratio = 0.01
Deflection		
TL = 0.00"	L/999+ > L/240 min	
DL = 0.00"		
L = 0.00"	L/999+ > L/360 min	

3-1/2x15 GLB

**Description - Upper Floor Framing - H2-17 - Header**




Uniform 1 = 0.31 klf (0.0'-0.6')  
 Uniform 2 = 0.12 klf (0.6'-3.0')

Controlling Load Combination/ Cd  
 $V = (D + 0.75 * (L + S))$  Cd=1.15  
 $M = (D + S)$  Cd=1.15  
 $\Delta = (D + S)$

V = 0.24k	Vall = 10.67k	Ratio = 0.02
M = 0.14k-ft	Mall = 30.19k-ft	Ratio = 0.00
Deflection		
TL = 0.00"	L/999+ > L/240 min	
DL = 0.00"		
L = 0.00"	L/999+ > L/360 min	

3-1/2x15 GLB

**Description - Upper Floor Framing - H2-18 - Header**




Uniform 1 = 0.25 klf (0.0'-3.0')

Controlling Load Combination/ Cd  
 $V = (D + S)$  Cd=1.15  
 $M = (D + S)$  Cd=1.15  
 $\Delta = (D + S)$

V = 0.37k	Vall = 10.67k	Ratio = 0.03
M = 0.28k-ft	Mall = 30.19k-ft	Ratio = 0.01
Deflection		
TL = 0.00"	L/999+ > L/240 min	
DL = 0.00"		
L = 0.00"	L/999+ > L/360 min	

3-1/2x15 GLB

**Description - Upper Floor Framing - B2-1 - Flush**



Uniform 1 = 0.16 klf (0.0'-19.4')

Controlling Load Combination/ Cd

V = (D + S) Cd=1.15

M = (D + S) Cd=1.15

Δ = NA

V = 1.52k	Vall = 0 k	Ratio = 0
-----------	------------	-----------

M = 7.40k-ft	Mall = 0 k-ft	Ratio = 0
--------------	---------------	-----------

Deflection


TL = NA L/ NA > L/240 min

DL = NA

L = NA L/ NA > L/360 min

Refer to External Design

**Description - Upper Floor Framing - B2-2 - Flush**



Uniform 1 = 0.07 klf (0.0'-12.5')

Controlling Load Combination/ Cd

V = (D + S) Cd=1.15

M = (D + S) Cd=1.15

Δ = (D + S)

V = 0.44k	Vall = 4.54k	Ratio = 0.10
-----------	--------------	--------------

M = 1.38k-ft	Mall = 10.25k-ft	Ratio = 0.13
--------------	------------------	--------------

Deflection


TL = 0.08" L/999+ > L/240 min

DL = 0.02"

L = 0.00" L/999+ > L/360 min

1-3/4x11-7/8 LVL

**Description - Upper Floor Framing - B2-3 - Flush**



Uniform 1 = 0.19 klf (0.0'-29.1')

Controlling Load Combination/ Cd

V = (D + S) Cd= NA

M = (D + S) Cd= NA

Δ = (D + S)

V = 2.82k	Vall = 56.40k	Ratio = 0.05
-----------	---------------	--------------

M = 20.50k-ft	Mall = 96.80k-ft	Ratio = 0.21
---------------	------------------	--------------

Deflection


TL = 0.63" L/555 > L/240 min

DL = 0.18"

L = 0.00" L/999+ > L/360 min

W10x33 Steel

**Description - Upper Floor Framing - B2-4 - Flush**



Uniform 1 = 0.32 klf (0.0'-5.0')

Controlling Load Combination/ Cd

V = (D + S) Cd=1.15

M = D Cd=0.9

Δ = NA

V = 0.81k	Vall = 0 k	Ratio = 0
-----------	------------	-----------

M = 0.28k-ft	Mall = 0 k-ft	Ratio = 0
--------------	---------------	-----------

Deflection


TL = NA L/ NA > L/240 min

DL = NA

L = NA L/ NA > L/360 min

Refer to External Design

Description - Upper Floor Framing - B2-5 - Refer to External Design




Controlling Load Combination/ Cd  
V = NA Cd=1  
M = NA Cd=1  
 $\Delta$  = NA

V = 0.00k	Vall = 0 k	Ratio = 0
M = 0.00k-ft	Mall = 0 k-ft	Ratio = 0
Deflection		
TL = NA	L/ NA > L/240 min	
DL = NA		
L = NA	L/ NA > L/360 min	

Refer to External Design

Description - Upper Floor Framing - B2-6 - Flush




Controlling Load Combination/ Cd  
V = NA Cd=1  
M = NA Cd=1  
 $\Delta$  = NA

V = 0.00k	Vall = 0 k	Ratio = 0
M = 0.00k-ft	Mall = 0 k-ft	Ratio = 0
Deflection		
TL = NA	L/ NA > L/240 min	
DL = NA		
L = NA	L/ NA > L/360 min	

Refer to External Design

Description - Upper Floor Framing - B2-7 - Flush



Controlling Load Combination/ Cd  
V = (D + L) Cd=1  
M = (D + L) Cd=1  
 $\Delta$  = (D + 0.75 \* (L + S))


V = 2.41k	Vall = 11.13k	Ratio = 0.22
M = 2.48k-ft	Mall = 37.80k-ft	Ratio = 0.07
Deflection		
TL = 0.00"	L/999+ > L/240 min	
DL = 0.00"		
L = 0.00"	L/999+ > L/360 min	

- Uniform 1 = 1.09 klf (0.0'-1.0')      P1 = 0.76 K (1.0')
- Uniform 2 = 0.96 klf (1.0'-1.7')      P2 = 0.76 K (2.3')
- Uniform 3 = 1.56 klf (1.7'-2.3')
- Uniform 4 = 1.09 klf (2.3'-4.0')

3-1/2x18 GLB



**Description - Upper Floor Framing - B2-8 - Flush**




- Uniform 1 = 1.05 klf (0.0'-3.0')      P1 = 1.18 K (4.4')
- Uniform 2 = 1.18 klf (3.0'-3.6')      P2 = 2.49 K (10.4')
- Uniform 3 = 1.11 klf (3.6'-4.0')      P3 = 0.77 K (3.7')
- Uniform 4 = 1.25 klf (4.0'-4.6')
- Uniform 5 = 0.64 klf (4.6'-10.4')
- Uniform 6 = 1.03 klf (10.4'-10.6')
- Uniform 7 = 0.54 klf (10.6'-18.3')

Controlling Load Combination/ Cd  
 $V = (D + 0.75 * (L + S))$  Cd=1.15  
 $M = (D + 0.75 * (L + S))$  Cd=1.15  
 $\Delta = NA$

V = 8.44k	Vall = 0 k	Ratio = 0
M = 34.66k-ft	Mall = 0 k-ft	Ratio = 0
Deflection		
TL = NA	L/ NA > L/240 min	
DL = NA		
L = NA	L/ NA > L/360 min	

Refer to External Design

**Description - Upper Floor Framing - B2-9 - Flush**




- Uniform 1 = 0.19 klf (0.0'-8.1')

Controlling Load Combination/ Cd  
 $V = (D + L)$  Cd=1  
 $M = (D + L)$  Cd=1  
 $\Delta = (D + 0.75 * (L + S))$

V = 0.67k	Vall = 11.13k	Ratio = 0.06
M = 1.34k-ft	Mall = 37.80k-ft	Ratio = 0.04
Deflection		
TL = 0.01"	L/999+ > L/240 min	
DL = 0.00"		
L = 0.00"	L/999+ > L/360 min	

3-1/2x18 GLB

**Description - Upper Floor Framing - B2-10 - Flush**




- Uniform 1 = 0.66 klf (0.0'-0.9')
- Uniform 2 = 0.28 klf (0.9'-8.9')
- Uniform 3 = 0.66 klf (8.9'-9.7')

Controlling Load Combination/ Cd  
 $V = (D + L)$  Cd=1  
 $M = (D + L)$  Cd=1  
 $\Delta = (D + L)$

V = 1.69k	Vall = 11.13k	Ratio = 0.15
M = 3.42k-ft	Mall = 37.80k-ft	Ratio = 0.09
Deflection		
TL = 0.02"	L/999+ > L/240 min	
DL = 0.00"		
L = 0.01"	L/999+ > L/360 min	

3-1/2x18 GLB

**Description - Upper Floor Framing - B2-11 - Flush**



Uniform 1 = 1.06 klf (0.0'-3.7')      P1 = 1.02 K (0.7')  
 Uniform 2 = 1.64 klf (3.7'-7.7')      P2 = 1.49 K (3.7')  
 Uniform 3 = 1.06 klf (7.7'-9.7')      P3 = 0.61 K (7.6')

Controlling Load Combination/ Cd

$V = (D + L) \quad Cd=1$

$M = (D + L) \quad Cd=1$

$\Delta = (D + 0.75 * (L + S))$

V = 6.10k      Vall = 11.13k      Ratio = 0.55

M = 15.23k-ft      Mall = 37.80k-ft      Ratio = 0.40

Deflection


TL = 0.09" L/999+ > L/240 min

DL = 0.03"

L = 0.05" L/999+ > L/360 min

3-1/2x18 GLB

**Description - Upper Floor Framing - B2-12 - Flush**



P1 = 1.69 K (3.0')

Controlling Load Combination/ Cd

$V = (D + L) \quad Cd=1$

$M = (D + L) \quad Cd=1$

$\Delta = (D + L)$

V = 1.39k      Vall = 11.13k      Ratio = 0.12

M = 4.16k-ft      Mall = 37.80k-ft      Ratio = 0.11

Deflection


TL = 0.07" L/999+ > L/240 min

DL = 0.02"

L = 0.05" L/999+ > L/360 min

3-1/2x18 GLB

**Description - Upper Floor Framing - B2-13 - Flush**



P1 = 1.65 K (3.0')

Controlling Load Combination/ Cd

$V = (D + L) \quad Cd=1$

$M = (D + L) \quad Cd=1$

$\Delta = NA$

V = 1.04k      Vall = 0 k      Ratio = 0

M = 1.85k-ft      Mall = 0 k-ft      Ratio = 0

Deflection


TL = NA L/ NA > L/240 min

DL = NA

L = NA L/ NA > L/360 min

Refer to External Design

**Description - Upper Floor Framing - B2-14 - Flush**



P1 = 0.56 K (3.0')

Controlling Load Combination/ Cd

$V = (D + S) \quad Cd=1.15$

$M = (D + S) \quad Cd=1.15$

$\Delta = (D + S)$

V = 0.32k      Vall = 12.80k      Ratio = 0.02

M = 0.96k-ft      Mall = 43.47k-ft      Ratio = 0.02

Deflection

TL = 0.00" L/999+ > L/240 min


DL = 0.00"

L = 0.00" L/999+ > L/360 min

3-1/2x18 GLB



**Description - Upper Floor Framing - B2-15 - Flush**




Uniform 1 = 0.34 klf (0.0'-2.1')      P1 = 8.11 K (2.1')  
Uniform 2 = 0.32 klf (2.1'-17.1')

Controlling Load Combination/ Cd  
V = (D + 0.75 \* (L + S)) Cd=1.15  
M = (D + 0.75 \* (L + S)) Cd=1.15  
Δ = NA

V = 8.13k	Vall = 0 k	Ratio = 0
M = 18.07k-ft	Mall = 0 k-ft	Ratio = 0
Deflection		
TL = NA	L/ NA > L/240 min	
DL = NA		
L = NA	L/ NA > L/360 min	

Refer to External Design

**Description - Upper Floor Framing - B2-17 - Flush**




Uniform 1 = 0.00 klf (0.0'-1.4')  
Uniform 2 = 0.98 klf (1.4'-16.0')

Controlling Load Combination/ Cd  
V = (D + L) Cd=1  
M = (D + L) Cd=1  
Δ = NA

V = 5.75k	Vall = 0 k	Ratio = 0
M = 19.40k-ft	Mall = 0 k-ft	Ratio = 0
Deflection		
TL = NA	L/ NA > L/240 min	
DL = NA		
L = NA	L/ NA > L/360 min	

Refer to External Design

**Description - Upper Floor Framing - B2-18 - Flush**




Uniform 1 = 0.35 klf (0.0'-8.4')      P1 = 0.07 K (8.4')  
Uniform 2 = 0.28 klf (8.4'-10.4')      P2 = 0.07 K (10.4')  
Uniform 3 = 0.35 klf (10.4'-14.1')      P3 = 13.00 K (14.1')  
Uniform 4 = 0.18 klf (14.1'-22.0')

Controlling Load Combination/ Cd  
V = (D + S) Cd=1.15  
M = (D + 0.75 \* (L + S)) Cd=1.15  
Δ = NA

V = 9.34k	Vall = 0 k	Ratio = 0
M = 67.95k-ft	Mall = 0 k-ft	Ratio = 0
Deflection		
TL = NA	L/ NA > L/240 min	
DL = NA		
L = NA	L/ NA > L/360 min	

Refer to External Design

**Description - Upper Floor Framing - B2-19 - Flush**



Uniform 1 = 0.18 klf (0.3'-22.3')

Controlling Load Combination/ Cd

$V = (D + S) \quad Cd=1.15$

$M = (D + S) \quad Cd=1.15$

$\Delta = NA$

V = 1.99k	Vall = 0 k	Ratio = 0
M = 7.34k-ft	Mall = 0 k-ft	Ratio = 0

Deflection


TL = NA L/ NA > L/240 min

DL = NA

L = NA L/ NA > L/360 min

Refer to External Design

**Description - Upper Floor Framing - B2-20 - Flush**



Uniform 1 = 0.73 klf (0.0'-0.9')

Uniform 2 = 0.54 klf (0.9'-3.0')

Uniform 3 = 0.67 klf (3.0'-3.9')

Controlling Load Combination/ Cd

$V = (D + 0.75 * (L + S)) \quad Cd=1.15$

$M = (D + 0.75 * (L + S)) \quad Cd=1.15$

$\Delta = (D + 0.75 * (L + S))$

V = 1.06k	Vall = 12.80k	Ratio = 0.08
M = 0.96k-ft	Mall = 43.47k-ft	Ratio = 0.02

Deflection


TL = 0.00" L/999+ > L/240 min

DL = 0.00"

L = 0.00" L/999+ > L/360 min

3-1/2x18 GLB

**Description - Upper Floor Framing - B2-23 - Flush**



Uniform 1 = 0.10 klf (6.8'-13.9')

P1 = 1.20 K (6.8')

Controlling Load Combination/ Cd

$V = (D + L) \quad Cd=1$

$M = (D + 0.75 * (L + S)) \quad Cd=1.15$

$\Delta = NA$

V = 0.91k	Vall = 0 k	Ratio = 0
M = 4.76k-ft	Mall = 0 k-ft	Ratio = 0

Deflection

TL = NA L/ NA > L/240 min


DL = NA

L = NA L/ NA > L/360 min

Refer to External Design



**Description - Upper Floor Framing - B2-24 - Flush**



- Uniform 1 = 0.98 klf (0.0'-0.2')
- Uniform 2 = 0.64 klf (0.2'-2.0')
- Uniform 3 = 0.64 klf (2.0'-3.4')
- Uniform 4 = 0.64 klf (3.4'-8.2')
- Uniform 5 = 0.98 klf (8.2'-8.7')
- Uniform 6 = 0.64 klf (8.7'-16.7')
- Uniform 7 = 0.98 klf (16.7'-18.0')


- P1 = 1.37 K (8.2')
- P2 = 1.37 K (8.7')
- P3 = 1.37 K (16.7')

Controlling Load Combination/ Cd  
 $V = (D + L)$  Cd=1  
 $M = (D + L)$  Cd=1  
 $\Delta = NA$

V = 6.63k	Vall = 0 k	Ratio = 0
M = 29.77k-ft	Mall = 0 k-ft	Ratio = 0
Deflection		
TL = NA	L/ NA > L/240 min	
DL = NA		
L = NA	L/ NA > L/360 min	

Refer to External Design

**Description - Upper Floor Framing - B2-25 - Flush**




- Uniform 1 = 0.25 klf (0.0'-6.0')

Controlling Load Combination/ Cd  
 $V = (D + S)$  Cd=1.15  
 $M = (D + S)$  Cd=1.15  
 $\Delta = NA$

V = 0.74k	Vall = 0 k	Ratio = 0
M = 0.94k-ft	Mall = 0 k-ft	Ratio = 0
Deflection		
TL = NA	L/ NA > L/240 min	
DL = NA		
L = NA	L/ NA > L/360 min	

Refer to External Design

**Description - Main Floor Framing - H1-1 - Header**



- Uniform 1 = 0.10 klf (0.0'-11.6')
- Uniform 2 = 0.21 klf (11.6'-12.0')

- P1 = 4.34 K (2.9')
- P2 = 4.37 K (8.6')
- P3 = 0.66 K (11.6')


Controlling Load Combination/ Cd  
 $V = (D + L)$  Cd=1  
 $M = (D + L)$  Cd=1  
 $\Delta = (D + L)$

V = 5.46k	Vall = 11.66k	Ratio = 0.47
M = 15.91k-ft	Mall = 26.40k-ft	Ratio = 0.60
Deflection		
TL = 0.29"	L/498 > L/240 min	
DL = 0.11"		
L = 0.19"	L/776 > L/360 min	

5-1/2x12 GLB



**Description - Main Floor Framing - H1-2 - Header**



Uniform 1 = 0.52 klf (0.0'-3.0')

Controlling Load Combination/ Cd

$V = (D + L) \quad Cd=1$


$M = (D + L) \quad Cd=1$

$\Delta = (D + L)$

V = 0.78k	Vall = 3.88k	Ratio = 0.20
M = 0.59k-ft	Mall = 4.49k-ft	Ratio = 0.13
Deflection		
TL = 0.00" L/999+ > L/240 min		
DL = 0.00"		
L = 0.00" L/999+ > L/360 min		

4x10 DF #2

**Description - Main Floor Framing - H1-3 - Header**



Uniform 1 = 0.60 klf (0.0'-2.2')

Uniform 2 = 0.20 klf (2.2'-2.5')

Controlling Load Combination/ Cd

$V = (D + L) \quad Cd=1$


$M = (D + L) \quad Cd=1$

$\Delta = (D + L)$

V = 0.66k	Vall = 3.88k	Ratio = 0.17
M = 0.41k-ft	Mall = 4.49k-ft	Ratio = 0.09
Deflection		
TL = 0.00" L/999+ > L/240 min		
DL = 0.00"		
L = 0.00" L/999+ > L/360 min		

4x10 DF #2

**Description - Main Floor Framing - B1-1 - Refer to External Design**



Uniform 1 = 2.03 klf (0.0'-0.3')

Uniform 2 = 1.70 klf (0.3'-1.5')

Uniform 3 = 0.62 klf (1.5'-6.3')

Uniform 4 = 0.62 klf (6.3'-7.9')

Controlling Load Combination/ Cd

$V = (D + L) \quad Cd=1$

$M = (D + L) \quad Cd=1$


$\Delta = NA$

V = 3.64k	Vall = 0 k	Ratio = 0
M = 5.35k-ft	Mall = 0 k-ft	Ratio = 0
Deflection		
TL = NA L/NA > L/240 min		
DL = NA		
L = NA L/NA > L/360 min		

Refer to External Design



Description - Main Floor Framing - B1-3 - Flush



- Uniform 1 = 0.30 klf (0.0'-2.3')
- Uniform 2 = 0.30 klf (2.3'-17.2')
- Uniform 3 = 0.49 klf (17.2'-17.9')

Controlling Load Combination/ Cd

$V = (D + L) \quad Cd=1$


$M = (D + L) \quad Cd=1$

$\Delta = (D + L)$

V = 2.69k	Vall = 11.85k	Ratio = 0.23
M = 11.88k-ft	Mall = 26.73k-ft	Ratio = 0.44
Deflection		
TL = 0.49" L/436 > L/240 min		
DL = 0.15"		
L = 0.35" L/617 > L/360 min		

(3)1-3/4x11-7/8 LVL

Description - Main Floor Framing - B1-4 - Flush



- Uniform 1 = 0.54 klf (0.0'-14.9')
- Uniform 2 = 0.89 klf (14.9'-15.4')

Controlling Load Combination/ Cd

$V = (D + L) \quad Cd=1$


$M = (D + L) \quad Cd=1$

$\Delta = (D + L)$

V = 4.34k	Vall = 11.85k	Ratio = 0.37
M = 16.07k-ft	Mall = 26.73k-ft	Ratio = 0.60
Deflection		
TL = 0.49" L/375 > L/240 min		
DL = 0.15"		
L = 0.35" L/531 > L/360 min		

(3)1-3/4x11-7/8 LVL

Description - Main Floor Framing - B1-5 - Flush



- Uniform 1 = 0.54 klf (0.0'-7.7')
- Uniform 2 = 0.54 klf (7.7'-14.9')
- Uniform 3 = 0.89 klf (14.9'-15.4')
- Uniform 4 = 0.48 klf (15.4'-15.6')

Controlling Load Combination/ Cd

$V = (D + L) \quad Cd=1$

$M = (D + L) \quad Cd=1$


$\Delta = (D + L)$

V = 4.37k	Vall = 11.85k	Ratio = 0.37
M = 16.46k-ft	Mall = 26.73k-ft	Ratio = 0.62
Deflection		
TL = 0.52" L/362 > L/240 min		
DL = 0.15"		
L = 0.37" L/512 > L/360 min		

(3)1-3/4x11-7/8 LVL



**Description - Main Floor Framing - B1-6 - Flush**



- Uniform 1 = 1.25 klf (0.0'-3.7')      P1 = 0.66 K (7.7')
- Uniform 2 = 1.52 klf (3.7'-4.0')      P2 = 0.66 K (3.7')
- Uniform 3 = 1.52 klf (4.0'-7.7')
- Uniform 4 = 0.74 klf (7.7'-9.5')

Controlling Load Combination/ Cd

$V = (D + L) \quad Cd=1$


$M = (D + L) \quad Cd=1$

$\Delta = (D + L)$

V = 6.18k	Vall = 7.90k	Ratio = 0.78
M = 14.96k-ft	Mall = 17.82k-ft	Ratio = 0.84
Deflection		
TL = 0.26" L/438 > L/240 min		
DL = 0.10"		
L = 0.16" L/696 > L/360 min		

(2)1-3/4x11-7/8 LVL

**Description - Main Floor Framing - B1-7 - Dropped**



- Uniform 1 = 1.27 klf (0.0'-1.6')      P1 = 0.62 K (0.5')
- Uniform 2 = 0.56 klf (1.6'-2.1')
- Uniform 3 = 0.56 klf (2.2'-4.4')
- Uniform 4 = 0.56 klf (4.4'-6.0')

Controlling Load Combination/ Cd

$V = (D + L) \quad Cd=1$


$M = (D + L) \quad Cd=1$

$\Delta = (D + L)$

V = 2.83k	Vall = 3.88k	Ratio = 0.73
M = 3.04k-ft	Mall = 4.49k-ft	Ratio = 0.68
Deflection		
TL = 0.05" L/999+ > L/240 min		
DL = 0.02"		
L = 0.04" L/999+ > L/360 min		

4x10 DF #2

**Description - Main Floor Framing - B1-8 - Dropped**



- Uniform 1 = 0.56 klf (0.0'-0.3')
- Uniform 2 = 0.56 klf (0.3'-2.3')
- Uniform 3 = 0.56 klf (2.3'-3.3')
- Uniform 4 = 0.56 klf (3.3'-6.0')

Controlling Load Combination/ Cd

$V = (D + L) \quad Cd=1$

$M = (D + L) \quad Cd=1$


$\Delta = (D + L)$

V = 1.69k	Vall = 3.88k	Ratio = 0.43
M = 2.53k-ft	Mall = 4.49k-ft	Ratio = 0.56
Deflection		
TL = 0.04" L/999+ > L/240 min		
DL = 0.01"		
L = 0.03" L/999+ > L/360 min		

4x10 DF #2



**Description - Main Floor Framing - B1-9 - Dropped**




Uniform 1 = 1.86 klf (0.0'-3.8')  
Uniform 2 = 0.24 klf (3.8'-4.0')

Controlling Load Combination/ Cd  
V = (D + L) Cd=1  
M = (D + L) Cd=1  
 $\Delta = (D + L)$

V = 3.20k	Vall = 3.88k	Ratio = 0.82
M = 3.19k-ft	Mall = 4.49k-ft	Ratio = 0.71
Deflection		
TL = 0.02" L/999+ > L/240 min		
DL = 0.01"		
L = 0.02" L/999+ > L/360 min		

4x10 DF #2

**Description - Main Floor Framing - B1-10 - Dropped**




Uniform 1 = 0.53 klf (0.0'-1.5')      P1 = 0.38 K (3.2)  
Uniform 2 = 1.50 klf (1.5'-2.1')  
Uniform 3 = 1.50 klf (2.1'-3.2')  
Uniform 4 = 1.43 klf (3.2'-4.4')

Controlling Load Combination/ Cd  
V = (D + L) Cd=1  
M = (D + L) Cd=1  
 $\Delta = (D + L)$

V = 3.06k	Vall = 3.88k	Ratio = 0.79
M = 3.15k-ft	Mall = 4.49k-ft	Ratio = 0.70
Deflection		
TL = 0.03" L/999+ > L/240 min		
DL = 0.01"		
L = 0.02" L/999+ > L/360 min		

4x10 DF #2

**Description - Main Floor Framing - B1-12 - Flush**



Uniform 1 = 0.99 klf (0.0'-0.7')  
Uniform 2 = 0.67 klf (0.7'-4.0')


Controlling Load Combination/ Cd  
V = (D + L) Cd=1  
M = (D + L) Cd=1  
 $\Delta = (D + L)$

V = 1.55k	Vall = 3.95k	Ratio = 0.39
M = 1.39k-ft	Mall = 8.91k-ft	Ratio = 0.16
Deflection		
TL = 0.01" L/999+ > L/240 min		
DL = 0.00"		
L = 0.01" L/999+ > L/360 min		

1-3/4x11-7/8 LVL



**Description - Main Floor Framing - B1-13 - Dropped**




Uniform 1 = 0.66 klf (0.0'-3.8')  
Uniform 2 = 0.40 klf (3.8'-4.0')

Controlling Load Combination/ Cd  
V = (D + L) Cd=1  
M = (D + L) Cd=1  
 $\Delta = (D + L)$

V = 1.33k	Vall = 3.88k	Ratio = 0.34
M = 1.32k-ft	Mall = 4.49k-ft	Ratio = 0.29
Deflection		
TL = 0.01" L/999+ > L/240 min		
DL = 0.00"		
L = 0.01" L/999+ > L/360 min		

4x10 DF #2

**Description - Main Floor Framing - B1-14 - Dropped**




Uniform 1 = 1.82 klf (0.0'-0.5')      P1 = 0.76 K (0.6')  
Uniform 2 = 2.51 klf (0.5'-3.0')

Controlling Load Combination/ Cd  
V = (D + L) Cd=1  
M = (D + L) Cd=1  
 $\Delta = (D + 0.75 * (L + S))$

V = 3.13k	Vall = 3.88k	Ratio = 0.81
M = 2.35k-ft	Mall = 4.49k-ft	Ratio = 0.52
Deflection		
TL = 0.01" L/999+ > L/240 min		
DL = 0.00"		
L = 0.01" L/999+ > L/360 min		

4x10 DF #2

**Description - Main Floor Framing - B1-15 - Dropped**



Uniform 1 = 1.89 klf (0.0'-0.4')      P1 = 0.45 K (0.9')  
Uniform 2 = 1.65 klf (0.4'-2.0')  
Uniform 3 = 1.76 klf (2.0'-2.5')


Controlling Load Combination/ Cd  
V = (D + L) Cd=1  
M = (D + L) Cd=1  
 $\Delta = (D + L)$

V = 2.28k	Vall = 3.88k	Ratio = 0.59
M = 1.41k-ft	Mall = 4.49k-ft	Ratio = 0.31
Deflection		
TL = 0.00" L/999+ > L/240 min		
DL = 0.00"		
L = 0.00" L/999+ > L/360 min		

4x10 DF #2



**Description - Main Floor Framing - B1-16 - Dropped**




Uniform 1 = 2.51 klf (0.0'-2.7')  
Uniform 2 = 0.40 klf (2.7'-2.9')

Controlling Load Combination/ Cd  
V = (D + L) Cd=1  
M = (D + L) Cd=1  
 $\Delta = (D + 0.75 * (L + S))$

V = 2.99k	Vall = 3.88k	Ratio = 0.77
M = 2.18k-ft	Mall = 4.49k-ft	Ratio = 0.49
Deflection		
TL = 0.01" L/999+ > L/240 min		
DL = 0.00"		
L = 0.01" L/999+ > L/360 min		

4x10 DF #2

**Description - Main Floor Framing - B1-17 - Dropped**




Uniform 1 = 1.50 klf (0.0'-1.6')      P1 = 0.42 K (2.3')  
Uniform 2 = 1.50 klf (1.6'-2.3')  
Uniform 3 = 1.86 klf (2.3'-3.7')

Controlling Load Combination/ Cd  
V = (D + L) Cd=1  
M = (D + L) Cd=1  
 $\Delta = (D + L)$

V = 3.01k	Vall = 3.88k	Ratio = 0.77
M = 2.78k-ft	Mall = 4.49k-ft	Ratio = 0.62
Deflection		
TL = 0.02" L/999+ > L/240 min		
DL = 0.01"		
L = 0.01" L/999+ > L/360 min		

4x10 DF #2

**Description - Main Floor Framing - B1-18 - Dropped**



Uniform 1 = 0.66 klf (0.0'-5.8')


Controlling Load Combination/ Cd  
V = (D + L) Cd=1  
M = (D + L) Cd=1  
 $\Delta = (D + L)$

V = 1.89k	Vall = 3.88k	Ratio = 0.49
M = 2.72k-ft	Mall = 4.49k-ft	Ratio = 0.61
Deflection		
TL = 0.04" L/999+ > L/240 min		
DL = 0.01"		
L = 0.03" L/999+ > L/360 min		

4x10 DF #2



**Description - Main Floor Framing - B1-19 - Dropped**




Uniform 1 = 0.66 klf (0.0'-1.6')  
Uniform 2 = 0.66 klf (1.6'-6.0')

Controlling Load Combination/ Cd  
V = (D + L) Cd=1  
M = (D + L) Cd=1  
 $\Delta = (D + L)$

V = 1.98k	Vall = 3.88k	Ratio = 0.51
M = 2.96k-ft	Mall = 4.49k-ft	Ratio = 0.66
Deflection		
TL = 0.05" L/999+ > L/240 min		
DL = 0.01"		
L = 0.04" L/999+ > L/360 min		

4x10 DF #2

**Description - Main Floor Framing - B1-20 - Dropped**




Uniform 1 = 0.66 klf (0.0'-6.0')

Controlling Load Combination/ Cd  
V = (D + L) Cd=1  
M = (D + L) Cd=1  
 $\Delta = (D + L)$

V = 1.99k	Vall = 3.88k	Ratio = 0.51
M = 3.00k-ft	Mall = 4.49k-ft	Ratio = 0.67
Deflection		
TL = 0.05" L/999+ > L/240 min		
DL = 0.01"		
L = 0.04" L/999+ > L/360 min		

4x10 DF #2

**Description - Main Floor Framing - B1-22 - Flush**




Uniform 1 = 0.20 klf (0.0'-6.8') P1 = 1.25 K (6.8')

Controlling Load Combination/ Cd  
V = (D + L) Cd=1  
M = (D + L) Cd=1  
 $\Delta = (D + 0.75 * (L + S))$

V = 1.26k	Vall = 3.95k	Ratio = 0.32
M = 2.45k-ft	Mall = 8.91k-ft	Ratio = 0.28
Deflection		
TL = 0.07" L/999+ > L/240 min		
DL = 0.06"		
L = 0.01" L/999+ > L/360 min		

1-3/4x11-7/8 LVL

**Description - Main Floor Framing - B1-23 - Flush**



P1 = 0.98 K (2.4')


Controlling Load Combination/ Cd  
V = (D + S) Cd=1.15  
M = (D + S) Cd=1.15  
 $\Delta = (D + S)$

V = 0.66k	Vall = 4.54k	Ratio = 0.15
M = 1.58k-ft	Mall = 10.25k-ft	Ratio = 0.15
Deflection		
TL = 0.03" L/999+ > L/240 min		
DL = 0.01"		
L = 0.00" L/999+ > L/360 min		

1-3/4x11-7/8 LVL



Description - Main Floor Framing - B1-24 - Flush



P1 = 0.98 K (2.4')

Controlling Load Combination/ Cd

V = (D + S) Cd=1.15

M = (D + S) Cd=1.15

$\Delta$  = (D + S)

V = 0.66k	Vall = 4.54k	Ratio = 0.15
M = 1.58k-ft	Mall = 10.25k-ft	Ratio = 0.15

Deflection


TL = 0.03" L/999+ > L/240 min

DL = 0.01"

L = 0.00" L/999+ > L/360 min

1-3/4x11-7/8 LVL

Description - Main Floor Framing - B1-25 - Flush



P1 = 0.84 K (2.4')

Controlling Load Combination/ Cd

V = (D + S) Cd=1.15

M = (D + S) Cd=1.15

$\Delta$  = (D + S)

V = 0.62k	Vall = 4.54k	Ratio = 0.14
M = 1.51k-ft	Mall = 10.25k-ft	Ratio = 0.15

Deflection

TL = 0.05" L/999+ > L/240 min

DL = 0.02"

L = 0.00" L/999+ > L/360 min

1-3/4x11-7/8 LVL



### BEAM & HEADER CALCULATIONS


**BEAM DESCRIPTION:** ROOF FRAMING - B3-1 - CANT'D FLUSH BM

**PARAMETERS:**

L = 10.83 FT

W = 0.25 KLF

P = -0.47 K



**ANALYSIS:**

R<sub>MAX</sub> = 1.29 K

V<sub>D</sub> = 0.72 K < V<sub>ALL</sub> = 7.90 K

ADEQUATE

M<sub>MAX</sub> = 2.31 K-FT < M<sub>ALL</sub> = 17.85 K-FT

ADEQUATE

Δ<sub>TL</sub> = 0.03 IN.

L/ 999+ < L/240

ADEQUATE

3-1/2"x11-7/8" LVL


**BEAM DESCRIPTION:** ROOF FRAMING - B3-2 - CANT'D FLUSH BM

**PARAMETERS:**

L = 10.5 FT

W = 0.40 KLF

P = 3.46 K



**ANALYSIS:**

R<sub>MAX</sub> = 8.29 K

V<sub>D</sub> = 4.18 K < V<sub>ALL</sub> = 7.90 K

ADEQUATE

M<sub>MAX</sub> = 11.05 K-FT < M<sub>ALL</sub> = 17.85 K-FT

ADEQUATE

Δ<sub>TL</sub> = 0.18 IN.

L/ 991 < L/240 @ CANT'L

ADEQUATE

3-1/2"x11-7/8" LVL


**BEAM DESCRIPTION:** ROOF FRAMING - B3-3 - CANT'D FLUSH BTM BM

**PARAMETERS:**

L = 22.58 FT

W = 0.05 KLF

P = 1.3 K



**ANALYSIS:**

R<sub>MAX</sub> = 2.93 K

V<sub>D</sub> = 1.59 K < V<sub>ALL</sub> = 13.97 K

ADEQUATE

M<sub>MAX</sub> = 11.22 K-FT < M<sub>ALL</sub> = 36.39 K-FT

ADEQUATE

Δ<sub>TL</sub> = 0.45 IN.

L/ 426 < L/240 @ CANT'L

ADEQUATE

5-1/4"x14" LVL




### BEAM & HEADER CALCULATIONS

**BEAM DESCRIPTION:** ROOF FRAMING - B3-5 - CANT'D FLUSH BM

**PARAMETERS:**

L =  FT  
W =  KLF  
P =  K




**ANALYSIS:**

$R_{MAX} = 4.66$  K       $V_D = 2.98$  K <  $V_{ALL} = 11.85$  K       ADEQUATE  
 $M_{MAX} = 11.64$  K-FT <  $M_{ALL} = 26.78$  K-FT       ADEQUATE  
 $\Delta_{TL} = 0.27$  IN.       $L/358 < L/240$  @ CANT'L       ADEQUATE

**BEAM DESCRIPTION:** ROOF FRAMING - B3-6 - CANT'D FLUSH BM

**PARAMETERS:**

L =  FT  
W =  KLF  
P =  K




**ANALYSIS:**

$R_{MAX} = 3.81$  K       $V_D = 2.03$  K <  $V_{ALL} = 7.90$  K       ADEQUATE  
 $M_{MAX} = 7.88$  K-FT <  $M_{ALL} = 17.85$  K-FT       ADEQUATE  
 $\Delta_{TL} = 0.17$  IN.       $L/556 < L/240$  @ CANT'L       ADEQUATE

**BEAM DESCRIPTION:** ROOF FRAMING - B3-7 - CANT'D FLUSH BM

**PARAMETERS:**

L =  FT  
W =  KLF  
P =  K



**ANALYSIS:**

$R_{MAX} = 1.18$  K       $V_D = 0.61$  K <  $V_{ALL} = 7.90$  K       ADEQUATE  
 $M_{MAX} = 2.19$  K-FT <  $M_{ALL} = 17.85$  K-FT       ADEQUATE  
 $\Delta_{TL} = 0.05$  IN.       $L/999+ < L/240$  @ CANT'L       ADEQUATE




### BEAM & HEADER CALCULATIONS

**BEAM DESCRIPTION:** ROOF FRAMING - B3-8 - CANT'D FLUSH BM

**PARAMETERS:**

L =  FT  
W =  KLF W3=0.03KLF  
P =  K W2=0.15KLF



**ANALYSIS:**


R<sub>MAX</sub> =  K      V<sub>D</sub> =  K < V<sub>ALL</sub> =  K       ADEQUATE  
M<sub>MAX</sub> =  K-FT < M<sub>ALL</sub> =  K-FT       ADEQUATE  
Δ<sub>TL</sub> =  IN.      L/  < L/240 @ CANT'L       ADEQUATE

3-1/2"x11-7/8" LVL

**BEAM DESCRIPTION:** UPPER FLOOR FRAMING - B2-1 - CANT'D FLUSH BM

**PARAMETERS:**

L =  FT  
W =  KLF W2=0.16KLF  
P =  K



**ANALYSIS:**


R<sub>MAX</sub> =  K      V<sub>D</sub> =  K < V<sub>ALL</sub> =  K       ADEQUATE  
M<sub>MAX</sub> =  K-FT < M<sub>ALL</sub> =  K-FT       ADEQUATE  
Δ<sub>TL</sub> =  IN.      L/  < L/240 @ CANT'L       ADEQUATE

5-1/4"x11-7/8" LVL

**BEAM DESCRIPTION:** UPPER FLOOR FRAMING - B2-4 - CANT'D FLUSH BM

**PARAMETERS:**

L =  FT  
W =  KLF  
P =  K



**ANALYSIS:**

R<sub>MAX</sub> =  K      V<sub>D</sub> =  K < V<sub>ALL</sub> =  K       ADEQUATE  
M<sub>MAX</sub> =  K-FT < M<sub>ALL</sub> =  K-FT       ADEQUATE  
Δ<sub>TL</sub> =  IN.      L/  < L/240 @ CANT'L       ADEQUATE

3-1/2"x11-7/8" LVL




**BEAM & HEADER CALCULATIONS**

**BEAM DESCRIPTION:** UPPER FLOOR FRAMING - B2-5 - CANT'D FLUSH BM

**PARAMETERS:**

L = 9 FT  
W = 0.05 KLF W2=0.04KLF  
P = 1.69 K



**ANALYSIS:**


$R_{MAX} = 4.04$  K       $V_D = -$  K <  $V_{ALL} = 7.90$  K       ADEQUATE  
 $M_{MAX} = 8.47$  K-FT <  $M_{ALL} = 17.85$  K-FT       ADEQUATE  
 $\Delta_{TL} = 0.19$  IN.      L/ 516 < L/240 @ CANT'L       ADEQUATE

3-1/2"x11-7/8" LVL

**BEAM DESCRIPTION:** UPPER FLOOR FRAMING - B2-6 - CANT'D FLUSH BM

**PARAMETERS:**

L = 11 FT  
W = 0.05 KLF W2=0.04KLF  
P = 3.4 K



**ANALYSIS:**


$R_{MAX} = 5.10$  K       $V_D = 3.18$  K <  $V_{ALL} = 51.0$  K       ADEQUATE  
 $M_{MAX} = 12.18$  K-FT <  $M_{ALL} = 53.9$  K-FT       ADEQUATE  
 $\Delta_{TL} = 0.11$  IN.      L/ 888 < L/240 @ CANT'L       ADEQUATE

W10x19 STEEL BEAM

**BEAM DESCRIPTION:** UPPER FLOOR FRAMING - B2-17 - CANT'D FLUSH BM

**PARAMETERS:**

L = 17.13 FT  
W = 0.84 KLF      P2=9.48K  
P = -2.62 K



**ANALYSIS:**

$R_{MAX} = 20.52$  K       $V_D = 12.10$  K <  $V_{ALL} = 17.5$  K       ADEQUATE  
 $M_{MAX} = 27.41$  K-FT <  $M_{ALL} = 59.4$  K-FT       ADEQUATE  
 $\Delta_{TL} = 0.2$  IN.      L/ 965 < L/240       ADEQUATE

5 1/2"x18" GLB




### BEAM & HEADER CALCULATIONS

**BEAM DESCRIPTION:** UPPER FLOOR FRAMING - B2-19 - CANT'D FLUSH BTM. STEEL BM

**PARAMETERS:**

L =  FT  
 W =  KLF W2=0.07KLF  
 P =  K



**ANALYSIS:**


R<sub>MAX</sub> =  K      V<sub>D</sub> =  K < V<sub>ALL</sub> =  K       ADEQUATE  
 M<sub>MAX</sub> =  K-FT < M<sub>ALL</sub> =  K-FT       ADEQUATE  
 Δ<sub>TL</sub> =  IN.      L/  < L/240       ADEQUATE

W10x68 STEEL BM

**BEAM DESCRIPTION:** NOT USED

**PARAMETERS:**

L =  FT  
 W =  KLF  
 P =  K




**ANALYSIS:**

R<sub>MAX</sub> =  K      V<sub>D</sub> =  K < V<sub>ALL</sub> =  K       ADEQUATE  
 M<sub>MAX</sub> =  K-FT < M<sub>ALL</sub> =  K-FT       ADEQUATE  
 Δ<sub>TL</sub> =  IN.      L/  < L/240       ADEQUATE

**BEAM DESCRIPTION:** UPPER FLOOR FRAMING - B2-25 - CANT'D FLUSH BTM. STEEL BM

**PARAMETERS:**

L =  FT  
 W =  KLF  
 P =  K



**ANALYSIS:**

R<sub>MAX</sub> =  K      V<sub>D</sub> =  K < V<sub>ALL</sub> =  K       ADEQUATE  
 M<sub>MAX</sub> =  K-FT < M<sub>ALL</sub> =  K-FT       ADEQUATE  
 Δ<sub>TL</sub> =  IN.      L/  < L/240       ADEQUATE

3-1/2"x11-7/8" LVL




**BEAM & HEADER CALCULATIONS**

**BEAM DESCRIPTION:** MAIN FLOOR FRAMING - B1-1 - FLUSH CANT'D STEEL BM

**PARAMETERS:**

L =  FT  
W =  KLF  
P =  K




**ANALYSIS:**

$R_{MAX} = 2.89$  K       $V_D = 2.89$  K <  $V_{ALL} = 11.9$  K       ADEQUATE  
 $M_{MAX} = 6.42$  K-FT <  $M_{ALL} = 17.9$  K-FT       ADEQUATE  
 $\Delta_{TL} = 0.05$  IN.       $L/999+$  <  $L/240$        ADEQUATE

**BEAM DESCRIPTION:** NOT USED

**PARAMETERS:**

L =  FT  
W =  KLF  
P =  K




**ANALYSIS:**

$R_{MAX} =$   K       $V_D =$   K <  $V_{ALL} =$   K       ADEQUATE  
 $M_{MAX} =$   K-FT <  $M_{ALL} =$   K-FT       ADEQUATE  
 $\Delta_{TL} =$   IN.       $L/$   <  $L/240$        ADEQUATE

**BEAM DESCRIPTION:** EXT. HDR @ OPEN TO BELOW - H3-21 - FLUSH HDR

**PARAMETERS:**

L =  FT  
W =  KLF  
P =  K



**ANALYSIS:**

$R_{MAX} = 0.96$  K       $V_D = -$  K <  $V_{ALL} = 3.95$  K       ADEQUATE  
 $M_{MAX} = 1.44$  K-FT <  $M_{ALL} = 8.93$  K-FT       ADEQUATE  
 $\Delta_{TL} = 0.02$  IN.       $L/999+$  <  $L/240$        ADEQUATE



### BEAM & HEADER CALCULATIONS


**BEAM DESCRIPTION:** EXT. HDR @ OPEN TO BELOW - H3-21 - FLUSH HDR

**PARAMETERS:**

L =  FT

W =  KLF

P =  K



**ANALYSIS:**

R<sub>MAX</sub> =  K

V<sub>D</sub> =  K < V<sub>ALL</sub> =  K

ADEQUATE

M<sub>MAX</sub> =  K-FT

< M<sub>ALL</sub> =  K-FT

ADEQUATE

Δ<sub>TL</sub> =  IN.

L/  < L/240

ADEQUATE


**BEAM DESCRIPTION:** -

**PARAMETERS:**

L =  FT

W =  KLF

P =  K



**ANALYSIS:**

R<sub>MAX</sub> =  K

V<sub>D</sub> =  K < V<sub>ALL</sub> =  K

ADEQUATE

M<sub>MAX</sub> =  K-FT

< M<sub>ALL</sub> =  K-FT

ADEQUATE

Δ<sub>TL</sub> =  IN.

L/  < L/240

ADEQUATE


**BEAM DESCRIPTION:** -

**PARAMETERS:**

L =  FT

W =  KLF

P =  K



**ANALYSIS:**

R<sub>MAX</sub> =  K

V<sub>D</sub> =  K < V<sub>ALL</sub> =  K

ADEQUATE

M<sub>MAX</sub> =  K-FT

< M<sub>ALL</sub> =  K-FT

ADEQUATE

Δ<sub>TL</sub> =  IN.

L/  < L/240

ADEQUATE




**OVERSTRENGTH CALCULATIONS**

**WALL DESCRIPTION/SW #:**

302

**PARAMETERS:**

- L = 4.0 FT
- H = 9.1 FT
- E = 0.20 K
- W<sub>DL WALL</sub> = 0.10 KLF
- W<sub>DL</sub> = 0.151 KLF
- Ω<sub>0</sub> = 2.5 (ASCE TABLE 12.2.1 FOOTNOTE)
- SDS = 1.124



**ANALYSIS:**

E (UNFACTORED) = 0.29

$E_{MH} = \Omega_0 * E = 0.71$  K       $E_v = 0.2 * SDS * DL = 0.226$  K

$E_M = E_{MH} + E_v = 0.940$  K

$E_M = E_{MH} - E_v = 0.489$  K

$E_M (MAX) = \sum MA = 0 = 0.94(9.1) + 0.251(4)(2) - R_B(4)$        $R_B = 0.5DL + 2.1E$

$R_A = 0.5DL - 2.1E$

$E_M (MIN) = \sum MA = 0 = 0.49(9.1) + 0.251(4)(2) - R_B(4)$        $R_B = 0.5DL + 1.1E$

$R_A = 0.5DL - 1.1E$

CHECK BEAMS FOR AXIAL FORCES SHOWN USING LOAD COMBOS PER SECTION 12.4.3.1 (ASD)

ALLOWABLE STRESS PERMITTED TO BE INCREASED BY 1.2

SEE FOLLOWING BEAM  
CALCS FOR LOAD  
APPLICATION




**OVERSTRENGTH CALCULATIONS**

**WALL DESCRIPTION/SW #:**

303

**PARAMETERS:**

- L = 8.3 FT
- H = 9.1 FT
- E = 0.70 K
- W<sub>DL WALL</sub> = 0.10 KLF
- W<sub>DL</sub> = 0.114 KLF
- Ω<sub>0</sub> = 2.5 (ASCE TABLE 12.2.1 FOOTNOTE)
- SDS = 1.124



**ANALYSIS:**

E (UNFACTORED) = 1.00

$E_{MH} = \Omega_0 * E = 2.50$  K       $E_v = 0.2 * SDS * DL = 0.399$  K

$E_M = E_{MH} + E_v = 2.899$  K

$E_M = E_{MH} - E_v = 2.101$  K

$E_M (MAX) = \sum MA = 0 = 2.90(9.1) + 0.214(8.3)(4.15) - R_B(8.3)$        $R_B = 0.9DL + 3.2E$

$R_A = 0.9DL - 3.2E$

$E_M (MIN) = \sum MA = 0 = 2.10(9.1) + 0.214(8.3)(4.15) - R_B(8.3)$        $R_B = 0.9DL + 2.3E$

$R_A = 0.9DL - 2.3E$

CHECK BEAMS FOR AXIAL FORCES SHOWN USING LOAD COMBOS PER SECTION 12.4.3.1 (ASD)

ALLOWABLE STRESS PERMITTED TO BE INCREASED BY 1.2

SEE FOLLOWING BEAM  
CALCS FOR LOAD  
APPLICATION




**OVERSTRENGTH CALCULATIONS**

**WALL DESCRIPTION/SW #:**

304

**PARAMETERS:**

- L = 36.1 FT
- H = 9.1 FT
- E = 1.90 K
- W<sub>DL WALL</sub> = 0.10 KLF
- W<sub>DL</sub> = 0.094 KLF
- Ω<sub>0</sub> = 2.5 (ASCE TABLE 12.2.1 FOOTNOTE)
- SDS = 1.124



**ANALYSIS:**

- E (UNFACTORED) = 2.71
- E<sub>MH</sub> = Ω<sub>0</sub> \* E = 6.79 K
- E<sub>v</sub> = 0.2 \* SDS \* DL = 1.574 K
- E<sub>M</sub> = E<sub>MH</sub> + E<sub>v</sub> = 8.360 K
- E<sub>M</sub> = E<sub>MH</sub> - E<sub>v</sub> = 5.211 K

E<sub>M</sub> (MAX) = ΣM<sub>A</sub> = 0 = 8.36(9.1) + 0.194(36.1)(18.05) - R<sub>B</sub>(36.1)      R<sub>B</sub> = 3.5DL + 2.1E

RA = 3.5DL - 2.1E

E<sub>M</sub> (MIN) = ΣM<sub>A</sub> = 0 = 5.21(9.1) + 0.194(36.1)(18.05) - R<sub>B</sub>(36.1)      R<sub>B</sub> = 3.5DL + 1.3E

RA = 3.5DL - 1.3E

CHECK BEAMS FOR AXIAL FORCES SHOWN USING LOAD COMBOS PER SECTION 12.4.3.1 (ASD)

ALLOWABLE STRESS PERMITTED TO BE INCREASED BY 1.2

SEE FOLLOWING BEAM  
CALCS FOR LOAD  
APPLICATION




**OVERSTRENGTH CALCULATIONS**

**WALL DESCRIPTION/SW #:**

305

PARAMETERS:

- L = 21.5 FT
- H = 9.1 FT
- E = 1.70 K
- W<sub>DL WALL</sub> = 0.10 KLF
- W<sub>DL</sub> = 0.106 KLF
- Ω<sub>0</sub> = 2.5 (ASCE TABLE 12.2.1 FOOTNOTE)
- SDS = 1.124



ANALYSIS:

E (UNFACTORED) = 2.43

$E_{MH} = \Omega_0 * E = 6.07$  K       $E_v = 0.2 * SDS * DL = 0.996$  K

$E_M = E_{MH} + E_v = 7.067$  K

$E_M = E_{MH} - E_v = 5.076$  K

$E_M (MAX) = \sum MA = 0 = 7.07(9.1) + 0.206(21.5)(10.75) - R_b(21.5)$        $R_b = 2.2DL + 3.0E$

$RA = 2.2DL - 3.0E$

$E_M (MIN) = \sum MA = 0 = 5.08(9.1) + 0.206(21.5)(10.75) - R_b(21.5)$        $R_b = 2.2DL + 2.1E$

$RA = 2.2DL - 2.1E$

CHECK BEAMS FOR AXIAL FORCES SHOWN USING LOAD COMBOS PER SECTION 12.4.3.1 (ASD)

ALLOWABLE STRESS PERMITTED TO BE INCREASED BY 1.2

SEE FOLLOWING BEAM  
CALCS FOR LOAD  
APPLICATION




**OVERSTRENGTH CALCULATIONS**

**WALL DESCRIPTION/SW #:**

306

**PARAMETERS:**

- L = 16.6 FT
- H = 9.1 FT
- E = 1.80 K
- W<sub>DL WALL</sub> = 0.10 KLF
- W<sub>DL</sub> = 0.195 KLF
- Ω<sub>0</sub> = 2.5 (ASCE TABLE 12.2.1 FOOTNOTE)
- SDS = 1.124



**ANALYSIS:**

- E (UNFACTORED) = 2.57
- E<sub>MH</sub> = Ω<sub>0</sub> \* E = 6.43 K
- E<sub>v</sub> = 0.2 \* SDS \* DL = 1.101 K
- E<sub>M</sub> = E<sub>MH</sub> + E<sub>v</sub> = 7.529 K
- E<sub>M</sub> = E<sub>MH</sub> - E<sub>v</sub> = 5.328 K

E<sub>M</sub> (MAX) = ΣMA = 0 = 7.53(9.1) + 0.295(16.6)(8.3) - R<sub>B</sub>(16.6)      R<sub>B</sub> = 2.4DL + 4.1E

RA = 2.4DL - 4.1E

E<sub>M</sub> (MIN) = ΣMA = 0 = 5.33(9.1) + 0.295(16.6)(8.3) - R<sub>B</sub>(16.6)      R<sub>B</sub> = 2.4DL + 2.9E

RA = 2.4DL - 2.9E

CHECK BEAMS FOR AXIAL FORCES SHOWN USING LOAD COMBOS PER SECTION 12.4.3.1 (ASD)

ALLOWABLE STRESS PERMITTED TO BE INCREASED BY 1.2

SEE FOLLOWING BEAM  
CALCS FOR LOAD  
APPLICATION




**OVERSTRENGTH CALCULATIONS**

**WALL DESCRIPTION/SW #:**

307

PARAMETERS:

- L = 11.1 FT
- H = 9.1 FT
- E = 0.70 K
- W<sub>DL WALL</sub> = 0.10 KLF
- W<sub>DL</sub> = 0.013 KLF
- Ω<sub>0</sub> = 2.5 (ASCE TABLE 12.2.1 FOOTNOTE)
- SDS = 1.124



ANALYSIS:

E (UNFACTORED) = 1.00

$E_{MH} = \Omega_0 * E = 2.50$  K       $E_v = 0.2 * SDS * DL = 0.282$  K

$E_M = E_{MH} + E_v = 2.782$  K

$E_M = E_{MH} - E_v = 2.218$  K

$E_M (MAX) = \sum MA = 0 = 2.78(9.1) + 0.113(11.1)(5.55) - R_b(11.1)$        $R_b = 0.6DL + 2.3E$

$E_M (MIN) = \sum MA = 0 = 2.22(9.1) + 0.113(11.1)(5.55) - R_b(11.1)$        $R_b = 0.6DL + 1.8E$

$RA = 0.6DL - 2.3E$

$RA = 0.6DL - 1.8E$

CHECK BEAMS FOR AXIAL FORCES SHOWN USING LOAD COMBOS PER SECTION 12.4.3.1 (ASD)

ALLOWABLE STRESS PERMITTED TO BE INCREASED BY 1.2

SEE FOLLOWING BEAM  
CALCS FOR LOAD  
APPLICATION




**OVERSTRENGTH CALCULATIONS**

**WALL DESCRIPTION/SW #:**

309

**PARAMETERS:**

- L = 8.1 FT
- H = 9.1 FT
- E = 0.50 K
- W<sub>DL WALL</sub> = 0.10 KLF
- W<sub>DL</sub> = 0.013 KLF
- Ω<sub>0</sub> = 2.5 (ASCE TABLE 12.2.1 FOOTNOTE)
- SDS = 1.124



**ANALYSIS:**

E (UNFACTORED) = 0.71

E<sub>MH</sub> = Ω<sub>0</sub> \* E = 1.79 K      E<sub>v</sub> = 0.2 \* SDS \* DL = 0.206 K

E<sub>M</sub> = E<sub>MH</sub> + E<sub>v</sub> = 1.991 K

E<sub>M</sub> = E<sub>MH</sub> - E<sub>v</sub> = 1.580 K

E<sub>M</sub> (MAX) = ΣMA = 0 = 1.99(9.1) + 0.113(8.1)(4.05) - R<sub>B</sub>(8.1)      R<sub>B</sub> = 0.5DL + 2.2E

RA = 0.5DL - 2.2E

E<sub>M</sub> (MIN) = ΣMA = 0 = 1.58(9.1) + 0.113(8.1)(4.05) - R<sub>B</sub>(8.1)      R<sub>B</sub> = 0.5DL + 1.8E

RA = 0.5DL - 1.8E

CHECK BEAMS FOR AXIAL FORCES SHOWN USING LOAD COMBOS PER SECTION 12.4.3.1 (ASD)

ALLOWABLE STRESS PERMITTED TO BE INCREASED BY 1.2

SEE FOLLOWING BEAM  
CALCS FOR LOAD  
APPLICATION




**OVERSTRENGTH CALCULATIONS**

**WALL DESCRIPTION/SW #:**

310

**PARAMETERS:**

- L = 7.2 FT
- H = 9.1 FT
- E = 0.40 K
- W<sub>DL WALL</sub> = 0.10 KLF
- W<sub>DL</sub> = 0.013 KLF
- Ω<sub>0</sub> = 2.5 (ASCE TABLE 12.2.1 FOOTNOTE)
- SDS = 1.124



**ANALYSIS:**

- E (UNFACTORED) = 0.57
- $E_{MH} = \Omega_0 * E = 1.43$  K
- $E_v = 0.2 * SDS * DL = 0.183$  K
- $E_M = E_{MH} + E_v = 1.611$  K
- $E_M = E_{MH} - E_v = 1.246$  K

$E_M$  (MAX) =  $\sum MA = 0 = 1.61(9.1) + 0.113(7.2)(3.6) - R_B(7.2)$        $R_B = 0.4DL + 2.0E$

$R_A = 0.4DL - 2.0E$

$E_M$  (MIN) =  $\sum MA = 0 = 1.25(9.1) + 0.113(7.2)(3.6) - R_B(7.2)$        $R_B = 0.4DL + 1.6E$

$R_A = 0.4DL - 1.6E$

CHECK BEAMS FOR AXIAL FORCES SHOWN USING LOAD COMBOS PER SECTION 12.4.3.1 (ASD)

ALLOWABLE STRESS PERMITTED TO BE INCREASED BY 1.2

SEE FOLLOWING BEAM  
CALCS FOR LOAD  
APPLICATION




**OVERSTRENGTH CALCULATIONS**

**WALL DESCRIPTION/SW #:**

311

**PARAMETERS:**

- L = 14.9 FT
- H = 9.1 FT
- E = 1.40 K
- W<sub>DL WALL</sub> = 0.10 KLF
- W<sub>DL</sub> = 0.013 KLF
- Ω<sub>0</sub> = 2.5 (ASCE TABLE 12.2.1 FOOTNOTE)
- SDS = 1.124



**ANALYSIS:**

E (UNFACTORED) = 2.00

E<sub>MH</sub> = Ω<sub>0</sub> \* E = 5.00 K      E<sub>v</sub> = 0.2 \* SDS \* DL = 0.378 K

E<sub>M</sub> = E<sub>MH</sub> + E<sub>v</sub> = 5.378 K

E<sub>M</sub> = E<sub>MH</sub> - E<sub>v</sub> = 4.622 K

E<sub>M</sub> (MAX) = ΣMA = 0 = 5.38(9.1) + 0.113(14.9)(7.45) - R<sub>B</sub>(14.9)      R<sub>B</sub> = 0.8DL + 3.3E

RA = 0.8DL - 3.3E

E<sub>M</sub> (MIN) = ΣMA = 0 = 4.62(9.1) + 0.113(14.9)(7.45) - R<sub>B</sub>(14.9)      R<sub>B</sub> = 0.8DL + 2.8E

RA = 0.8DL - 2.8E

CHECK BEAMS FOR AXIAL FORCES SHOWN USING LOAD COMBOS PER SECTION 12.4.3.1 (ASD)

ALLOWABLE STRESS PERMITTED TO BE INCREASED BY 1.2

SEE FOLLOWING BEAM  
CALCS FOR LOAD  
APPLICATION




**OVERSTRENGTH CALCULATIONS**

**WALL DESCRIPTION/SW #:**

312

**PARAMETERS:**

- L = 14.2 FT
- H = 9.1 FT
- E = 1.20 K
- W<sub>DL WALL</sub> = 0.10 KLF
- W<sub>DL</sub> = 0.013 KLF
- Ω<sub>0</sub> = 2.5 (ASCE TABLE 12.2.1 FOOTNOTE)
- SDS = 1.124



**ANALYSIS:**

E (UNFACTORED) = 1.71

E<sub>MH</sub> = Ω<sub>0</sub> \* E = 4.29 K      E<sub>v</sub> = 0.2 \* SDS \* DL = 0.361 K

E<sub>M</sub> = E<sub>MH</sub> + E<sub>v</sub> = 4.646 K

E<sub>M</sub> = E<sub>MH</sub> - E<sub>v</sub> = 3.925 K

E<sub>M</sub> (MAX) = ΣMA = 0 = 4.65(9.1) + 0.113(14.2)(7.1) - R<sub>B</sub>(14.2)      R<sub>B</sub> = 0.8DL + 3.0E

RA = 0.8DL - 3.0E

E<sub>M</sub> (MIN) = ΣMA = 0 = 3.93(9.1) + 0.113(14.2)(7.1) - R<sub>B</sub>(14.2)      R<sub>B</sub> = 0.8DL + 2.5E

RA = 0.8DL - 2.5E

CHECK BEAMS FOR AXIAL FORCES SHOWN USING LOAD COMBOS PER SECTION 12.4.3.1 (ASD)

ALLOWABLE STRESS PERMITTED TO BE INCREASED BY 1.2

SEE FOLLOWING BEAM  
CALCS FOR LOAD  
APPLICATION




**OVERSTRENGTH CALCULATIONS**

**WALL DESCRIPTION/SW #:**

313

**PARAMETERS:**

- L = 18.8 FT
- H = 9.1 FT
- E = 1.50 K
- W<sub>DL WALL</sub> = 0.10 KLF
- W<sub>DL</sub> = 0.000 KLF
- Ω<sub>0</sub> = 2.5 (ASCE TABLE 12.2.1 FOOTNOTE)
- SDS = 1.124



**ANALYSIS:**

- E (UNFACTORED) = 2.14
- E<sub>MH</sub> = Ω<sub>0</sub> \* E = 5.36 K
- E<sub>v</sub> = 0.2 \* SDS \* DL = 0.423 K
- E<sub>M</sub> = E<sub>MH</sub> + E<sub>v</sub> = 5.780 K
- E<sub>M</sub> = E<sub>MH</sub> - E<sub>v</sub> = 4.935 K

E<sub>M</sub> (MAX) = ΣMA = 0 = 5.78(9.1) + 0.1(18.8)(9.4) - R<sub>B</sub>(18.8)      R<sub>B</sub> = 0.9DL + 2.8E  
 RA = 0.9DL - 2.8E

E<sub>M</sub> (MIN) = ΣMA = 0 = 4.93(9.1) + 0.1(18.8)(9.4) - R<sub>B</sub>(18.8)      R<sub>B</sub> = 0.9DL + 2.4E  
 RA = 0.9DL - 2.4E

CHECK BEAMS FOR AXIAL FORCES SHOWN USING LOAD COMBOS PER SECTION 12.4.3.1 (ASD)

ALLOWABLE STRESS PERMITTED TO BE INCREASED BY 1.2

SEE FOLLOWING BEAM  
CALCS FOR LOAD  
APPLICATION

# Wood Beam

Project File: beam calcs with overstrength.ec6

LIC# : KW-06017913, Build:20.24.08.01

MULHERN & KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

**DESCRIPTION:** B2-17 OS 305

## CODE REFERENCES


Calculations per NDS 2018, IBC 2021, ASCE 7-16

Load Combination Set : ASCE 7-16

## Material Properties

Analysis Method : Allowable Stress Design	Fb +	2,880.0 psi	E : Modulus of Elasticity
Load Combination : ASCE 7-16	Fb -	2,220.0 psi	Ebend- xx
	Fc - Prll	1,980.0 psi	Eminbend - xx
Wood Species : DF/DF	Fc - Perp	650.0 psi	Ebend- yy
Wood Grade : 24F-V4	Fv	318.0 psi	Eminbend - yy
	Ft	1,320.0 psi	Density
			31.210pcf

Beam Bracing : Beam is Fully Braced against lateral-torsional buckling



## Applied Loads

Service loads entered. Load Factors will be applied for calculations.

Beam self weight calculated and added to loading

Load for Span Number 1

Uniform Load : D = 0.350, L = 0.250, S = 0.40 , Tributary Width = 1.0 ft

Point Load : D = -0.390, L = -1.960, S = -1.010 k @ 0.0 ft

Point Load : D = 2.20, E = 3.0 k @ 0.0 ft

Load for Span Number 2

Uniform Load : D = 0.350, L = 0.250, S = 0.40 , Tributary Width = 1.0 ft

Load for Span Number 3

Uniform Load : D = 0.350, L = 0.250, S = 0.40 , Tributary Width = 1.0 ft

Point Load : D = 3.336, L = 4.30, S = 3.891 k @ 2.50 ft

Point Load : D = -2.20 k @ 2.50 ft

## DESIGN SUMMARY

**Design OK**

<b>Maximum Bending Stress Ratio</b>	=	<b>0.338</b> 1	<b>Maximum Shear Stress Ratio</b>	=	<b>0.337</b> : 1
Section used for this span		<b>5.5x18</b>	Section used for this span		<b>5.5x18</b>
fb: Actual	=	843.73psi	fv: Actual	=	123.42 psi
F'b	=	2,498.77psi	F'v	=	365.70 psi
Load Combination +D+0.750L+0.750S+H, LL Comb Run (**L)			Load Combination +D+0.750L+0.750S+H, LL Comb Run (LLL)		
Location of maximum on span	=	16.170ft	Location of maximum on span	=	16.170 ft
Span # where maximum occurs	=	Span # 2	Span # where maximum occurs	=	Span # 2
<b>Maximum Deflection</b>					
Max Downward Transient Deflection	0.064 in	Ratio = 934 >=360	Span: 3 : L Only, LL Comb Run (**L)		
Max Upward Transient Deflection	-0.047 in	Ratio = 1030 >=360	Span: 1 : L Only, LL Comb Run (LL*)		
Max Downward Total Deflection	0.201 in	Ratio = 965 >=180	Span: 2 : +D+0.750L+0.750S+H, LL Comb Run (LL*)		
Max Upward Total Deflection	-0.081 in	Ratio = 588 >=180	Span: 1 : +D+0.750L+0.750S+H, LL Comb Run (LL*)		

## Maximum Forces & Stresses for Load Combinations

Load Combination	Segment Length	Span #	Max Stress Ratios										Moment Values			Shear Values						
			M	V	CD	CM	C <sub>t</sub>	CLx	C <sub>v</sub>	C <sub>fu</sub>	C <sub>i</sub>	C <sub>r</sub>	M	fb	F'b	V	fv	F'v				
+D+H	Length = 2.0 ft	1	0.088	0.131	0.90	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	4.36	176.3	1,998.0	0.0	0.00	0.0	0.0	286.2

# Wood Beam

Project File: beam calcs with overstrength.ec6

LIC# : KW-06017913, Build:20.24.08.01

MULHERN & KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

## DESCRIPTION: B2-17 OS 305

### Maximum Forces & Stresses for Load Combinations

Load Combination	Max Stress Ratios												Moment Values			Shear Values				
			Segment Length	Span #	M	V	CD	CM	C <sub>t</sub>	CLx	C <sub>y</sub>	C <sub>fu</sub>	C <sub>i</sub>	C <sub>r</sub>	M	fb	F'b	V	fv	F'v
Length = 16.170 ft	2	0.127	0.131	0.90	1.00	1.00	1.00	0.979	1.00	1.00	1.00	7.96	321.6	2,536.9	2.47	37.4	286.2			
Length = 2.50 ft	3	0.081	0.131	0.90	1.00	1.00	1.00	1.000	1.00	1.00	1.00	4.00	161.6	1,998.0	1.51	37.4	286.2			
+D+L+H, LL Comb Run (**L)						1.00	1.00	1.00	1.000	1.00	1.00			0.0	0.00	0.0	0.0			
Length = 2.0 ft	1	0.079	0.113	1.00	1.00	1.00	1.00	1.000	1.00	1.00	1.00	4.36	176.3	2,220.0	2.37	35.9	318.0			
Length = 16.170 ft	2	0.289	0.289	1.00	1.00	1.00	1.00	0.979	1.00	1.00	1.00	15.53	627.6	2,172.8	6.06	91.9	318.0			
Length = 2.50 ft	3	0.283	0.289	1.00	1.00	1.00	1.00	1.000	1.00	1.00	1.00	15.53	627.6	2,220.0	6.06	91.9	318.0			
+D+L+H, LL Comb Run (*L*)						1.00	1.00	1.00	1.000	1.00	1.00			0.0	0.00	0.0	0.0			
Length = 2.0 ft	1	0.079	0.196	1.00	1.00	1.00	1.00	1.000	1.00	1.00	1.00	4.36	176.3	2,220.0	4.12	62.4	318.0			
Length = 16.170 ft	2	0.231	0.196	1.00	1.00	1.00	1.00	0.979	1.00	1.00	1.00	16.13	651.7	2,818.8	4.12	62.4	318.0			
Length = 2.50 ft	3	0.073	0.196	1.00	1.00	1.00	1.00	1.000	1.00	1.00	1.00	4.00	161.6	2,220.0	1.51	62.4	318.0			
+D+L+H, LL Comb Run (*LL)						1.00	1.00	1.00	1.000	1.00	1.00			0.0	0.00	0.0	0.0			
Length = 2.0 ft	1	0.079	0.162	1.00	1.00	1.00	1.00	1.000	1.00	1.00	1.00	4.36	176.3	2,220.0	3.40	51.6	318.0			
Length = 16.170 ft	2	0.289	0.289	1.00	1.00	1.00	1.00	0.979	1.00	1.00	1.00	15.53	627.6	2,172.8	6.06	91.9	318.0			
Length = 2.50 ft	3	0.283	0.289	1.00	1.00	1.00	1.00	1.000	1.00	1.00	1.00	15.53	627.6	2,220.0	6.06	91.9	318.0			
+D+L+H, LL Comb Run (L**)						1.00	1.00	1.00	1.000	1.00	1.00			0.0	0.00	0.0	0.0			
Length = 2.0 ft	1	0.017	0.108	1.00	1.00	1.00	1.00	1.000	1.00	1.00	1.00	0.94	38.1	2,220.0	2.26	34.2	318.0			
Length = 16.170 ft	2	0.139	0.126	1.00	1.00	1.00	1.00	0.979	1.00	1.00	1.00	9.72	392.6	2,818.8	2.64	40.0	318.0			
Length = 2.50 ft	3	0.073	0.126	1.00	1.00	1.00	1.00	1.000	1.00	1.00	1.00	4.00	161.6	2,220.0	1.51	40.0	318.0			
+D+L+H, LL Comb Run (L*L)						1.00	1.00	1.00	1.000	1.00	1.00			0.0	0.00	0.0	0.0			
Length = 2.0 ft	1	0.017	0.074	1.00	1.00	1.00	1.00	1.000	1.00	1.00	1.00	0.94	38.1	2,220.0	1.55	23.4	318.0			
Length = 16.170 ft	2	0.289	0.289	1.00	1.00	1.00	1.00	0.979	1.00	1.00	1.00	15.53	627.6	2,172.8	6.06	91.9	318.0			
Length = 2.50 ft	3	0.283	0.289	1.00	1.00	1.00	1.00	1.000	1.00	1.00	1.00	15.53	627.6	2,220.0	6.06	91.9	318.0			
+D+L+H, LL Comb Run (LLL)						1.00	1.00	1.00	1.000	1.00	1.00			0.0	0.00	0.0	0.0			
Length = 2.0 ft	1	0.017	0.152	1.00	1.00	1.00	1.00	1.000	1.00	1.00	1.00	0.94	38.1	2,220.0	3.19	48.4	318.0			
Length = 16.170 ft	2	0.289	0.289	1.00	1.00	1.00	1.00	0.979	1.00	1.00	1.00	15.53	627.6	2,172.8	6.06	91.9	318.0			
Length = 2.50 ft	3	0.283	0.289	1.00	1.00	1.00	1.00	1.000	1.00	1.00	1.00	15.53	627.6	2,220.0	6.06	91.9	318.0			
+D+Lr+H, LL Comb Run (**L)						1.00	1.00	1.00	1.000	1.00	1.00			0.0	0.00	0.0	0.0			
Length = 2.0 ft	1	0.064	0.094	1.25	1.00	1.00	1.00	1.000	1.00	1.00	1.00	4.36	176.3	2,775.0	2.47	37.4	397.5			
Length = 16.170 ft	2	0.091	0.094	1.25	1.00	1.00	1.00	0.979	1.00	1.00	1.00	7.96	321.6	3,523.5	2.47	37.4	397.5			
Length = 2.50 ft	3	0.058	0.094	1.25	1.00	1.00	1.00	1.000	1.00	1.00	1.00	4.00	161.6	2,775.0	1.51	37.4	397.5			
+D+Lr+H, LL Comb Run (*L*)						1.00	1.00	1.00	1.000	1.00	1.00			0.0	0.00	0.0	0.0			
Length = 2.0 ft	1	0.064	0.094	1.25	1.00	1.00	1.00	1.000	1.00	1.00	1.00	4.36	176.3	2,775.0	2.47	37.4	397.5			
Length = 16.170 ft	2	0.091	0.094	1.25	1.00	1.00	1.00	0.979	1.00	1.00	1.00	7.96	321.6	3,523.5	2.47	37.4	397.5			
Length = 2.50 ft	3	0.058	0.094	1.25	1.00	1.00	1.00	1.000	1.00	1.00	1.00	4.00	161.6	2,775.0	1.51	37.4	397.5			
+D+Lr+H, LL Comb Run (*LL)						1.00	1.00	1.00	1.000	1.00	1.00			0.0	0.00	0.0	0.0			
Length = 2.0 ft	1	0.064	0.094	1.25	1.00	1.00	1.00	1.000	1.00	1.00	1.00	4.36	176.3	2,775.0	2.47	37.4	397.5			
Length = 16.170 ft	2	0.091	0.094	1.25	1.00	1.00	1.00	0.979	1.00	1.00	1.00	7.96	321.6	3,523.5	2.47	37.4	397.5			
Length = 2.50 ft	3	0.058	0.094	1.25	1.00	1.00	1.00	1.000	1.00	1.00	1.00	4.00	161.6	2,775.0	1.51	37.4	397.5			
+D+Lr+H, LL Comb Run (L**)						1.00	1.00	1.00	1.000	1.00	1.00			0.0	0.00	0.0	0.0			
Length = 2.0 ft	1	0.064	0.094	1.25	1.00	1.00	1.00	1.000	1.00	1.00	1.00	4.36	176.3	2,775.0	2.47	37.4	397.5			
Length = 16.170 ft	2	0.091	0.094	1.25	1.00	1.00	1.00	0.979	1.00	1.00	1.00	7.96	321.6	3,523.5	2.47	37.4	397.5			
Length = 2.50 ft	3	0.058	0.094	1.25	1.00	1.00	1.00	1.000	1.00	1.00	1.00	4.00	161.6	2,775.0	1.51	37.4	397.5			
+D+Lr+H, LL Comb Run (L*L)						1.00	1.00	1.00	1.000	1.00	1.00			0.0	0.00	0.0	0.0			

# Wood Beam

Project File: beam calcs with overstrength.ec6

LIC# : KW-06017913, Build:20.24.08.01

MULHERN & KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

## DESCRIPTION: B2-17 OS 305

### Maximum Forces & Stresses for Load Combinations

Load Combination		Max Stress Ratios										Moment Values			Shear Values		
Segment Length	Span #	M	V	CD	CM	C <sub>t</sub>	CLx	C <sub>y</sub>	C <sub>fu</sub>	C <sub>i</sub>	C <sub>r</sub>	M	fb	F'b	V	fv	F'v
Length = 2.0 ft	1	0.064	0.094	1.25	1.00	1.00	1.00	1.000	1.00	1.00	1.00	4.36	176.3	2,775.0	2.47	37.4	397.5
Length = 16.170 ft	2	0.091	0.094	1.25	1.00	1.00	1.00	0.979	1.00	1.00	1.00	7.96	321.6	3,523.5	2.47	37.4	397.5
Length = 2.50 ft	3	0.058	0.094	1.25	1.00	1.00	1.00	1.000	1.00	1.00	1.00	4.00	161.6	2,775.0	1.51	37.4	397.5
+D+Lr+H, LL Comb Run (LL*)														0.0	0.00	0.0	0.0
Length = 2.0 ft	1	0.064	0.094	1.25	1.00	1.00	1.00	1.000	1.00	1.00	1.00	4.36	176.3	2,775.0	2.47	37.4	397.5
Length = 16.170 ft	2	0.091	0.094	1.25	1.00	1.00	1.00	0.979	1.00	1.00	1.00	7.96	321.6	3,523.5	2.47	37.4	397.5
Length = 2.50 ft	3	0.058	0.094	1.25	1.00	1.00	1.00	1.000	1.00	1.00	1.00	4.00	161.6	2,775.0	1.51	37.4	397.5
+D+Lr+H, LL Comb Run (LLL)														0.0	0.00	0.0	0.0
Length = 2.0 ft	1	0.064	0.094	1.25	1.00	1.00	1.00	1.000	1.00	1.00	1.00	4.36	176.3	2,775.0	2.47	37.4	397.5
Length = 16.170 ft	2	0.091	0.094	1.25	1.00	1.00	1.00	0.979	1.00	1.00	1.00	7.96	321.6	3,523.5	2.47	37.4	397.5
Length = 2.50 ft	3	0.058	0.094	1.25	1.00	1.00	1.00	1.000	1.00	1.00	1.00	4.00	161.6	2,775.0	1.51	37.4	397.5
+D+S+H														0.0	0.00	0.0	0.0
Length = 2.0 ft	1	0.050	0.180	1.15	1.00	1.00	1.00	1.000	1.00	1.00	1.00	3.14	127.0	2,553.0	4.35	65.9	365.7
Length = 16.170 ft	2	0.206	0.241	1.15	1.00	1.00	1.00	0.979	1.00	1.00	1.00	16.50	666.6	3,241.6	5.82	88.1	365.7
Length = 2.50 ft	3	0.237	0.241	1.15	1.00	1.00	1.00	1.000	1.00	1.00	1.00	14.98	605.2	2,553.0	5.80	88.1	365.7
+D+0.750Lr+0.750L+H, LL Cor														0.0	0.00	0.0	0.0
Length = 2.0 ft	1	0.064	0.090	1.25	1.00	1.00	1.00	1.000	1.00	1.00	1.00	4.36	176.3	2,775.0	2.37	35.9	397.5
Length = 16.170 ft	2	0.188	0.188	1.25	1.00	1.00	1.00	0.979	1.00	1.00	1.00	12.65	511.1	2,716.1	4.92	74.6	397.5
Length = 2.50 ft	3	0.184	0.188	1.25	1.00	1.00	1.00	1.000	1.00	1.00	1.00	12.65	511.1	2,775.0	4.92	74.6	397.5
+D+0.750Lr+0.750L+H, LL Cor														0.0	0.00	0.0	0.0
Length = 2.0 ft	1	0.064	0.141	1.25	1.00	1.00	1.00	1.000	1.00	1.00	1.00	4.36	176.3	2,775.0	3.71	56.2	397.5
Length = 16.170 ft	2	0.162	0.141	1.25	1.00	1.00	1.00	0.979	1.00	1.00	1.00	14.09	569.2	3,523.5	3.71	56.2	397.5
Length = 2.50 ft	3	0.058	0.141	1.25	1.00	1.00	1.00	1.000	1.00	1.00	1.00	4.00	161.6	2,775.0	1.51	56.2	397.5
+D+0.750Lr+0.750L+H, LL Cor														0.0	0.00	0.0	0.0
Length = 2.0 ft	1	0.064	0.121	1.25	1.00	1.00	1.00	1.000	1.00	1.00	1.00	4.36	176.3	2,775.0	3.17	48.0	397.5
Length = 16.170 ft	2	0.188	0.188	1.25	1.00	1.00	1.00	0.979	1.00	1.00	1.00	12.65	511.1	2,716.1	4.92	74.6	397.5
Length = 2.50 ft	3	0.184	0.188	1.25	1.00	1.00	1.00	1.000	1.00	1.00	1.00	12.65	511.1	2,775.0	4.92	74.6	397.5
+D+0.750Lr+0.750L+H, LL Cor														0.0	0.00	0.0	0.0
Length = 2.0 ft	1	0.026	0.088	1.25	1.00	1.00	1.00	1.000	1.00	1.00	1.00	1.80	72.6	2,775.0	2.31	35.0	397.5
Length = 16.170 ft	2	0.106	0.099	1.25	1.00	1.00	1.00	0.979	1.00	1.00	1.00	9.27	374.4	3,523.5	2.58	39.2	397.5
Length = 2.50 ft	3	0.058	0.099	1.25	1.00	1.00	1.00	1.000	1.00	1.00	1.00	4.00	161.6	2,775.0	1.51	39.2	397.5
+D+0.750Lr+0.750L+H, LL Cor														0.0	0.00	0.0	0.0
Length = 2.0 ft	1	0.026	0.068	1.25	1.00	1.00	1.00	1.000	1.00	1.00	1.00	1.80	72.6	2,775.0	1.78	26.9	397.5
Length = 16.170 ft	2	0.188	0.188	1.25	1.00	1.00	1.00	0.979	1.00	1.00	1.00	12.65	511.1	2,716.1	4.92	74.6	397.5
Length = 2.50 ft	3	0.184	0.188	1.25	1.00	1.00	1.00	1.000	1.00	1.00	1.00	12.65	511.1	2,775.0	4.92	74.6	397.5
+D+0.750Lr+0.750L+H, LL Cor														0.0	0.00	0.0	0.0
Length = 2.0 ft	1	0.026	0.135	1.25	1.00	1.00	1.00	1.000	1.00	1.00	1.00	1.80	72.6	2,775.0	3.55	53.7	397.5
Length = 16.170 ft	2	0.176	0.146	1.25	1.00	1.00	1.00	0.979	1.00	1.00	1.00	15.39	621.6	3,523.5	3.82	57.9	397.5
Length = 2.50 ft	3	0.058	0.146	1.25	1.00	1.00	1.00	1.000	1.00	1.00	1.00	4.00	161.6	2,775.0	1.51	57.9	397.5
+D+0.750Lr+0.750L+H, LL Cor														0.0	0.00	0.0	0.0
Length = 2.0 ft	1	0.026	0.115	1.25	1.00	1.00	1.00	1.000	1.00	1.00	1.00	1.80	72.6	2,775.0	3.01	45.6	397.5
Length = 16.170 ft	2	0.188	0.188	1.25	1.00	1.00	1.00	0.979	1.00	1.00	1.00	12.65	511.1	2,716.1	4.92	74.6	397.5
Length = 2.50 ft	3	0.184	0.188	1.25	1.00	1.00	1.00	1.000	1.00	1.00	1.00	12.65	511.1	2,775.0	4.92	74.6	397.5
+D+0.750L+0.750S+H, LL Cor														0.0	0.00	0.0	0.0
Length = 2.0 ft	1	0.055	0.139	1.15	1.00	1.00	1.00	1.000	1.00	1.00	1.00	3.45	139.3	2,553.0	3.35	50.7	365.7
Length = 16.170 ft	2	0.338	0.337	1.15	1.00	1.00	1.00	0.979	1.00	1.00	1.00	20.88	843.7	2,498.8	8.15	123.4	365.7
Length = 2.50 ft	3	0.330	0.337	1.15	1.00	1.00	1.00	1.000	1.00	1.00	1.00	20.88	843.7	2,553.0	8.15	123.4	365.7

# Wood Beam

Project File: beam calcs with overstrength.ec6

LIC# : KW-06017913, Build:20.24.08.01

MULHERN & KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

## DESCRIPTION: B2-17 OS 305

### Maximum Forces & Stresses for Load Combinations

Load Combination		Max Stress Ratios										Moment Values			Shear Values		
Segment Length	Span #	M	V	CD	CM	C <sub>t</sub>	CLx	C <sub>y</sub>	C <sub>fu</sub>	C <sub>i</sub>	C <sub>r</sub>	M	fb	F'b	V	fv	F'v
+D+0.750L+0.750S+H, LL Cor																	
Length = 2.0 ft	1	0.055	0.212	1.15	1.00	1.00	1.00	1.000	1.00	1.00	1.00	3.45	139.3	2,553.0	5.12	77.5	365.7
Length = 16.170 ft	2	0.254	0.257	1.15	1.00	1.00	1.00	0.979	1.00	1.00	1.00	20.40	824.4	3,241.6	6.20	94.0	365.7
Length = 2.50 ft	3	0.194	0.257	1.15	1.00	1.00	1.00	1.000	1.00	1.00	1.00	12.23	494.3	2,553.0	4.73	94.0	365.7
+D+0.750L+0.750S+H, LL Cor																	
Length = 2.0 ft	1	0.055	0.190	1.15	1.00	1.00	1.00	1.000	1.00	1.00	1.00	3.45	139.3	2,553.0	4.58	69.4	365.7
Length = 16.170 ft	2	0.338	0.337	1.15	1.00	1.00	1.00	0.979	1.00	1.00	1.00	20.88	843.7	2,498.8	8.15	123.4	365.7
Length = 2.50 ft	3	0.330	0.337	1.15	1.00	1.00	1.00	1.000	1.00	1.00	1.00	20.88	843.7	2,553.0	8.15	123.4	365.7
+D+0.750L+0.750S+H, LL Cor																	
Length = 2.0 ft	1	0.014	0.154	1.15	1.00	1.00	1.00	1.000	1.00	1.00	1.00	0.88	35.7	2,553.0	3.72	56.4	365.7
Length = 16.170 ft	2	0.196	0.212	1.15	1.00	1.00	1.00	0.979	1.00	1.00	1.00	15.75	636.5	3,241.6	5.13	77.7	365.7
Length = 2.50 ft	3	0.194	0.212	1.15	1.00	1.00	1.00	1.000	1.00	1.00	1.00	12.23	494.3	2,553.0	4.73	77.7	365.7
+D+0.750L+0.750S+H, LL Cor																	
Length = 2.0 ft	1	0.014	0.132	1.15	1.00	1.00	1.00	1.000	1.00	1.00	1.00	0.88	35.7	2,553.0	3.19	48.3	365.7
Length = 16.170 ft	2	0.338	0.337	1.15	1.00	1.00	1.00	0.979	1.00	1.00	1.00	20.88	843.7	2,498.8	8.15	123.4	365.7
Length = 2.50 ft	3	0.330	0.337	1.15	1.00	1.00	1.00	1.000	1.00	1.00	1.00	20.88	843.7	2,553.0	8.15	123.4	365.7
+D+0.750L+0.750S+H, LL Cor																	
Length = 2.0 ft	1	0.014	0.205	1.15	1.00	1.00	1.00	1.000	1.00	1.00	1.00	0.88	35.7	2,553.0	4.96	75.1	365.7
Length = 16.170 ft	2	0.272	0.264	1.15	1.00	1.00	1.00	0.979	1.00	1.00	1.00	21.80	880.8	3,241.6	6.36	96.4	365.7
Length = 2.50 ft	3	0.194	0.264	1.15	1.00	1.00	1.00	1.000	1.00	1.00	1.00	12.23	494.3	2,553.0	4.73	96.4	365.7
+D+0.750L+0.750S+H, LL Cor																	
Length = 2.0 ft	1	0.014	0.183	1.15	1.00	1.00	1.00	1.000	1.00	1.00	1.00	0.88	35.7	2,553.0	4.42	67.0	365.7
Length = 16.170 ft	2	0.338	0.337	1.15	1.00	1.00	1.00	0.979	1.00	1.00	1.00	20.88	843.7	2,498.8	8.15	123.4	365.7
Length = 2.50 ft	3	0.330	0.337	1.15	1.00	1.00	1.00	1.000	1.00	1.00	1.00	20.88	843.7	2,553.0	8.15	123.4	365.7
+D+0.60W+H																	
Length = 2.0 ft	1	0.050	0.074	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	4.36	176.3	3,552.0	2.47	37.4	508.8
Length = 16.170 ft	2	0.071	0.074	1.60	1.00	1.00	1.00	0.979	1.00	1.00	1.00	7.96	321.6	4,510.1	2.47	37.4	508.8
Length = 2.50 ft	3	0.046	0.074	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	4.00	161.6	3,552.0	1.51	37.4	508.8
+D+0.750Lr+0.750L+0.450W+																	
Length = 2.0 ft	1	0.050	0.071	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	4.36	176.3	3,552.0	2.37	35.9	508.8
Length = 16.170 ft	2	0.147	0.147	1.60	1.00	1.00	1.00	0.979	1.00	1.00	1.00	12.65	511.1	3,476.5	4.92	74.6	508.8
Length = 2.50 ft	3	0.144	0.147	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	12.65	511.1	3,552.0	4.92	74.6	508.8
+D+0.750Lr+0.750L+0.450W+																	
Length = 2.0 ft	1	0.050	0.110	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	4.36	176.3	3,552.0	3.71	56.2	508.8
Length = 16.170 ft	2	0.126	0.110	1.60	1.00	1.00	1.00	0.979	1.00	1.00	1.00	14.09	569.2	4,510.1	3.71	56.2	508.8
Length = 2.50 ft	3	0.046	0.110	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	4.00	161.6	3,552.0	1.51	56.2	508.8
+D+0.750Lr+0.750L+0.450W+																	
Length = 2.0 ft	1	0.050	0.094	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	4.36	176.3	3,552.0	3.17	48.0	508.8
Length = 16.170 ft	2	0.147	0.147	1.60	1.00	1.00	1.00	0.979	1.00	1.00	1.00	12.65	511.1	3,476.5	4.92	74.6	508.8
Length = 2.50 ft	3	0.144	0.147	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	12.65	511.1	3,552.0	4.92	74.6	508.8
+D+0.750Lr+0.750L+0.450W+																	
Length = 2.0 ft	1	0.020	0.069	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	1.80	72.6	3,552.0	2.31	35.0	508.8
Length = 16.170 ft	2	0.083	0.077	1.60	1.00	1.00	1.00	0.979	1.00	1.00	1.00	9.27	374.4	4,510.1	2.58	39.2	508.8
Length = 2.50 ft	3	0.046	0.077	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	4.00	161.6	3,552.0	1.51	39.2	508.8
+D+0.750Lr+0.750L+0.450W+																	
Length = 2.0 ft	1	0.020	0.053	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	1.80	72.6	3,552.0	1.78	26.9	508.8
Length = 16.170 ft	2	0.147	0.147	1.60	1.00	1.00	1.00	0.979	1.00	1.00	1.00	12.65	511.1	3,476.5	4.92	74.6	508.8

# Wood Beam

Project File: beam calcs with overstrength.ec6

LIC# : KW-06017913, Build:20.24.08.01

MULHERN & KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

## DESCRIPTION: B2-17 OS 305

### Maximum Forces & Stresses for Load Combinations

Load Combination		Max Stress Ratios										Moment Values			Shear Values		
Segment Length	Span #	M	V	CD	CM	C <sub>t</sub>	CLx	C <sub>y</sub>	C <sub>fu</sub>	C <sub>i</sub>	C <sub>r</sub>	M	fb	F'b	V	fv	F'v
Length = 2.50 ft	3	0.144	0.147	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	12.65	511.1	3,552.0	4.92	74.6	508.8
+D+0.750Lr+0.750L+0.450W+						1.00	1.00	1.00	1.000	1.00	1.00			0.0	0.00	0.0	0.0
Length = 2.0 ft	1	0.020	0.106	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	1.80	72.6	3,552.0	3.55	53.7	508.8
Length = 16.170 ft	2	0.138	0.114	1.60	1.00	1.00	1.00	0.979	1.00	1.00	1.00	15.39	621.6	4,510.1	3.82	57.9	508.8
Length = 2.50 ft	3	0.046	0.114	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	4.00	161.6	3,552.0	1.51	57.9	508.8
+D+0.750Lr+0.750L+0.450W+						1.00	1.00	1.00	1.000	1.00	1.00			0.0	0.00	0.0	0.0
Length = 2.0 ft	1	0.020	0.090	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	1.80	72.6	3,552.0	3.01	45.6	508.8
Length = 16.170 ft	2	0.147	0.147	1.60	1.00	1.00	1.00	0.979	1.00	1.00	1.00	12.65	511.1	3,476.5	4.92	74.6	508.8
Length = 2.50 ft	3	0.144	0.147	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	12.65	511.1	3,552.0	4.92	74.6	508.8
+D+0.750L+0.750S+0.450W+						1.00	1.00	1.00	1.000	1.00	1.00			0.0	0.00	0.0	0.0
Length = 2.0 ft	1	0.039	0.100	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	3.45	139.3	3,552.0	3.35	50.7	508.8
Length = 16.170 ft	2	0.243	0.243	1.60	1.00	1.00	1.00	0.979	1.00	1.00	1.00	20.88	843.7	3,476.5	8.15	123.4	508.8
Length = 2.50 ft	3	0.238	0.243	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	20.88	843.7	3,552.0	8.15	123.4	508.8
+D+0.750L+0.750S+0.450W+						1.00	1.00	1.00	1.000	1.00	1.00			0.0	0.00	0.0	0.0
Length = 2.0 ft	1	0.039	0.152	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	3.45	139.3	3,552.0	5.12	77.5	508.8
Length = 16.170 ft	2	0.183	0.185	1.60	1.00	1.00	1.00	0.979	1.00	1.00	1.00	20.40	824.4	4,510.1	6.20	94.0	508.8
Length = 2.50 ft	3	0.139	0.185	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	12.23	494.3	3,552.0	4.73	94.0	508.8
+D+0.750L+0.750S+0.450W+						1.00	1.00	1.00	1.000	1.00	1.00			0.0	0.00	0.0	0.0
Length = 2.0 ft	1	0.039	0.136	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	3.45	139.3	3,552.0	4.58	69.4	508.8
Length = 16.170 ft	2	0.243	0.243	1.60	1.00	1.00	1.00	0.979	1.00	1.00	1.00	20.88	843.7	3,476.5	8.15	123.4	508.8
Length = 2.50 ft	3	0.238	0.243	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	20.88	843.7	3,552.0	8.15	123.4	508.8
+D+0.750L+0.750S+0.450W+						1.00	1.00	1.00	1.000	1.00	1.00			0.0	0.00	0.0	0.0
Length = 2.0 ft	1	0.010	0.111	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	0.88	35.7	3,552.0	3.72	56.4	508.8
Length = 16.170 ft	2	0.141	0.153	1.60	1.00	1.00	1.00	0.979	1.00	1.00	1.00	15.75	636.5	4,510.1	5.13	77.7	508.8
Length = 2.50 ft	3	0.139	0.153	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	12.23	494.3	3,552.0	4.73	77.7	508.8
+D+0.750L+0.750S+0.450W+						1.00	1.00	1.00	1.000	1.00	1.00			0.0	0.00	0.0	0.0
Length = 2.0 ft	1	0.010	0.095	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	0.88	35.7	3,552.0	3.19	48.3	508.8
Length = 16.170 ft	2	0.243	0.243	1.60	1.00	1.00	1.00	0.979	1.00	1.00	1.00	20.88	843.7	3,476.5	8.15	123.4	508.8
Length = 2.50 ft	3	0.238	0.243	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	20.88	843.7	3,552.0	8.15	123.4	508.8
+D+0.750L+0.750S+0.450W+						1.00	1.00	1.00	1.000	1.00	1.00			0.0	0.00	0.0	0.0
Length = 2.0 ft	1	0.010	0.148	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	0.88	35.7	3,552.0	4.96	75.1	508.8
Length = 16.170 ft	2	0.195	0.189	1.60	1.00	1.00	1.00	0.979	1.00	1.00	1.00	21.80	880.8	4,510.1	6.36	96.4	508.8
Length = 2.50 ft	3	0.139	0.189	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	12.23	494.3	3,552.0	4.73	96.4	508.8
+D+0.750L+0.750S+0.450W+						1.00	1.00	1.00	1.000	1.00	1.00			0.0	0.00	0.0	0.0
Length = 2.0 ft	1	0.010	0.132	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	0.88	35.7	3,552.0	4.42	67.0	508.8
Length = 16.170 ft	2	0.243	0.243	1.60	1.00	1.00	1.00	0.979	1.00	1.00	1.00	20.88	843.7	3,476.5	8.15	123.4	508.8
Length = 2.50 ft	3	0.238	0.243	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	20.88	843.7	3,552.0	8.15	123.4	508.8
+0.60D+0.60W+0.60H						1.00	1.00	1.00	1.000	1.00	1.00			0.0	0.00	0.0	0.0
Length = 2.0 ft	1	0.030	0.044	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	2.62	105.8	3,552.0	1.48	22.5	508.8
Length = 16.170 ft	2	0.043	0.044	1.60	1.00	1.00	1.00	0.979	1.00	1.00	1.00	4.78	193.0	4,510.1	1.48	22.5	508.8
Length = 2.50 ft	3	0.027	0.044	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	2.40	97.0	3,552.0	0.91	22.5	508.8
+D+0.70E+0.60H						1.00	1.00	1.00	1.000	1.00	1.00			0.0	0.00	0.0	0.0
Length = 2.0 ft	1	0.097	0.133	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	8.56	346.0	3,552.0	4.47	67.8	508.8
Length = 16.170 ft	2	0.100	0.133	1.60	1.00	1.00	1.00	0.979	1.00	1.00	1.00	8.56	346.0	3,476.5	2.73	67.8	508.8
Length = 2.50 ft	3	0.046	0.133	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	4.00	161.6	3,552.0	1.51	67.8	508.8
+D-0.70E+0.60H						1.00	1.00	1.00	1.000	1.00	1.00			0.0	0.00	0.0	0.0
Length = 2.0 ft	1	0.002	0.066	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	0.16	6.6	3,552.0	2.21	33.5	508.8

# Wood Beam

Project File: beam calcs with overstrength.ec6

LIC# : KW-06017913, Build:20.24.08.01

MULHERN & KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

## DESCRIPTION: B2-17 OS 305

### Maximum Forces & Stresses for Load Combinations

Load Combination	Segment Length	Span #	Max Stress Ratios									Moment Values			Shear Values		
			M	V	CD	CM	C <sub>t</sub>	CLx	C <sub>y</sub>	C <sub>fu</sub>	C <sub>i</sub>	C <sub>r</sub>	M	fb	F'b	V	fv
Length = 16.170 ft	2	0.091	0.080	1.60	1.00	1.00	1.00	0.979	1.00	1.00	1.00	10.13	409.5	4,510.1	2.69	40.7	508.8
	Length = 2.50 ft	3	0.046	0.080	1.60	1.00	1.00	1.00	1.000	1.00	1.00	4.00	161.6	3,552.0	1.51	40.7	508.8
		+D+0.750L+0.750S+0.5250E+				1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0
Length = 16.170 ft	2	0.075	0.108	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	6.60	266.6	3,552.0	3.64	55.2	508.8
	Length = 2.50 ft	3	0.243	0.243	1.60	1.00	1.00	1.00	0.979	1.00	1.00	20.88	843.7	3,476.5	8.15	123.4	508.8
		+D+0.750L+0.750S+0.5250E+				1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0
Length = 16.170 ft	2	0.168	0.179	1.60	1.00	1.00	1.00	0.979	1.00	1.00	1.00	18.73	756.6	4,510.1	6.01	91.1	508.8
	Length = 2.50 ft	3	0.139	0.179	1.60	1.00	1.00	1.00	1.000	1.00	1.00	12.23	494.3	3,552.0	4.73	91.1	508.8
		+D+0.750L+0.750S+0.5250E+				1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0
Length = 16.170 ft	2	0.125	0.147	1.60	1.00	1.00	1.00	0.979	1.00	1.00	1.00	14.00	565.8	4,510.1	4.93	74.7	508.8
	Length = 2.50 ft	3	0.139	0.147	1.60	1.00	1.00	1.00	1.000	1.00	1.00	12.23	494.3	3,552.0	4.73	74.7	508.8
		+D+0.750L+0.750S+0.5250E+				1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0
Length = 16.170 ft	2	0.243	0.243	1.60	1.00	1.00	1.00	0.979	1.00	1.00	1.00	20.88	843.7	3,476.5	8.15	123.4	508.8
	Length = 2.50 ft	3	0.238	0.243	1.60	1.00	1.00	1.00	1.000	1.00	1.00	20.88	843.7	3,552.0	8.15	123.4	508.8
		+D+0.750L+0.750S+0.5250E+				1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0
Length = 16.170 ft	2	0.180	0.184	1.60	1.00	1.00	1.00	0.979	1.00	1.00	1.00	20.09	811.7	4,510.1	6.17	93.5	508.8
	Length = 2.50 ft	3	0.139	0.184	1.60	1.00	1.00	1.00	1.000	1.00	1.00	12.23	494.3	3,552.0	4.73	93.5	508.8
		+D+0.750L+0.750S+0.5250E+				1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0
Length = 16.170 ft	2	0.046	0.101	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	4.03	162.9	3,552.0	3.38	51.3	508.8
	Length = 2.50 ft	3	0.243	0.243	1.60	1.00	1.00	1.00	0.979	1.00	1.00	20.88	843.7	3,476.5	8.15	123.4	508.8
		+D+0.750L+0.750S+0.5250E+				1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0
Length = 16.170 ft	2	0.243	0.243	1.60	1.00	1.00	1.00	0.979	1.00	1.00	1.00	20.88	843.7	3,476.5	8.15	123.4	508.8
	Length = 2.50 ft	3	0.238	0.243	1.60	1.00	1.00	1.00	1.000	1.00	1.00	20.88	843.7	3,552.0	8.15	123.4	508.8
		+D+0.750L+0.750S+0.5250E+				1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0
Length = 16.170 ft	2	0.003	0.094	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	0.30	12.0	3,552.0	3.15	47.8	508.8
	Length = 2.50 ft	3	0.243	0.243	1.60	1.00	1.00	1.00	0.979	1.00	1.00	20.88	843.7	3,476.5	8.15	123.4	508.8
		+D+0.750L+0.750S-0.5250E+				1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0
Length = 16.170 ft	2	0.198	0.191	1.60	1.00	1.00	1.00	0.979	1.00	1.00	1.00	22.12	893.9	4,510.1	6.40	97.0	508.8
	Length = 2.50 ft	3	0.139	0.191	1.60	1.00	1.00	1.00	1.000	1.00	1.00	12.23	494.3	3,552.0	4.73	97.0	508.8
		+D+0.750L+0.750S-0.5250E+				1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0
Length = 16.170 ft	2	0.003	0.131	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	0.30	12.0	3,552.0	4.39	66.5	508.8
	Length = 2.50 ft	3	0.243	0.243	1.60	1.00	1.00	1.00	0.979	1.00	1.00	20.88	843.7	3,476.5	8.15	123.4	508.8
		+D+0.750L+0.750S-0.5250E+				1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0
Length = 16.170 ft	2	0.157	0.158	1.60	1.00	1.00	1.00	0.979	1.00	1.00	1.00	17.56	709.5	4,510.1	5.32	80.6	508.8
	Length = 2.50 ft	3	0.139	0.158	1.60	1.00	1.00	1.00	1.000	1.00	1.00	12.23	494.3	3,552.0	4.73	80.6	508.8
		+D+0.750L+0.750S-0.5250E+				1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0

# Wood Beam

Project File: beam calcs with overstrength.ec6

LIC# : KW-06017913, Build:20.24.08.01

MULHERN & KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

## DESCRIPTION: B2-17 OS 305

### Maximum Forces & Stresses for Load Combinations

Load Combination		Max Stress Ratios										Moment Values			Shear Values			
Segment Length	Span #	M	V	CD	CM	C <sub>t</sub>	CLx	C <sub>v</sub>	C <sub>fu</sub>	C <sub>i</sub>	C <sub>r</sub>	M	fb	F'b	V	fv	F'v	
Length = 2.0 ft	1	0.020	0.089	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	2.27	91.6	4,608.0	2.99	45.4	508.8	
Length = 16.170 ft	2	0.243	0.243	1.60	1.00	1.00	1.00	0.979	1.00	1.00	1.00	20.88	843.7	3,476.5	8.15	123.4	508.8	
Length = 2.50 ft	3	0.238	0.243	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	20.88	843.7	3,552.0	8.15	123.4	508.8	
+D+0.750L+0.750S-0.5250E+															0.0	0.00	0.0	0.0
Length = 2.0 ft	1	0.020	0.142	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	2.27	91.6	4,608.0	4.76	72.2	508.8	
Length = 16.170 ft	2	0.211	0.195	1.60	1.00	1.00	1.00	0.979	1.00	1.00	1.00	23.56	951.8	4,510.1	6.56	99.4	508.8	
Length = 2.50 ft	3	0.139	0.195	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	12.23	494.3	3,552.0	4.73	99.4	508.8	
+D+0.750L+0.750S-0.5250E+															0.0	0.00	0.0	0.0
Length = 2.0 ft	1	0.020	0.126	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	2.27	91.6	4,608.0	4.23	64.1	508.8	
Length = 16.170 ft	2	0.243	0.243	1.60	1.00	1.00	1.00	0.979	1.00	1.00	1.00	20.88	843.7	3,476.5	8.15	123.4	508.8	
Length = 2.50 ft	3	0.238	0.243	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	20.88	843.7	3,552.0	8.15	123.4	508.8	
+0.60D+0.70E+H															0.0	0.00	0.0	0.0
Length = 2.0 ft	1	0.078	0.105	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	6.82	275.5	3,552.0	3.52	53.4	508.8	
Length = 16.170 ft	2	0.079	0.105	1.60	1.00	1.00	1.00	0.979	1.00	1.00	1.00	6.82	275.5	3,476.5	1.74	53.4	508.8	
Length = 2.50 ft	3	0.027	0.105	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	2.40	97.0	3,552.0	0.91	53.4	508.8	
+0.60D-0.70E+H															0.0	0.00	0.0	0.0
Length = 2.0 ft	1	0.014	0.036	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	1.58	63.9	4,608.0	1.22	18.5	508.8	
Length = 16.170 ft	2	0.063	0.051	1.60	1.00	1.00	1.00	0.979	1.00	1.00	1.00	7.01	283.3	4,510.1	1.72	26.0	508.8	
Length = 2.50 ft	3	0.027	0.051	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	2.40	97.0	3,552.0	0.91	26.0	508.8	
+1.140D+0.70E															0.0	0.00	0.0	0.0
Length = 2.0 ft	1	0.104	0.143	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	9.17	370.7	3,552.0	4.80	72.8	508.8	
Length = 16.170 ft	2	0.107	0.143	1.60	1.00	1.00	1.00	0.979	1.00	1.00	1.00	9.17	370.7	3,476.5	3.08	72.8	508.8	
Length = 2.50 ft	3	0.052	0.143	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	4.56	184.3	3,552.0	1.72	72.8	508.8	
+1.140D-0.70E															0.0	0.00	0.0	0.0
Length = 2.0 ft	1	0.009	0.076	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	0.77	31.3	3,552.0	2.56	38.7	508.8	
Length = 16.170 ft	2	0.101	0.090	1.60	1.00	1.00	1.00	0.979	1.00	1.00	1.00	11.24	454.0	4,510.1	3.02	45.8	508.8	
Length = 2.50 ft	3	0.052	0.090	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	4.56	184.3	3,552.0	1.72	45.8	508.8	
+1.105D+0.750L+0.750S+0.52															0.0	0.00	0.0	0.0
Length = 2.0 ft	1	0.080	0.116	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	7.06	285.1	3,552.0	3.89	59.0	508.8	
Length = 16.170 ft	2	0.248	0.247	1.60	1.00	1.00	1.00	0.979	1.00	1.00	1.00	21.30	860.7	3,476.5	8.30	125.8	508.8	
Length = 2.50 ft	3	0.242	0.247	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	21.30	860.7	3,552.0	8.30	125.8	508.8	
+1.105D+0.750L+0.750S+0.52															0.0	0.00	0.0	0.0
Length = 2.0 ft	1	0.080	0.166	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	7.06	285.1	3,552.0	5.57	84.4	508.8	
Length = 16.170 ft	2	0.175	0.187	1.60	1.00	1.00	1.00	0.979	1.00	1.00	1.00	19.56	790.3	4,510.1	6.26	94.9	508.8	
Length = 2.50 ft	3	0.144	0.187	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	12.65	511.3	3,552.0	4.89	94.9	508.8	
+1.105D+0.750L+0.750S+0.52															0.0	0.00	0.0	0.0
Length = 2.0 ft	1	0.080	0.150	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	7.06	285.1	3,552.0	5.04	76.3	508.8	
Length = 16.170 ft	2	0.248	0.247	1.60	1.00	1.00	1.00	0.979	1.00	1.00	1.00	21.30	860.7	3,476.5	8.30	125.8	508.8	
Length = 2.50 ft	3	0.242	0.247	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	21.30	860.7	3,552.0	8.30	125.8	508.8	
+1.105D+0.750L+0.750S+0.52															0.0	0.00	0.0	0.0
Length = 2.0 ft	1	0.051	0.124	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	4.49	181.5	3,552.0	4.18	63.3	508.8	
Length = 16.170 ft	2	0.133	0.154	1.60	1.00	1.00	1.00	0.979	1.00	1.00	1.00	14.83	599.1	4,510.1	5.19	78.6	508.8	
Length = 2.50 ft	3	0.144	0.154	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	12.65	511.3	3,552.0	4.89	78.6	508.8	
+1.105D+0.750L+0.750S+0.52															0.0	0.00	0.0	0.0
Length = 2.0 ft	1	0.051	0.108	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	4.49	181.5	3,552.0	3.64	55.2	508.8	
Length = 16.170 ft	2	0.248	0.247	1.60	1.00	1.00	1.00	0.979	1.00	1.00	1.00	21.30	860.7	3,476.5	8.30	125.8	508.8	
Length = 2.50 ft	3	0.242	0.247	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	21.30	860.7	3,552.0	8.30	125.8	508.8	

# Wood Beam

Project File: beam calcs with overstrength.ec6

LIC# : KW-06017913, Build:20.24.08.01

MULHERN & KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

## DESCRIPTION: B2-17 OS 305

### Maximum Forces & Stresses for Load Combinations

Load Combination		Max Stress Ratios										Moment Values			Shear Values		
Segment Length	Span #	M	V	CD	CM	C <sub>t</sub>	CLx	C <sub>v</sub>	C <sub>fu</sub>	C <sub>i</sub>	C <sub>r</sub>	M	fb	F'b	V	fv	F'v
+1.105D+0.750L+0.750S+0.52					1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 2.0 ft	1	0.051	0.161	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	4.49	181.5	3,552.0	5.41	82.0	508.8
Length = 16.170 ft	2	0.187	0.191	1.60	1.00	1.00	1.00	0.979	1.00	1.00	1.00	20.92	845.1	4,510.1	6.42	97.3	508.8
Length = 2.50 ft	3	0.144	0.191	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	12.65	511.3	3,552.0	4.89	97.3	508.8
+1.105D+0.750L+0.750S+0.52					1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 2.0 ft	1	0.051	0.145	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	4.49	181.5	3,552.0	4.88	73.9	508.8
Length = 16.170 ft	2	0.248	0.247	1.60	1.00	1.00	1.00	0.979	1.00	1.00	1.00	21.30	860.7	3,476.5	8.30	125.8	508.8
Length = 2.50 ft	3	0.242	0.247	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	21.30	860.7	3,552.0	8.30	125.8	508.8
+1.105D+0.750L+0.750S-0.52					1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 2.0 ft	1	0.009	0.102	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	0.76	30.5	3,552.0	3.41	51.7	508.8
Length = 16.170 ft	2	0.248	0.247	1.60	1.00	1.00	1.00	0.979	1.00	1.00	1.00	21.30	860.7	3,476.5	8.30	125.8	508.8
Length = 2.50 ft	3	0.242	0.247	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	21.30	860.7	3,552.0	8.30	125.8	508.8
+1.105D+0.750L+0.750S-0.52					1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 2.0 ft	1	0.009	0.154	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	0.76	30.5	3,552.0	5.18	78.5	508.8
Length = 16.170 ft	2	0.206	0.198	1.60	1.00	1.00	1.00	0.979	1.00	1.00	1.00	22.94	927.0	4,510.1	6.65	100.8	508.8
Length = 2.50 ft	3	0.144	0.198	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	12.65	511.3	3,552.0	4.89	100.8	508.8
+1.105D+0.750L+0.750S-0.52					1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 2.0 ft	1	0.009	0.138	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	0.76	30.5	3,552.0	4.65	70.4	508.8
Length = 16.170 ft	2	0.248	0.247	1.60	1.00	1.00	1.00	0.979	1.00	1.00	1.00	21.30	860.7	3,476.5	8.30	125.8	508.8
Length = 2.50 ft	3	0.242	0.247	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	21.30	860.7	3,552.0	8.30	125.8	508.8
+1.105D+0.750L+0.750S-0.52					1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 2.0 ft	1	0.016	0.113	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	1.81	73.1	4,608.0	3.79	57.4	508.8
Length = 16.170 ft	2	0.164	0.166	1.60	1.00	1.00	1.00	0.979	1.00	1.00	1.00	18.36	741.8	4,510.1	5.58	84.5	508.8
Length = 2.50 ft	3	0.144	0.166	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	12.65	511.3	3,552.0	4.89	84.5	508.8
+1.105D+0.750L+0.750S-0.52					1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 2.0 ft	1	0.016	0.097	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	1.81	73.1	4,608.0	3.25	49.3	508.8
Length = 16.170 ft	2	0.248	0.247	1.60	1.00	1.00	1.00	0.979	1.00	1.00	1.00	21.30	860.7	3,476.5	8.30	125.8	508.8
Length = 2.50 ft	3	0.242	0.247	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	21.30	860.7	3,552.0	8.30	125.8	508.8
+1.105D+0.750L+0.750S-0.52					1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 2.0 ft	1	0.016	0.150	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	1.81	73.1	4,608.0	5.02	76.1	508.8
Length = 16.170 ft	2	0.218	0.203	1.60	1.00	1.00	1.00	0.979	1.00	1.00	1.00	24.37	984.7	4,510.1	6.81	103.2	508.8
Length = 2.50 ft	3	0.144	0.203	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	12.65	511.3	3,552.0	4.89	103.2	508.8
+1.105D+0.750L+0.750S-0.52					1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 2.0 ft	1	0.016	0.134	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	1.81	73.1	4,608.0	4.49	68.0	508.8
Length = 16.170 ft	2	0.248	0.247	1.60	1.00	1.00	1.00	0.979	1.00	1.00	1.00	21.30	860.7	3,476.5	8.30	125.8	508.8
Length = 2.50 ft	3	0.242	0.247	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	21.30	860.7	3,552.0	8.30	125.8	508.8
+0.460D+0.70E					1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 2.0 ft	1	0.071	0.095	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	6.21	250.8	3,552.0	3.19	48.3	508.8
Length = 16.170 ft	2	0.072	0.095	1.60	1.00	1.00	1.00	0.979	1.00	1.00	1.00	6.21	250.8	3,476.5	1.40	48.3	508.8
Length = 2.50 ft	3	0.021	0.095	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	1.84	74.4	3,552.0	0.69	48.3	508.8
+0.460D-0.70E					1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 2.0 ft	1	0.019	0.038	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	2.19	88.6	4,608.0	1.27	19.2	508.8
Length = 16.170 ft	2	0.053	0.041	1.60	1.00	1.00	1.00	0.979	1.00	1.00	1.00	5.94	240.1	4,510.1	1.38	20.8	508.8
Length = 2.50 ft	3	0.021	0.041	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	1.84	74.4	3,552.0	0.69	20.8	508.8

### Overall Maximum Deflections

Load Combination	Span	Max. "-" Defl	Location in Span	Load Combination	Max. "+" Defl	Location in Span
	1	0.0000	0.000	+D+0.750L+0.750S+0.450W+H, LI	-0.0814	0.000

## Wood Beam

Project File: beam calcs with overstrength.ec6

LIC# : KW-06017913, Build:20.24.08.01

MULHERN & KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

### DESCRIPTION: B2-17 OS 305

### Overall Maximum Deflections

Load Combination	Span	Max. "-" Defl	Location in Span	Load Combination	Max. "+" Defl	Location in Span
+D+0.750L+0.750S+0.450W+H, LI	2	0.2009	7.745	+D+L+H, LL Comb Run (LL*)	0.0000	0.000
	3	0.0000	7.745		-0.0739	2.500

### Vertical Reactions

Support notation : Far left is #1

Values in KIPS

Load Combination	Support 1	Support 2	Support 3	Support 4
Max Upward from all Load Conditions		10.567	17.803	
Max Upward from Load Combinations		10.567	17.803	
Max Upward from Load Cases		5.579	8.879	
Max Downward from all Load Conditio		-3.371	-0.371	
Max Downward from Load Cases (Resis		-3.371	-0.371	
+D+H		5.579	5.045	
+D+L+H, LL Comb Run (**L)		4.865	10.684	
+D+L+H, LL Comb Run (*L*)		7.600	7.067	
+D+L+H, LL Comb Run (*LL)		6.887	12.705	
+D+L+H, LL Comb Run (L**)		3.907	5.257	
+D+L+H, LL Comb Run (L*L)		3.194	10.895	
+D+L+H, LL Comb Run (LL*)		5.928	7.278	
+D+L+H, LL Comb Run (LLL)		5.215	12.916	
+D+Lr+H, LL Comb Run (**L)		5.579	5.045	
+D+Lr+H, LL Comb Run (*L*)		5.579	5.045	
+D+Lr+H, LL Comb Run (*LL)		5.579	5.045	
+D+Lr+H, LL Comb Run (L**)		5.579	5.045	
+D+Lr+H, LL Comb Run (L*L)		5.579	5.045	
+D+Lr+H, LL Comb Run (LL*)		5.579	5.045	
+D+Lr+H, LL Comb Run (LLL)		5.579	5.045	
+D+S+H		7.848	13.925	
+D+0.750Lr+0.750L+H, LL Comb Run (*		5.044	9.274	
+D+0.750Lr+0.750L+H, LL Comb Run (*		7.094	6.561	
+D+0.750Lr+0.750L+H, LL Comb Run (*		6.560	10.790	
+D+0.750Lr+0.750L+H, LL Comb Run (L		4.325	5.204	
+D+0.750Lr+0.750L+H, LL Comb Run (L		3.790	9.433	
+D+0.750Lr+0.750L+H, LL Comb Run (L		5.841	6.720	
+D+0.750Lr+0.750L+H, LL Comb Run (L		5.306	10.949	
+D+0.750L+0.750S+H, LL Comb Run (**		6.746	15.934	
+D+0.750L+0.750S+H, LL Comb Run (*L		8.797	13.221	
+D+0.750L+0.750S+H, LL Comb Run (*L		8.262	17.450	
+D+0.750L+0.750S+H, LL Comb Run (L*		6.027	11.864	
+D+0.750L+0.750S+H, LL Comb Run (L*		5.492	16.092	
+D+0.750L+0.750S+H, LL Comb Run (LL		7.543	13.380	
+D+0.750L+0.750S+H, LL Comb Run (LL		7.008	17.608	
+D+0.60W+H		5.579	5.045	
+D+0.750Lr+0.750L+0.450W+H, LL Comb		5.044	9.274	
+D+0.750Lr+0.750L+0.450W+H, LL Comb		7.094	6.561	
+D+0.750Lr+0.750L+0.450W+H, LL Comb		6.560	10.790	
+D+0.750Lr+0.750L+0.450W+H, LL Comb		4.325	5.204	
+D+0.750Lr+0.750L+0.450W+H, LL Comb		3.790	9.433	
+D+0.750Lr+0.750L+0.450W+H, LL Comb		5.841	6.720	
+D+0.750Lr+0.750L+0.450W+H, LL Comb		5.306	10.949	
+D+0.750L+0.750S+0.450W+H, LL Comb		6.746	15.934	
+D+0.750L+0.750S+0.450W+H, LL Comb		8.797	13.221	
+D+0.750L+0.750S+0.450W+H, LL Comb		8.262	17.450	
+D+0.750L+0.750S+0.450W+H, LL Comb		6.027	11.864	
+D+0.750L+0.750S+0.450W+H, LL Comb		5.492	16.092	
+D+0.750L+0.750S+0.450W+H, LL Comb		7.543	13.380	
+D+0.750L+0.750S+0.450W+H, LL Comb		7.008	17.608	
+0.60D+0.60W+0.60H		3.347	3.027	
+D+0.70E+0.60H		7.938	4.786	
+D-0.70E+0.60H		3.219	5.305	
+D+0.750L+0.750S+0.5250E+H, LL Comb		8.516	15.739	

**Wood Beam**

Project File: beam calcs with overstrength.ec6

LIC# : KW-06017913, Build:20.24.08.01

MULHERN &amp; KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

**DESCRIPTION: B2-17 OS 305****Vertical Reactions**

Support notation : Far left is #1

Values in KIPS

Load Combination	Support 1	Support 2	Support 3	Support 4
+D+0.750L+0.750S+0.5250E+H, LL Comb		10.567	13.026	
+D+0.750L+0.750S+0.5250E+H, LL Comb		10.032	17.255	
+D+0.750L+0.750S+0.5250E+H, LL Comb		7.797	11.669	
+D+0.750L+0.750S+0.5250E+H, LL Comb		7.262	15.897	
+D+0.750L+0.750S+0.5250E+H, LL Comb		9.313	13.185	
+D+0.750L+0.750S+0.5250E+H, LL Comb		8.778	17.413	
+D+0.750L+0.750S-0.5250E+H, LL Comb		4.976	16.128	
+D+0.750L+0.750S-0.5250E+H, LL Comb		7.027	13.416	
+D+0.750L+0.750S-0.5250E+H, LL Comb		6.492	17.644	
+D+0.750L+0.750S-0.5250E+H, LL Comb		4.257	12.058	
+D+0.750L+0.750S-0.5250E+H, LL Comb		3.723	16.287	
+D+0.750L+0.750S-0.5250E+H, LL Comb		5.773	13.574	
+D+0.750L+0.750S-0.5250E+H, LL Comb		5.238	17.803	
+0.60D+0.70E+H		5.707	2.768	
+0.60D-0.70E+H		0.987	3.287	
D Only		5.579	5.045	
L Only, LL Comb Run (**L)		-0.713	5.638	
L Only, LL Comb Run (*L*)		2.021	2.021	
L Only, LL Comb Run (*LL)		1.308	7.659	
L Only, LL Comb Run (L**)		-1.672	0.212	
L Only, LL Comb Run (L*L)		-2.385	5.850	
L Only, LL Comb Run (LL*)		0.350	2.233	
L Only, LL Comb Run (LLL)		-0.363	7.871	
S Only		2.270	8.879	
E Only		3.371	-0.371	
E Only * -1.0		-3.371	0.371	
H Only				

# Wood Beam

Project File: beam calcs with overstrength.ecb

LIC#: KW-06017913, Build:20.24.08.01

MULHERN & KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

**DESCRIPTION:** B2-8 OS 303


## CODE REFERENCES

Calculations per NDS 2018, IBC 2021, ASCE 7-16

Load Combination Set : ASCE 7-16

## Material Properties

Analysis Method :	Allowable Stress Design	Fb +	2,880.0 psi	E : Modulus of Elasticity	
Load Combination :	ASCE 7-16	Fb -	2,220.0 psi	Ebend- xx	1,800.0ksi
		Fc - Prll	1,980.0 psi	Eminbend - xx	950.0ksi
Wood Species :	24-V4 GLB OS	Fc - Perp	780.0 psi	Ebend- yy	ksi
Wood Grade :	GLB - Western	Fv	318.0 psi	Eminbend - yy	ksi
		Ft	318.0 psi	Density	35.0pcf
Beam Bracing :	Beam is Fully Braced against lateral-torsional buckling				



## Applied Loads

Service loads entered. Load Factors will be applied for calculations.

Beam self weight calculated and added to loading

Load for Span Number 1

- Uniform Load : D = 0.360, L = 0.450, S = 0.250 k/ft, Extent = 0.0 -->> 4.0 ft, Tributary Width = 1.0 ft
- Uniform Load : D = 0.420, L = 0.450, S = 0.380 k/ft, Extent = 4.0 -->> 4.60 ft, Tributary Width = 1.0 ft
- Uniform Load : D = 0.150, L = 0.290, S = 0.10 k/ft, Extent = 4.60 -->> 10.40 ft, Tributary Width = 1.0 ft
- Uniform Load : D = 0.360, L = 0.290, S = 0.380 k/ft, Extent = 10.40 -->> 10.60 ft, Tributary Width = 1.0 ft
- Uniform Load : D = 0.150, L = 0.290, S = 0.10 k/ft, Extent = 10.60 -->> 18.30 ft, Tributary Width = 1.0 ft
- Point Load : D = 0.60, L = 0.20, S = 0.10 k @ 3.70 ft
- Point Load : D = 0.40, S = 0.90 k @ 4.40 ft
- Point Load : D = 0.80, S = 2.0 k @ 10.40 ft
- Point Load : D = 0.90, E = 3.20 k @ 10.670 ft

## DESIGN SUMMARY

Design OK

<p><b>Maximum Bending Stress Ratio</b> = <span style="color: green;">0.496</span> : 1</p> <p>Section used for this span = <b>5.5x18</b></p> <p>fb: Actual = 1,588.58psi</p> <p>F'b = 3,201.78psi</p> <p>Load Combination = +D+0.750L+0.750S+H</p> <p>Location of maximum on span = 10.352ft</p> <p>Span # where maximum occurs = Span # 1</p> <p><b>Maximum Deflection</b></p> <p>Max Downward Transient Deflection = 0.189 in Ratio = <span style="color: green;">1160</span> &gt;=360</p> <p>Max Upward Transient Deflection = 0 in Ratio = <span style="color: red;">0</span> &lt;360</p> <p>Max Downward Total Deflection = 0.559 in Ratio = <span style="color: green;">392</span> &gt;=180</p> <p>Max Upward Total Deflection = 0 in Ratio = <span style="color: red;">0</span> &lt;180</p>	<p><b>Maximum Shear Stress Ratio</b> = <span style="color: green;">0.318</span> : 1</p> <p>Section used for this span = <b>5.5x18</b></p> <p>fv: Actual = 116.12 psi</p> <p>F'v = 365.70 psi</p> <p>Load Combination = +D+0.750L+0.750S+H</p> <p>Location of maximum on span = 0.000 ft</p> <p>Span # where maximum occurs = Span # 1</p> <p>Span: 1 : S Only</p> <p>Span: 1 : +D+0.750L+0.750S+0.5250E+H</p>
---	---

## Maximum Forces & Stresses for Load Combinations

Load Combination	Segment Length	Span #	Max Stress Ratios										Moment Values			Shear Values			
			M	V	CD	CM	C <sub>t</sub>	CLx	C <sub>v</sub>	C <sub>fu</sub>	C <sub>i</sub>	C <sub>r</sub>	M	fb	F'b	V	fv	F'v	
+D+H	Length = 18.30 ft	1	0.283	0.181	0.90	1.00	1.00	1.00	0.967	1.00	1.00	1.00	17.57	709.8	2,505.7	0.0	0.00	0.0	0.0

# Wood Beam

Project File: beam calcs with overstrength.ec6

LIC# : KW-06017913, Build:20.24.08.01

MULHERN & KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

## DESCRIPTION: B2-8 OS 303

### Maximum Forces & Stresses for Load Combinations

Load Combination	Segment Length	Span #	Max Stress Ratios									Moment Values			Shear Values			
			M	V	CD	CM	C <sub>t</sub>	CLx	C <sub>v</sub>	C <sub>fu</sub>	C <sub>i</sub>	C <sub>r</sub>	M	fb	F'b	V	fv	F'v
+D+L+H						1.00	1.00	1.00	0.967	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.30 ft	1		0.445	0.296	1.00	1.00	1.00	1.00	0.967	1.00	1.00	1.00	30.65	1,238.4	2,784.2	6.22	94.2	318.0
+D+Lr+H						1.00	1.00	1.00	0.967	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.30 ft	1		0.204	0.130	1.25	1.00	1.00	1.00	0.967	1.00	1.00	1.00	17.57	709.8	3,480.2	3.42	51.8	397.5
+D+S+H						1.00	1.00	1.00	0.967	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.30 ft	1		0.424	0.260	1.15	1.00	1.00	1.00	0.967	1.00	1.00	1.00	33.58	1,356.8	3,201.8	6.28	95.2	365.7
+D+0.750Lr+0.750L+H						1.00	1.00	1.00	0.967	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.30 ft	1		0.317	0.210	1.25	1.00	1.00	1.00	0.967	1.00	1.00	1.00	27.35	1,105.0	3,480.2	5.52	83.6	397.5
+D+0.750L+0.750S+H						1.00	1.00	1.00	0.967	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.30 ft	1		0.496	0.318	1.15	1.00	1.00	1.00	0.967	1.00	1.00	1.00	39.32	1,588.6	3,201.8	7.66	116.1	365.7
+D+0.60W+H						1.00	1.00	1.00	0.967	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.30 ft	1		0.159	0.102	1.60	1.00	1.00	1.00	0.967	1.00	1.00	1.00	17.57	709.8	4,454.6	3.42	51.8	508.8
+D+0.750Lr+0.750L+0.450W+						1.00	1.00	1.00	0.967	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.30 ft	1		0.248	0.164	1.60	1.00	1.00	1.00	0.967	1.00	1.00	1.00	27.35	1,105.0	4,454.6	5.52	83.6	508.8
+D+0.750L+0.750S+0.450W+						1.00	1.00	1.00	0.967	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.30 ft	1		0.357	0.228	1.60	1.00	1.00	1.00	0.967	1.00	1.00	1.00	39.32	1,588.6	4,454.6	7.66	116.1	508.8
+0.60D+0.60W+0.60H						1.00	1.00	1.00	0.967	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.30 ft	1		0.096	0.061	1.60	1.00	1.00	1.00	0.967	1.00	1.00	1.00	10.54	425.9	4,454.6	2.05	31.1	508.8
+D+0.70E+0.60H						1.00	1.00	1.00	0.967	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.30 ft	1		0.248	0.130	1.60	1.00	1.00	1.00	0.967	1.00	1.00	1.00	27.35	1,104.9	4,454.6	4.36	66.0	508.8
+D-0.70E+0.60H						1.00	1.00	1.00	0.967	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.30 ft	1		0.086	0.074	1.60	1.00	1.00	1.00	0.967	1.00	1.00	1.00	9.52	384.8	4,454.6	2.49	37.7	508.8
+D+0.750L+0.750S+0.5250E+						1.00	1.00	1.00	0.967	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.30 ft	1		0.422	0.249	1.60	1.00	1.00	1.00	0.967	1.00	1.00	1.00	46.58	1,882.0	4,454.6	8.36	126.7	508.8
+D+0.750L+0.750S-0.5250E+						1.00	1.00	1.00	0.967	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.30 ft	1		0.294	0.207	1.60	1.00	1.00	1.00	0.967	1.00	1.00	1.00	32.40	1,309.2	4,454.6	6.96	105.5	508.8
+0.60D+0.70E+H						1.00	1.00	1.00	0.967	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.30 ft	1		0.185	0.089	1.60	1.00	1.00	1.00	0.967	1.00	1.00	1.00	20.37	823.2	4,454.6	2.99	45.3	508.8
+0.60D-0.70E+H						1.00	1.00	1.00	0.967	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.30 ft	1		0.036	0.040	1.60	1.00	1.00	1.00	0.967	1.00	1.00	1.00	3.93	158.6	4,454.6	1.36	20.6	508.8
+1.140D+0.70E						1.00	1.00	1.00	0.967	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.30 ft	1		0.270	0.144	1.60	1.00	1.00	1.00	0.967	1.00	1.00	1.00	29.79	1,203.5	4,454.6	4.83	73.2	508.8
+1.140D-0.70E						1.00	1.00	1.00	0.967	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.30 ft	1		0.106	0.088	1.60	1.00	1.00	1.00	0.967	1.00	1.00	1.00	11.69	472.2	4,454.6	2.97	44.9	508.8
+1.105D+0.750L+0.750S+0.52						1.00	1.00	1.00	0.967	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.30 ft	1		0.439	0.260	1.60	1.00	1.00	1.00	0.967	1.00	1.00	1.00	48.42	1,956.5	4,454.6	8.72	132.2	508.8
+1.105D+0.750L+0.750S-0.52						1.00	1.00	1.00	0.967	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.30 ft	1		0.310	0.218	1.60	1.00	1.00	1.00	0.967	1.00	1.00	1.00	34.21	1,382.3	4,454.6	7.32	111.0	508.8
+0.460D+0.70E						1.00	1.00	1.00	0.967	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.30 ft	1		0.163	0.076	1.60	1.00	1.00	1.00	0.967	1.00	1.00	1.00	17.93	724.6	4,454.6	2.54	38.5	508.8
+0.460D-0.70E						1.00	1.00	1.00	0.967	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.30 ft	1		0.019	0.037	1.60	1.00	1.00	1.00	0.967	1.00	1.00	1.00	2.12	85.6	4,454.6	1.26	19.1	508.8

### Overall Maximum Deflections

Load Combination	Span	Max. "-" Defl	Location in Span	Load Combination	Max. "+" Defl	Location in Span
+D+0.750L+0.750S+0.5250E+H	1	0.5591	9.217		0.0000	0.000

**Wood Beam**

Project File: beam calcs with overstrength.ec6

LIC# : KW-06017913, Build:20.24.08.01

MULHERN &amp; KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

**DESCRIPTION: B2-8 OS 303****Vertical Reactions**

Support notation : Far left is #1

Values in KIPS

Load Combination	Support 1	Support 2
Max Upward from all Load Conditions	9.700	7.832
Max Upward from Load Combinations	9.700	7.832
Max Upward from Load Cases	3.986	2.944
Max Downward from all Load Conditio	-1.334	-1.866
Max Downward from Load Cases (Resis	-1.334	-1.866
+D+H	3.986	2.944
+D+L+H	7.442	5.730
+D+Lr+H	3.986	2.944
+D+S+H	7.214	5.369
+D+0.750Lr+0.750L+H	6.578	5.033
+D+0.750L+0.750S+H	9.000	6.852
+D+0.60W+H	3.986	2.944
+D+0.750Lr+0.750L+0.450W+H	6.578	5.033
+D+0.750L+0.750S+0.450W+H	9.000	6.852
+0.60D+0.60W+0.60H	2.391	1.766
+D+0.70E+0.60H	4.920	4.250
+D-0.70E+0.60H	3.052	1.637
+D+0.750L+0.750S+0.5250E+H	9.700	7.832
+D+0.750L+0.750S-0.5250E+H	8.299	5.873
+0.60D+0.70E+H	3.325	3.072
+0.60D-0.70E+H	1.458	0.460
D Only	3.986	2.944
L Only	3.457	2.786
S Only	3.229	2.425
E Only	1.334	1.866
E Only * -1.0	-1.334	-1.866
H Only		

# Wood Beam

Project File: beam calcs with overstrength.ecb

LIC#: KW-06017913, Build:20.24.08.01

MULHERN & KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

**DESCRIPTION:** B2-8 OS 309


## CODE REFERENCES

Calculations per NDS 2018, IBC 2021, ASCE 7-16

Load Combination Set : ASCE 7-16

## Material Properties

Analysis Method :	Allowable Stress Design	Fb +	2,880.0 psi	E : Modulus of Elasticity	
Load Combination :	ASCE 7-16	Fb -	2,220.0 psi	Ebend- xx	1,800.0ksi
		Fc - Prll	1,980.0 psi	Eminbend - xx	950.0ksi
Wood Species :	24-V4 GLB OS	Fc - Perp	780.0 psi	Ebend- yy	ksi
Wood Grade :	GLB - Western	Fv	318.0 psi	Eminbend - yy	ksi
		Ft	318.0 psi	Density	35.0pcf
Beam Bracing :	Beam is Fully Braced against lateral-torsional buckling				



## Applied Loads

Service loads entered. Load Factors will be applied for calculations.

Beam self weight calculated and added to loading

Load for Span Number 1

- Uniform Load : D = 0.360, L = 0.450, S = 0.250 k/ft, Extent = 0.0 -->> 4.0 ft, Tributary Width = 1.0 ft
- Uniform Load : D = 0.420, L = 0.450, S = 0.380 k/ft, Extent = 4.0 -->> 4.60 ft, Tributary Width = 1.0 ft
- Uniform Load : D = 0.150, L = 0.290, S = 0.10 k/ft, Extent = 4.60 -->> 10.40 ft, Tributary Width = 1.0 ft
- Uniform Load : D = 0.360, L = 0.290, S = 0.380 k/ft, Extent = 10.40 -->> 10.60 ft, Tributary Width = 1.0 ft
- Uniform Load : D = 0.150, L = 0.290, S = 0.10 k/ft, Extent = 10.60 -->> 18.30 ft, Tributary Width = 1.0 ft
- Point Load : D = 0.60, L = 0.20, S = 0.10 k @ 3.70 ft
- Point Load : D = 0.40, S = 0.90 k @ 4.40 ft
- Point Load : D = 0.80, S = 2.0 k @ 10.40 ft
- Point Load : D = 0.50, E = 2.20 k @ 3.70 ft

## DESIGN SUMMARY

Design OK

<b>Maximum Bending Stress Ratio</b>	=	<b>0.459</b> : 1	<b>Maximum Shear Stress Ratio</b>	=	<b>0.319</b> : 1
Section used for this span		<b>5.5x18</b>	Section used for this span		<b>5.5x18</b>
fb: Actual	=	1,468.99psi	fv: Actual	=	116.48 psi
F'b	=	3,201.78psi	F'v	=	365.70 psi
Load Combination	=	+D+0.750L+0.750S+H	Load Combination	=	+D+0.750L+0.750S+H
Location of maximum on span	=	9.618ft	Location of maximum on span	=	0.000 ft
Span # where maximum occurs	=	Span # 1	Span # where maximum occurs	=	Span # 1
<b>Maximum Deflection</b>					
Max Downward Transient Deflection		0.189 in Ratio = 1160 >=360	Span: 1 : S Only		
Max Upward Transient Deflection		0 in Ratio = 0 <360	n/a		
Max Downward Total Deflection		0.489 in Ratio = 449 >=180	Span: 1 : +D+0.750L+0.750S+0.5250E+H		
Max Upward Total Deflection		0 in Ratio = 0 <180	n/a		

## Maximum Forces & Stresses for Load Combinations

Load Combination	Segment Length	Span #	Max Stress Ratios										Moment Values			Shear Values				
			M	V	CD	CM	C <sub>t</sub>	CLx	C <sub>v</sub>	C <sub>fu</sub>	C <sub>i</sub>	C <sub>r</sub>	M	fb	F'b	V	fv	F'v		
+D+H	Length = 18.30 ft	1	0.238	0.182	0.90	1.00	1.00	1.00	1.00	0.967	1.00	1.00	1.00	14.73	595.3	2,505.7	0.0	0.00	0.0	0.0

# Wood Beam

Project File: beam calcs with overstrength.ec6

LIC#: KW-06017913, Build:20.24.08.01

MULHERN & KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

## DESCRIPTION: B2-8 OS 309

### Maximum Forces & Stresses for Load Combinations

Load Combination	Segment Length	Span #	Max Stress Ratios									Moment Values			Shear Values			
			M	V	CD	CM	C <sub>t</sub>	CLx	C <sub>v</sub>	C <sub>fu</sub>	C <sub>i</sub>	C <sub>r</sub>	M	fb	F'b	V	fv	F'v
+D+L+H						1.00	1.00	1.00	0.967	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.30 ft	1		0.408	0.297	1.00	1.00	1.00	1.00	0.967	1.00	1.00	1.00	28.12	1,136.2	2,784.2	6.24	94.6	318.0
+D+Lr+H						1.00	1.00	1.00	0.967	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.30 ft	1		0.171	0.131	1.25	1.00	1.00	1.00	0.967	1.00	1.00	1.00	14.73	595.3	3,480.2	3.45	52.2	397.5
+D+S+H						1.00	1.00	1.00	0.967	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.30 ft	1		0.385	0.261	1.15	1.00	1.00	1.00	0.967	1.00	1.00	1.00	30.50	1,232.3	3,201.8	6.31	95.6	365.7
+D+0.750Lr+0.750L+H						1.00	1.00	1.00	0.967	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.30 ft	1		0.288	0.211	1.25	1.00	1.00	1.00	0.967	1.00	1.00	1.00	24.77	1,001.0	3,480.2	5.54	84.0	397.5
+D+0.750L+0.750S+H						1.00	1.00	1.00	0.967	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.30 ft	1		0.459	0.319	1.15	1.00	1.00	1.00	0.967	1.00	1.00	1.00	36.36	1,469.0	3,201.8	7.69	116.5	365.7
+D+0.60W+H						1.00	1.00	1.00	0.967	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.30 ft	1		0.134	0.103	1.60	1.00	1.00	1.00	0.967	1.00	1.00	1.00	14.73	595.3	4,454.6	3.45	52.2	508.8
+D+0.750Lr+0.750L+0.450W+						1.00	1.00	1.00	0.967	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.30 ft	1		0.225	0.165	1.60	1.00	1.00	1.00	0.967	1.00	1.00	1.00	24.77	1,001.0	4,454.6	5.54	84.0	508.8
+D+0.750L+0.750S+0.450W+l						1.00	1.00	1.00	0.967	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.30 ft	1		0.330	0.229	1.60	1.00	1.00	1.00	0.967	1.00	1.00	1.00	36.36	1,469.0	4,454.6	7.69	116.5	508.8
+0.60D+0.60W+0.60H						1.00	1.00	1.00	0.967	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.30 ft	1		0.080	0.062	1.60	1.00	1.00	1.00	0.967	1.00	1.00	1.00	8.84	357.2	4,454.6	2.07	31.3	508.8
+D+0.70E+0.60H						1.00	1.00	1.00	0.967	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.30 ft	1		0.163	0.139	1.60	1.00	1.00	1.00	0.967	1.00	1.00	1.00	18.01	727.9	4,454.6	4.67	70.8	508.8
+D-0.70E+0.60H						1.00	1.00	1.00	0.967	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.30 ft	1		0.109	0.066	1.60	1.00	1.00	1.00	0.967	1.00	1.00	1.00	12.01	485.3	4,454.6	2.22	33.6	508.8
+D+0.750L+0.750S+0.5250E+						1.00	1.00	1.00	0.967	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.30 ft	1		0.349	0.256	1.60	1.00	1.00	1.00	0.967	1.00	1.00	1.00	38.44	1,553.2	4,454.6	8.61	130.4	508.8
+D+0.750L+0.750S-0.5250E+l						1.00	1.00	1.00	0.967	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.30 ft	1		0.312	0.201	1.60	1.00	1.00	1.00	0.967	1.00	1.00	1.00	34.39	1,389.6	4,454.6	6.77	102.5	508.8
+0.60D+0.70E+H						1.00	1.00	1.00	0.967	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.30 ft	1		0.112	0.098	1.60	1.00	1.00	1.00	0.967	1.00	1.00	1.00	12.31	497.2	4,454.6	3.30	49.9	508.8
+0.60D-0.70E+H						1.00	1.00	1.00	0.967	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.30 ft	1		0.056	0.036	1.60	1.00	1.00	1.00	0.967	1.00	1.00	1.00	6.22	251.2	4,454.6	1.20	18.1	508.8
+1.140D+0.70E						1.00	1.00	1.00	0.967	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.30 ft	1		0.182	0.154	1.60	1.00	1.00	1.00	0.967	1.00	1.00	1.00	20.04	809.8	4,454.6	5.16	78.1	508.8
+1.140D-0.70E						1.00	1.00	1.00	0.967	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.30 ft	1		0.127	0.080	1.60	1.00	1.00	1.00	0.967	1.00	1.00	1.00	14.04	567.3	4,454.6	2.70	40.9	508.8
+1.105D+0.750L+0.750S+0.52						1.00	1.00	1.00	0.967	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.30 ft	1		0.363	0.267	1.60	1.00	1.00	1.00	0.967	1.00	1.00	1.00	39.99	1,615.6	4,454.6	8.97	135.9	508.8
+1.105D+0.750L+0.750S-0.52						1.00	1.00	1.00	0.967	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.30 ft	1		0.326	0.212	1.60	1.00	1.00	1.00	0.967	1.00	1.00	1.00	35.92	1,451.3	4,454.6	7.13	108.0	508.8
+0.460D+0.70E						1.00	1.00	1.00	0.967	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.30 ft	1		0.094	0.084	1.60	1.00	1.00	1.00	0.967	1.00	1.00	1.00	10.38	419.6	4,454.6	2.81	42.6	508.8
+0.460D-0.70E						1.00	1.00	1.00	0.967	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.30 ft	1		0.038	0.029	1.60	1.00	1.00	1.00	0.967	1.00	1.00	1.00	4.19	169.4	4,454.6	0.99	15.0	508.8

### Overall Maximum Deflections

Load Combination	Span	Max. "-" Defl	Location in Span	Load Combination	Max. "+" Defl	Location in Span
+D+0.750L+0.750S+0.5250E+H	1	0.4890	8.950		0.0000	0.000

**Wood Beam**

Project File: beam calcs with overstrength.ec6

LIC# : KW-06017913, Build:20.24.08.01

MULHERN &amp; KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

**DESCRIPTION: B2-8 OS 309****Vertical Reactions**

Support notation : Far left is #1

Values in KIPS

Load Combination	Support 1	Support 2
Max Upward from all Load Conditions	9.945	6.662
Max Upward from Load Combinations	9.945	6.662
Max Upward from Load Cases	4.009	2.786
Max Downward from all Load Conditio	-1.755	-0.445
Max Downward from Load Cases (Resis	-1.755	-0.445
+D+H	4.009	2.520
+D+L+H	7.466	5.306
+D+Lr+H	4.009	2.520
+D+S+H	7.238	4.945
+D+0.750Lr+0.750L+H	6.602	4.610
+D+0.750L+0.750S+H	9.023	6.429
+D+0.60W+H	4.009	2.520
+D+0.750Lr+0.750L+0.450W+H	6.602	4.610
+D+0.750L+0.750S+0.450W+H	9.023	6.429
+0.60D+0.60W+0.60H	2.406	1.512
+D+0.70E+0.60H	5.238	2.831
+D-0.70E+0.60H	2.781	2.208
+D+0.750L+0.750S+0.5250E+H	9.945	6.662
+D+0.750L+0.750S-0.5250E+H	8.102	6.195
+0.60D+0.70E+H	3.634	1.823
+0.60D-0.70E+H	1.177	1.201
D Only	4.009	2.520
L Only	3.457	2.786
S Only	3.229	2.425
E Only	1.755	0.445
E Only * -1.0	-1.755	-0.445
H Only		

# Wood Beam

Project File: beam calcs with overstrength.ec6

LIC# : KW-06017913, Build:20.24.08.01

MULHERN & KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

**DESCRIPTION:** H2-9 OS 309


## CODE REFERENCES

Calculations per NDS 2018, IBC 2021, ASCE 7-16

Load Combination Set : ASCE 7-16

## Material Properties

Analysis Method :	Allowable Stress Design	Fb +	2,880.0 psi	E : Modulus of Elasticity	
Load Combination :	ASCE 7-16	Fb -	2,220.0 psi	Ebend- xx	1,800.0ksi
		Fc - Prll	1,980.0 psi	Eminbend - xx	950.0ksi
Wood Species :	24-V4 GLB OS	Fc - Perp	780.0 psi	Ebend- yy	ksi
Wood Grade :	GLB - Western	Fv	318.0 psi	Eminbend - yy	ksi
		Ft	318.0 psi	Density	35.0pcf
Beam Bracing :	Beam is Fully Braced against lateral-torsional buckling				



## Applied Loads

Service loads entered. Load Factors will be applied for calculations.

Beam self weight calculated and added to loading

Load for Span Number 1

- Uniform Load : D = 0.280, L = 0.160, S = 0.270 k/ft, Extent = 0.0 -->> 1.0 ft, Tributary Width = 1.0 ft
- Uniform Load : D = 0.320, L = 0.160, S = 0.370 k/ft, Extent = 1.0 -->> 1.70 ft, Tributary Width = 1.0 ft
- Uniform Load : D = 0.160, L = 0.160, S = 0.240 k/ft, Extent = 1.70 -->> 2.70 ft, Tributary Width = 1.0 ft
- Uniform Load : D = 0.10, S = 0.240 k/ft, Extent = 2.70 -->> 16.30 ft, Tributary Width = 1.0 ft
- Point Load : D = 0.90, L = 0.20, S = 1.0 k @ 1.70 ft
- Point Load : D = 0.50, E = 2.20 k @ 1.70 ft

## DESIGN SUMMARY

**Design OK**

Maximum Bending Stress Ratio	=	<b>0.391</b> : 1	Maximum Shear Stress Ratio	=	<b>0.310</b> : 1
Section used for this span		<b>5.5x12</b>	Section used for this span		<b>5.5x12</b>
fb: Actual	=	1,296.59psi	fv: Actual	=	113.47 psi
F'b	=	3,312.00psi	F'v	=	365.70 psi
Load Combination		+D+S+H	Load Combination		+D+S+H
Location of maximum on span	=	7.377ft	Location of maximum on span	=	0.000 ft
Span # where maximum occurs	=	Span # 1	Span # where maximum occurs	=	Span # 1
<b>Maximum Deflection</b>					
Max Downward Transient Deflection		0.306 in Ratio = <b>639</b> >=360	Span: 1 : S Only		
Max Upward Transient Deflection		0 in Ratio = <b>0</b> <360	n/a		
Max Downward Total Deflection		0.492 in Ratio = <b>397</b> >=180	Span: 1 : +D+S+H		
Max Upward Total Deflection		0 in Ratio = <b>0</b> <180	n/a		

## Maximum Forces & Stresses for Load Combinations

Load Combination	Segment Length	Span #	Max Stress Ratios										Moment Values			Shear Values			
			M	V	CD	CM	C <sub>t</sub>	CLx	C <sub>y</sub>	C <sub>fu</sub>	C <sub>i</sub>	C <sub>r</sub>	M	fb	F'b	V	fv	F'v	
+D+H	Length = 16.30 ft	1	0.189	0.181	0.90	1.00	1.00	1.00	1.000	1.00	1.00	1.00	5.39	489.7	2,592.0	0.0	0.00	0.0	0.0
+D+L+H	Length = 16.30 ft	1	0.188	0.194	1.00	1.00	1.00	1.00	1.000	1.00	1.00	1.00	5.95	540.6	2,880.0	0.0	0.00	0.0	0.0

# Wood Beam

Project File: beam calcs with overstrength.ec6

LIC# : KW-06017913, Build:20.24.08.01

MULHERN & KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

## DESCRIPTION: H2-9 OS 309

### Maximum Forces & Stresses for Load Combinations

Load Combination	Segment Length	Span #	Max Stress Ratios									Moment Values			Shear Values			
			M	V	CD	CM	C <sub>t</sub>	CLx	C <sub>y</sub>	C <sub>fu</sub>	C <sub>i</sub>	C <sub>r</sub>	M	fb	F'b	V	fv	F'v
+D+Lr+H	Length = 16.30 ft	1	0.136	0.131	1.25	1.00	1.00	1.00	1.000	1.00	1.00	1.00	5.39	489.7	3,600.0	2.29	51.9	397.5
+D+S+H	Length = 16.30 ft	1	0.391	0.310	1.15	1.00	1.00	1.00	1.000	1.00	1.00	1.00	14.26	1,296.6	3,312.0	4.99	113.5	365.7
+D+0.750Lr+0.750L+H	Length = 16.30 ft	1	0.147	0.149	1.25	1.00	1.00	1.00	1.000	1.00	1.00	1.00	5.80	527.6	3,600.0	2.60	59.2	397.5
+D+0.750L+0.750S+H	Length = 16.30 ft	1	0.341	0.288	1.15	1.00	1.00	1.00	1.000	1.00	1.00	1.00	12.42	1,129.4	3,312.0	4.63	105.3	365.7
+D+0.60W+H	Length = 16.30 ft	1	0.106	0.102	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	5.39	489.7	4,608.0	2.29	51.9	508.8
+D+0.750Lr+0.750L+0.450W+	Length = 16.30 ft	1	0.115	0.116	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	5.80	527.6	4,608.0	2.60	59.2	508.8
+D+0.750L+0.750S+0.450W+I	Length = 16.30 ft	1	0.245	0.207	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	12.42	1,129.4	4,608.0	4.63	105.3	508.8
+0.60D+0.60W+0.60H	Length = 16.30 ft	1	0.064	0.061	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	3.23	293.8	4,608.0	1.37	31.2	508.8
+D+0.70E+0.60H	Length = 16.30 ft	1	0.139	0.164	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	7.05	640.5	4,608.0	3.66	83.3	508.8
+D-0.70E+0.60H	Length = 16.30 ft	1	0.078	0.040	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	3.95	359.1	4,608.0	0.91	20.6	508.8
+D+0.750L+0.750S+0.5250E+	Length = 16.30 ft	1	0.267	0.253	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	13.55	1,232.0	4,608.0	5.67	128.8	508.8
+D+0.750L+0.750S-0.5250E+I	Length = 16.30 ft	1	0.224	0.161	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	11.34	1,031.3	4,608.0	3.60	81.8	508.8
+0.60D+0.70E+H	Length = 16.30 ft	1	0.098	0.123	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	4.96	451.4	4,608.0	2.75	62.5	508.8
+0.60D-0.70E+H	Length = 16.30 ft	1	0.037	0.024	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	1.87	170.0	4,608.0	0.54	12.3	508.8
+1.140D+0.70E	Length = 16.30 ft	1	0.154	0.178	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	7.79	707.8	4,608.0	3.98	90.6	508.8
+1.140D-0.70E	Length = 16.30 ft	1	0.093	0.055	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	4.69	426.4	4,608.0	1.23	27.9	508.8
+1.105D+0.750L+0.750S+0.52	Length = 16.30 ft	1	0.279	0.264	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	14.12	1,283.4	4,608.0	5.91	134.3	508.8
+1.105D+0.750L+0.750S-0.52	Length = 16.30 ft	1	0.235	0.171	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	11.91	1,082.3	4,608.0	3.84	87.2	508.8
+0.460D+0.70E	Length = 16.30 ft	1	0.084	0.109	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	4.27	387.9	4,608.0	2.43	55.2	508.8
+0.460D-0.70E	Length = 16.30 ft	1	0.023	0.020	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	1.17	106.5	4,608.0	0.45	10.3	508.8

### Overall Maximum Deflections

Load Combination	Span	Max. "-" Defl	Location in Span	Load Combination	Max. "+" Defl	Location in Span
+D+S+H	1	0.4924	7.972		0.0000	0.000

### Vertical Reactions

Support notation : Far left is #1

Values in KIPS

Load Combination	Support 1	Support 2
Max Upward from all Load Conditions	6.257	3.187
Max Upward from Load Combinations	6.257	3.187

**Wood Beam**

Project File: beam calcs with overstrength.ec6

LIC# : KW-06017913, Build:20.24.08.01

MULHERN &amp; KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

**DESCRIPTION: H2-9 OS 309****Vertical Reactions**

Support notation : Far left is #1

Values in KIPS

Load Combination	Support 1	Support 2
Max Upward from Load Cases	2.964	2.069
Max Downward from all Load Conditio	-1.971	-0.229
Max Downward from Load Cases (Resis	-1.971	-0.229
+D+H	2.567	1.118
+D+L+H	3.143	1.175
+D+Lr+H	2.567	1.118
+D+S+H	5.532	3.187
+D+0.750Lr+0.750L+H	2.999	1.161
+D+0.750L+0.750S+H	5.222	2.712
+D+0.60W+H	2.567	1.118
+D+0.750Lr+0.750L+0.450W+H	2.999	1.161
+D+0.750L+0.750S+0.450W+H	5.222	2.712
+0.60D+0.60W+0.60H	1.540	0.671
+D+0.70E+0.60H	3.947	1.279
+D-0.70E+0.60H	1.188	0.958
+D+0.750L+0.750S+0.5250E+H	6.257	2.833
+D+0.750L+0.750S-0.5250E+H	4.188	2.592
+0.60D+0.70E+H	2.920	0.831
+0.60D-0.70E+H	0.161	0.510
D Only	2.567	1.118
L Only	0.575	0.057
S Only	2.964	2.069
E Only	1.971	0.229
E Only * -1.0	-1.971	-0.229
H Only		

# Steel Beam

Project File: beam calcs with overstrength.ec6

LIC#: KW-06017913, Build:20.24.08.01

MULHERN & KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

**DESCRIPTION:** B2-18 OS 303


## CODE REFERENCES

Calculations per AISC 360-16, IBC 2021, ASCE 7-16

Load Combination Set : ASCE 7-16

## Material Properties

Analysis Method : Allowable Strength Design	Fy : Steel Yield :	50.0 ksi
Beam Bracing : Beam is Fully Braced against lateral-torsional buckling	E: Modulus :	29,000.0 ksi
Bending Axis : Major Axis Bending		



## Applied Loads

Service loads entered. Load Factors will be applied for calculations.

Beam self weight calculated and added to loading  
Load for Span Number 1

- Uniform Load : D = 0.180, L = 0.180 k/ft, Extent = 0.0 -->> 8.40 ft, Tributary Width = 1.0 ft
- Uniform Load : D = 0.060, S = 0.130 k/ft, Extent = 8.40 -->> 10.40 ft, Tributary Width = 1.0 ft
- Uniform Load : D = 0.180, S = 0.180 k/ft, Extent = 10.40 -->> 14.10 ft, Tributary Width = 1.0 ft
- Uniform Load : D = 0.060, S = 0.130 k/ft, Extent = 14.10 -->> 22.0 ft, Tributary Width = 1.0 ft
- Point Load : D = 0.10, S = 0.10 k @ 8.40 ft
- Point Load : D = 0.10, S = 0.10 k @ 10.40 ft
- Point Load : D = 3.0, L = 2.80, S = 4.60 k @ 14.10 ft
- Point Load : D = 0.90, E = 3.20 k @ 14.10 ft

## DESIGN SUMMARY

**Design OK**

Maximum Bending Stress Ratio =	<b>0.509</b> : 1	Maximum Shear Stress Ratio =	<b>0.156</b> : 1
Section used for this span	<b>W10x49</b>	Section used for this span	<b>W10x49</b>
Ma : Applied	76.687 k-ft	Va : Applied	10.575 k
Mn / Omega : Allowable	150.699 k-ft	Vn/Omega : Allowable	68.0 k
Load Combination	+1.105D+0.750L+0.750S+0.5250E	Load Combination	+1.105D+0.750L+0.750S+0.5250E
Location of maximum on span	22.000 ft	Location of maximum on span	22.000 ft
Span # where maximum occurs	Span # 1	Span # where maximum occurs	Span # 1
Maximum Deflection			
Max Downward Transient Deflection	0.279 in Ratio =	<b>944</b> >=360	Span: 1 : S Only
Max Upward Transient Deflection	0 in Ratio =	<b>0</b> <360	n/a
Max Downward Total Deflection	0.703 in Ratio =	<b>376</b> >=180	Span: 1 : +D+0.750L+0.750S+0.5250E+H
Max Upward Total Deflection	0 in Ratio =	<b>0</b> <180	n/a

## Maximum Forces & Stresses for Load Combinations

Load Combination	Segment Length	Span #	Max Stress Ratios		Summary of Moment Values					Summary of Shear Values				
			M	V	Mmax +	Mmax -	Ma Max	Mnx	Mnx/Omega	Cb	Rm	Va Max	Vnx	Vnx/Omega
+D+H	Dsgn. L = 22.00 ft	1	0.199	0.062	29.95		29.95	251.67	150.70	1.00	1.00	4.22	102.00	68.00
+D+L+H	Dsgn. L = 22.00 ft	1	0.308	0.093	46.40		46.40	251.67	150.70	1.00	1.00	6.31	102.00	68.00
+D+Lr+H	Dsgn. L = 22.00 ft	1	0.199	0.062	29.95		29.95	251.67	150.70	1.00	1.00	4.22	102.00	68.00
+D+S+H	Dsgn. L = 22.00 ft	1	0.400	0.126	60.30		60.30	251.67	150.70	1.00	1.00	8.58	102.00	68.00
+D+0.750Lr+0.750L+H	Dsgn. L = 22.00 ft	1	0.281	0.085	42.29		42.29	251.67	150.70	1.00	1.00	5.79	102.00	68.00
+D+0.750L+0.750S+H	Dsgn. L = 22.00 ft	1	0.432	0.133	65.05		65.05	251.67	150.70	1.00	1.00	9.05	102.00	68.00
+D+0.60W+H	Dsgn. L = 22.00 ft	1	0.199	0.062	29.95		29.95	251.67	150.70	1.00	1.00	4.22	102.00	68.00
+D+0.750Lr+0.750L+0.450W+H	Dsgn. L = 22.00 ft	1	0.281	0.085	42.29		42.29	251.67	150.70	1.00	1.00	5.79	102.00	68.00

# Steel Beam

Project File: beam calcs with overstrength.ec6

LIC# : KW-06017913, Build:20.24.08.01

MULHERN & KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

## DESCRIPTION: B2-18 OS 303

### Maximum Forces & Stresses for Load Combinations

Load Combination	Segment Length	Span #	Max Stress Ratios		Summary of Moment Values					Summary of Shear Values				
			M	V	Mmax +	Mmax -	Ma Max	Mnx	Mnx/Omega Cb	Rm	Va Max	Vnx	Vnx/Omega	
+D+0.750L+0.750S+0.450W+H	Dsgn. L = 22.00 ft	1	0.432	0.133	65.05		65.05	251.67	150.70	1.00	1.00	9.05	102.00	68.00
+0.60D+0.60W+0.60H	Dsgn. L = 22.00 ft	1	0.119	0.037	17.97		17.97	251.67	150.70	1.00	1.00	2.53	102.00	68.00
+D+0.70E+0.60H	Dsgn. L = 22.00 ft	1	0.274	0.083	41.28		41.28	251.67	150.70	1.00	1.00	5.66	102.00	68.00
+D-0.70E+0.60H	Dsgn. L = 22.00 ft	1	0.125	0.043	18.78		18.78	251.67	150.70	1.00	1.00	2.92	102.00	68.00
+D+0.750L+0.750S+0.5250E+H	Dsgn. L = 22.00 ft	1	0.488	0.149	73.54		73.54	251.67	150.70	1.00	1.00	10.13	102.00	68.00
+D+0.750L+0.750S-0.5250E+H	Dsgn. L = 22.00 ft	1	0.375	0.117	56.55		56.55	251.67	150.70	1.00	1.00	7.98	102.00	68.00
+0.60D+0.70E+H	Dsgn. L = 22.00 ft	1	0.194	0.058	29.30		29.30	251.67	150.70	1.00	1.00	3.97	102.00	68.00
+0.60D-0.70E+H	Dsgn. L = 22.00 ft	1	0.050	0.021	7.48		7.48	251.67	150.70	1.00	1.00	1.43	102.00	68.00
+1.140D+0.70E	Dsgn. L = 22.00 ft	1	0.302	0.092	45.47		45.47	251.67	150.70	1.00	1.00	6.25	102.00	68.00
+1.140D-0.70E	Dsgn. L = 22.00 ft	1	0.152	0.051	22.89		22.89	251.67	150.70	1.00	1.00	3.44	102.00	68.00
+1.105D+0.750L+0.750S+0.5250E	Dsgn. L = 22.00 ft	1	0.509	0.156	76.69		76.69	251.67	150.70	1.00	1.00	10.57	102.00	68.00
+1.105D+0.750L+0.750S-0.5250E	Dsgn. L = 22.00 ft	1	0.396	0.124	59.70		59.70	251.67	150.70	1.00	1.00	8.42	102.00	68.00
+0.460D+0.70E	Dsgn. L = 22.00 ft	1	0.167	0.050	25.10		25.10	251.67	150.70	1.00	1.00	3.38	102.00	68.00
+0.460D-0.70E	Dsgn. L = 22.00 ft	1	0.026	0.013	3.93		3.93	251.67	150.70	1.00	1.00	0.91	102.00	68.00

### Overall Maximum Deflections

Load Combination	Span	Max. "-" Defl	Location in Span	Load Combination	Max. "+" Defl	Location in Span
+D+0.750L+0.750S+0.5250E+H	1	0.7026	11.566		0.0000	0.000

### Vertical Reactions

Support notation : Far left is #1

Values in KIPS

Load Combination	Support 1	Support 2
Max Upward from all Load Conditions	7.797	10.131
Max Upward from Load Combinations	7.797	10.131
Max Upward from Load Cases	3.726	4.358
Max Downward from all Load Conditions (Resistii	-1.149	-2.051
Max Downward from Load Cases (Resisting Uplii	-1.149	-2.051
+D+H	3.726	4.224
+D+L+H	5.955	6.307
+D+Lr+H	3.726	4.224
+D+S+H	6.121	8.582
+D+0.750Lr+0.750L+H	5.398	5.786
+D+0.750L+0.750S+H	7.194	9.055
+D+0.60W+H	3.726	4.224
+D+0.750Lr+0.750L+0.450W+H	5.398	5.786
+D+0.750L+0.750S+0.450W+H	7.194	9.055
+0.60D+0.60W+0.60H	2.236	2.534
+D+0.70E+0.60H	4.531	5.659
+D-0.70E+0.60H	2.922	2.788
+D+0.750L+0.750S+0.5250E+H	7.797	10.131
+D+0.750L+0.750S-0.5250E+H	6.591	7.978
+0.60D+0.70E+H	3.040	3.970
+0.60D-0.70E+H	1.431	1.099
D Only	3.726	4.224
L Only	2.229	2.083
S Only	2.395	4.358
E Only	1.149	2.051
E Only * -1.0	-1.149	-2.051
H Only		

# Steel Beam

Project File: beam calcs with overstrength.ec6

LIC#: KW-06017913, Build:20.24.08.01

MULHERN & KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

**DESCRIPTION:** B2-18 OS 311


## CODE REFERENCES

Calculations per AISC 360-16, IBC 2021, ASCE 7-16

Load Combination Set : ASCE 7-16

## Material Properties

Analysis Method : Allowable Strength Design	Fy : Steel Yield :	50.0 ksi
Beam Bracing : Beam is Fully Braced against lateral-torsional buckling	E: Modulus :	29,000.0 ksi
Bending Axis : Major Axis Bending		



## Applied Loads

Service loads entered. Load Factors will be applied for calculations.

Beam self weight calculated and added to loading  
Load for Span Number 1

- Uniform Load : D = 0.180, L = 0.180 k/ft, Extent = 0.0 --> 8.40 ft, Tributary Width = 1.0 ft
- Uniform Load : D = 0.060, S = 0.130 k/ft, Extent = 8.40 --> 10.40 ft, Tributary Width = 1.0 ft
- Uniform Load : D = 0.180, S = 0.180 k/ft, Extent = 10.40 --> 14.10 ft, Tributary Width = 1.0 ft
- Uniform Load : D = 0.060, S = 0.130 k/ft, Extent = 14.10 --> 22.0 ft, Tributary Width = 1.0 ft
- Point Load : D = 0.10, S = 0.10 k @ 8.40 ft
- Point Load : D = 0.10, S = 0.10 k @ 10.40 ft
- Point Load : D = 3.0, L = 2.80, S = 4.60 k @ 14.10 ft
- Point Load : D = 0.80, E = 3.30 k @ 14.10 ft

## DESIGN SUMMARY

**Design OK**

Maximum Bending Stress Ratio =	<b>0.507</b> : 1	Maximum Shear Stress Ratio =	<b>0.155</b> : 1
Section used for this span	<b>W10x49</b>	Section used for this span	<b>W10x49</b>
Ma : Applied	76.394 k-ft	Va : Applied	10.538 k
Mn / Omega : Allowable	150.699 k-ft	Vn/Omega : Allowable	68.0 k
Load Combination	+1.105D+0.750L+0.750S+0.5250E	Load Combination	+1.105D+0.750L+0.750S+0.5250E
Location of maximum on span	22.000 ft	Location of maximum on span	22.000 ft
Span # where maximum occurs	Span # 1	Span # where maximum occurs	Span # 1
Maximum Deflection			
Max Downward Transient Deflection	0.279 in Ratio =	<b>944</b> >=360	Span: 1 : S Only
Max Upward Transient Deflection	0 in Ratio =	<b>0</b> <360	n/a
Max Downward Total Deflection	0.700 in Ratio =	<b>377</b> >=180	Span: 1 : +D+0.750L+0.750S+0.5250E+H
Max Upward Total Deflection	0 in Ratio =	<b>0</b> <180	n/a

## Maximum Forces & Stresses for Load Combinations

Load Combination	Segment Length	Span #	Max Stress Ratios		Summary of Moment Values					Summary of Shear Values				
			M	V	Mmax +	Mmax -	Ma Max	Mnx	Mnx/Omega	Cb	Rm	Va Max	Vnx	Vnx/Omega
+D+H	Dsgn. L = 22.00 ft	1	0.195	0.061	29.45		29.45	251.67	150.70	1.00	1.00	4.16	102.00	68.00
+D+L+H	Dsgn. L = 22.00 ft	1	0.305	0.092	45.89		45.89	251.67	150.70	1.00	1.00	6.24	102.00	68.00
+D+Lr+H	Dsgn. L = 22.00 ft	1	0.195	0.061	29.45		29.45	251.67	150.70	1.00	1.00	4.16	102.00	68.00
+D+S+H	Dsgn. L = 22.00 ft	1	0.397	0.125	59.80		59.80	251.67	150.70	1.00	1.00	8.52	102.00	68.00
+D+0.750Lr+0.750L+H	Dsgn. L = 22.00 ft	1	0.277	0.084	41.78		41.78	251.67	150.70	1.00	1.00	5.72	102.00	68.00
+D+0.750L+0.750S+H	Dsgn. L = 22.00 ft	1	0.428	0.132	64.54		64.54	251.67	150.70	1.00	1.00	8.99	102.00	68.00
+D+0.60W+H	Dsgn. L = 22.00 ft	1	0.195	0.061	29.45		29.45	251.67	150.70	1.00	1.00	4.16	102.00	68.00
+D+0.750Lr+0.750L+0.450W+H	Dsgn. L = 22.00 ft	1	0.277	0.084	41.78		41.78	251.67	150.70	1.00	1.00	5.72	102.00	68.00

# Steel Beam

Project File: beam calcs with overstrength.ec6

LIC# : KW-06017913, Build:20.24.08.01

MULHERN & KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

## DESCRIPTION: B2-18 OS 311

### Maximum Forces & Stresses for Load Combinations

Load Combination	Segment Length	Span #	Max Stress Ratios		Summary of Moment Values					Summary of Shear Values				
			M	V	Mmax +	Mmax -	Ma Max	Mnx	Mnx/Omega Cb	Rm	Va Max	Vnx	Vnx/Omega	
+D+0.750L+0.750S+0.450W+H	Dsgn. L = 22.00 ft	1	0.428	0.132	64.54		64.54	251.67	150.70	1.00	1.00	8.99	102.00	68.00
+0.60D+0.60W+0.60H	Dsgn. L = 22.00 ft	1	0.117	0.037	17.67		17.67	251.67	150.70	1.00	1.00	2.50	102.00	68.00
+D+0.70E+0.60H	Dsgn. L = 22.00 ft	1	0.273	0.083	41.13		41.13	251.67	150.70	1.00	1.00	5.64	102.00	68.00
+D-0.70E+0.60H	Dsgn. L = 22.00 ft	1	0.119	0.042	18.00		18.00	251.67	150.70	1.00	1.00	2.86	102.00	68.00
+D+0.750L+0.750S+0.5250E+H	Dsgn. L = 22.00 ft	1	0.486	0.149	73.30		73.30	251.67	150.70	1.00	1.00	10.10	102.00	68.00
+D+0.750L+0.750S-0.5250E+H	Dsgn. L = 22.00 ft	1	0.370	0.116	55.78		55.78	251.67	150.70	1.00	1.00	7.88	102.00	68.00
+0.60D+0.70E+H	Dsgn. L = 22.00 ft	1	0.195	0.058	29.35		29.35	251.67	150.70	1.00	1.00	3.98	102.00	68.00
+0.60D-0.70E+H	Dsgn. L = 22.00 ft	1	0.046	0.020	6.99		6.99	251.67	150.70	1.00	1.00	1.38	102.00	68.00
+1.140D+0.70E	Dsgn. L = 22.00 ft	1	0.300	0.092	45.25		45.25	251.67	150.70	1.00	1.00	6.22	102.00	68.00
+1.140D-0.70E	Dsgn. L = 22.00 ft	1	0.146	0.050	22.01		22.01	251.67	150.70	1.00	1.00	3.38	102.00	68.00
+1.105D+0.750L+0.750S+0.5250E	Dsgn. L = 22.00 ft	1	0.507	0.155	76.39		76.39	251.67	150.70	1.00	1.00	10.54	102.00	68.00
+1.105D+0.750L+0.750S-0.5250E	Dsgn. L = 22.00 ft	1	0.391	0.122	58.87		58.87	251.67	150.70	1.00	1.00	8.32	102.00	68.00
+0.460D+0.70E	Dsgn. L = 22.00 ft	1	0.167	0.050	25.23		25.23	251.67	150.70	1.00	1.00	3.39	102.00	68.00
+0.460D-0.70E	Dsgn. L = 22.00 ft	1	0.024	0.013	3.58		3.58	251.67	150.70	1.00	1.00	0.87	102.00	68.00

### Overall Maximum Deflections

Load Combination	Span	Max. "-" Defl	Location in Span	Load Combination	Max. "+" Defl	Location in Span
+D+0.750L+0.750S+0.5250E+H	1	0.7005	11.566		0.0000	0.000

### Vertical Reactions

Support notation : Far left is #1

Values in KIPS

Load Combination	Support 1	Support 2
Max Upward from all Load Conditions	7.780	10.101
Max Upward from Load Combinations	7.780	10.101
Max Upward from Load Cases	3.690	4.358
Max Downward from all Load Conditions (Resistii	-1.185	-2.115
Max Downward from Load Cases (Resisting Uplii	-1.185	-2.115
+D+H	3.690	4.160
+D+L+H	5.919	6.243
+D+Lr+H	3.690	4.160
+D+S+H	6.085	8.518
+D+0.750Lr+0.750L+H	5.362	5.722
+D+0.750L+0.750S+H	7.158	8.991
+D+0.60W+H	3.690	4.160
+D+0.750Lr+0.750L+0.450W+H	5.362	5.722
+D+0.750L+0.750S+0.450W+H	7.158	8.991
+0.60D+0.60W+0.60H	2.214	2.496
+D+0.70E+0.60H	4.520	5.640
+D-0.70E+0.60H	2.861	2.679
+D+0.750L+0.750S+0.5250E+H	7.780	10.101
+D+0.750L+0.750S-0.5250E+H	6.536	7.880
+0.60D+0.70E+H	3.044	3.976
+0.60D-0.70E+H	1.385	1.015
D Only	3.690	4.160
L Only	2.229	2.083
S Only	2.395	4.358
E Only	1.185	2.115
E Only * -1.0	-1.185	-2.115
H Only		

# Wood Beam

Project File: beam calcs with overstrength.ec6

LIC#: KW-06017913, Build:20.24.08.01

MULHERN & KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

**DESCRIPTION:** B2-23 OS 310


## CODE REFERENCES

Calculations per NDS 2018, IBC 2021, ASCE 7-16

Load Combination Set : ASCE 7-16

## Material Properties

Analysis Method :	Allowable Stress Design	Fb +	2880 psi	E : Modulus of Elasticity	
Load Combination :	ASCE 7-16	Fb -	2220 psi	Ebend- xx	1800ksi
		Fc - Prll	1980 psi	Eminbend - xx	950ksi
Wood Species :	24F-V4 GLB OS	Fc - Perp	780 psi	Ebend- yy	ksi
Wood Grade :	GLB - Western	Fv	318 psi	Eminbend - yy	ksi
		Ft	318 psi	Density	35pcf
Beam Bracing :	Beam is Fully Braced against lateral-torsional buckling				



## Applied Loads

Service loads entered. Load Factors will be applied for calculations.

Beam self weight calculated and added to loading

Load for Span Number 1

Uniform Load : D = 0.10 k/ft, Extent = 6.80 -->> 13.90 ft, Tributary Width = 1.0 ft

Point Load : D = 0.50, L = 0.40, S = 0.50 k @ 6.80 ft

Point Load : D = 0.40, E = 2.0 k @ 6.80 ft

## DESIGN SUMMARY

**Design OK**

Maximum Bending Stress Ratio	=	<b>0.155</b> : 1	Maximum Shear Stress Ratio	=	<b>0.086</b> : 1
Section used for this span		<b>3.5x18</b>	Section used for this span		<b>3.5x18</b>
fb: Actual	=	711.96psi	fv: Actual	=	43.92 psi
F'b	=	4,608.00psi	F'v	=	508.80 psi
Load Combination		+1.105D+0.750L+0.750S+0.5250E	Load Combination		+1.105D+0.750L+0.750S+0.5250E
Location of maximum on span	=	6.798ft	Location of maximum on span	=	12.429 ft
Span # where maximum occurs	=	Span # 1	Span # where maximum occurs	=	Span # 1
<b>Maximum Deflection</b>					
Max Downward Transient Deflection		0.063 in Ratio = <b>2628</b> >=360	Span: 1 : E Only		
Max Upward Transient Deflection		0 in Ratio = <b>0</b> <360	n/a		
Max Downward Total Deflection		0.102 in Ratio = <b>1638</b> >=180	Span: 1 : +D+0.750L+0.750S+0.5250E+H		
Max Upward Total Deflection		0 in Ratio = <b>0</b> <180	n/a		

## Maximum Forces & Stresses for Load Combinations

Load Combination	Segment Length	Span #	Max Stress Ratios										Moment Values			Shear Values			
			M	V	CD	CM	C <sub>t</sub>	CLx	C <sub>v</sub>	C <sub>fu</sub>	C <sub>i</sub>	C <sub>r</sub>	M	fb	F'b	V	fv	F'v	
+D+H	Length = 13.90 ft	1	0.116	0.075	0.90	1.00	1.00	1.00	1.000	1.00	1.00	1.00	4.73	300.1	2,592.0	0.0	0.00	0.0	0.0
+D+L+H	Length = 13.90 ft	1	0.135	0.082	1.00	1.00	1.00	1.00	1.000	1.00	1.00	1.00	6.12	388.3	2,880.0	1.10	26.2	318.0	0.0
+D+Lr+H	Length = 13.90 ft	1	0.083	0.054	1.25	1.00	1.00	1.00	1.000	1.00	1.00	1.00	4.73	300.1	3,600.0	0.91	21.6	397.5	0.0
+D+S+H						1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0	0.0	0.0

# Wood Beam

Project File: beam calcs with overstrength.ec6

LIC# : KW-06017913, Build:20.24.08.01

MULHERN & KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

## DESCRIPTION: B2-23 OS 310

### Maximum Forces & Stresses for Load Combinations

Load Combination		Max Stress Ratios										Moment Values			Shear Values		
Segment Length	Span #	M	V	CD	CM	C <sub>t</sub>	CLx	C <sub>y</sub>	C <sub>fu</sub>	C <sub>i</sub>	C <sub>r</sub>	M	fb	F'b	V	fv	F'v
Length = 13.90 ft	1	0.124	0.075	1.15	1.00	1.00	1.00	1.000	1.00	1.00	1.00	6.46	410.4	3,312.0	1.15	27.4	365.7
+D+0.750Lr+0.750L+H						1.00	1.00	1.00	1.000	1.00	1.00			0.0	0.00	0.0	0.0
Length = 13.90 ft	1	0.102	0.063	1.25	1.00	1.00	1.00	1.000	1.00	1.00	1.00	5.77	366.3	3,600.0	1.05	25.1	397.5
+D+0.750L+0.750S+H						1.00	1.00	1.00	1.000	1.00	1.00			0.0	0.00	0.0	0.0
Length = 13.90 ft	1	0.136	0.080	1.15	1.00	1.00	1.00	1.000	1.00	1.00	1.00	7.07	449.0	3,312.0	1.24	29.4	365.7
+D+0.60W+H						1.00	1.00	1.00	1.000	1.00	1.00			0.0	0.00	0.0	0.0
Length = 13.90 ft	1	0.065	0.042	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	4.73	300.1	4,608.0	0.91	21.6	508.8
+D+0.750Lr+0.750L+0.450W+						1.00	1.00	1.00	1.000	1.00	1.00			0.0	0.00	0.0	0.0
Length = 13.90 ft	1	0.079	0.049	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	5.77	366.3	4,608.0	1.05	25.1	508.8
+D+0.750L+0.750S+0.450W+l						1.00	1.00	1.00	1.000	1.00	1.00			0.0	0.00	0.0	0.0
Length = 13.90 ft	1	0.097	0.058	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	7.07	449.0	4,608.0	1.24	29.4	508.8
+0.60D+0.60W+0.60H						1.00	1.00	1.00	1.000	1.00	1.00			0.0	0.00	0.0	0.0
Length = 13.90 ft	1	0.039	0.025	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	2.84	180.1	4,608.0	0.54	12.9	508.8
+D+0.70E+0.60H						1.00	1.00	1.00	1.000	1.00	1.00			0.0	0.00	0.0	0.0
Length = 13.90 ft	1	0.132	0.074	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	9.59	608.8	4,608.0	1.59	37.9	508.8
+D-0.70E+0.60H						1.00	1.00	1.00	1.000	1.00	1.00			0.0	0.00	0.0	0.0
Length = 13.90 ft	1	0.009	0.020	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	0.66	42.0	4,608.0	0.42	10.1	508.8
+D+0.750L+0.750S+0.5250E+						1.00	1.00	1.00	1.000	1.00	1.00			0.0	0.00	0.0	0.0
Length = 13.90 ft	1	0.148	0.082	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	10.72	680.4	4,608.0	1.75	41.7	508.8
+D+0.750L+0.750S-0.5250E+l						1.00	1.00	1.00	1.000	1.00	1.00			0.0	0.00	0.0	0.0
Length = 13.90 ft	1	0.047	0.034	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	3.43	217.5	4,608.0	0.72	17.2	508.8
+0.60D+0.70E+H						1.00	1.00	1.00	1.000	1.00	1.00			0.0	0.00	0.0	0.0
Length = 13.90 ft	1	0.106	0.057	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	7.70	488.7	4,608.0	1.23	29.2	508.8
+0.60D-0.70E+H						1.00	1.00	1.00	1.000	1.00	1.00			0.0	0.00	0.0	0.0
Length = 13.90 ft	1	0.036	0.025	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	2.02	128.6	3,552.0	0.53	12.6	508.8
+1.140D+0.70E						1.00	1.00	1.00	1.000	1.00	1.00			0.0	0.00	0.0	0.0
Length = 13.90 ft	1	0.141	0.080	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	10.25	650.8	4,608.0	1.72	40.9	508.8
+1.140D-0.70E						1.00	1.00	1.00	1.000	1.00	1.00			0.0	0.00	0.0	0.0
Length = 13.90 ft	1	0.015	0.018	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	1.11	70.7	4,608.0	0.39	9.2	508.8
+1.105D+0.750L+0.750S+0.52						1.00	1.00	1.00	1.000	1.00	1.00			0.0	0.00	0.0	0.0
Length = 13.90 ft	1	0.155	0.086	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	11.21	712.0	4,608.0	1.84	43.9	508.8
+1.105D+0.750L+0.750S-0.52						1.00	1.00	1.00	1.000	1.00	1.00			0.0	0.00	0.0	0.0
Length = 13.90 ft	1	0.054	0.038	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	3.92	249.0	4,608.0	0.82	19.5	508.8
+0.460D+0.70E						1.00	1.00	1.00	1.000	1.00	1.00			0.0	0.00	0.0	0.0
Length = 13.90 ft	1	0.097	0.052	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	7.04	446.7	4,608.0	1.10	26.2	508.8
+0.460D-0.70E						1.00	1.00	1.00	1.000	1.00	1.00			0.0	0.00	0.0	0.0
Length = 13.90 ft	1	0.048	0.026	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	2.69	170.6	3,552.0	0.56	13.4	508.8

### Overall Maximum Deflections

Load Combination	Span	Max. "-" Defl	Location in Span	Load Combination	Max. "+" Defl	Location in Span
+D+0.750L+0.750S+0.5250E+H	1	0.1018	7.001		0.0000	0.000

### Vertical Reactions

Support notation : Far left is #1

Values in KIPS

Load Combination	Support 1	Support 2
Max Upward from all Load Conditions	1.629	1.919
Max Upward from Load Combinations	1.629	1.919
Max Upward from Load Cases	1.022	1.075
Max Downward from all Load Conditio	-1.022	-0.978
Max Downward from Load Combinations	-0.267	-0.040
Max Downward from Load Cases (Resis	-1.022	-0.978

**Wood Beam**

Project File: beam calcs with overstrength.ec6

LIC# : KW-06017913, Build:20.24.08.01

MULHERN &amp; KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

**DESCRIPTION: B2-23 OS 310****Vertical Reactions**

Support notation : Far left is #1

Values in KIPS

Load Combination	Support 1	Support 2
+D+H	0.747	1.075
+D+L+H	0.952	1.271
+D+Lr+H	0.747	1.075
+D+S+H	1.003	1.320
+D+0.750Lr+0.750L+H	0.901	1.222
+D+0.750L+0.750S+H	1.092	1.406
+D+0.60W+H	0.747	1.075
+D+0.750Lr+0.750L+0.450W+H	0.901	1.222
+D+0.750L+0.750S+0.450W+H	1.092	1.406
+0.60D+0.60W+0.60H	0.448	0.645
+D+0.70E+0.60H	1.463	1.760
+D-0.70E+0.60H	0.032	0.390
+D+0.750L+0.750S+0.5250E+H	1.629	1.919
+D+0.750L+0.750S-0.5250E+H	0.556	0.892
+0.60D+0.70E+H	1.164	1.330
+0.60D-0.70E+H	-0.267	-0.040
D Only	0.747	1.075
L Only	0.204	0.196
S Only	0.255	0.245
E Only	1.022	0.978
E Only * -1.0	-1.022	-0.978
H Only		

# Wood Beam

Project File: beam calcs with overstrength.ec6

LIC# : KW-06017913, Build:20.24.08.01

MULHERN & KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

**DESCRIPTION:** B2-24 OS 304


## CODE REFERENCES

Calculations per NDS 2018, IBC 2021, ASCE 7-16

Load Combination Set : ASCE 7-16

## Material Properties

Analysis Method :	Allowable Stress Design	Fb +	2,880.0 psi	E : Modulus of Elasticity	
Load Combination :	ASCE 7-16	Fb -	2,220.0 psi	Ebend- xx	1,800.0ksi
		Fc - Prll	1,980.0 psi	Eminbend - xx	950.0ksi
Wood Species :	24F-V4 GLB OS	Fc - Perp	780.0 psi	Ebend- yy	ksi
Wood Grade :	GLB - Western	Fv	318.0 psi	Eminbend - yy	ksi
		Ft	318.0 psi	Density	35.0pcf
Beam Bracing :	Beam is Fully Braced against lateral-torsional buckling				



## Applied Loads

Service loads entered. Load Factors will be applied for calculations.

Beam self weight calculated and added to loading

Load for Span Number 1

- Uniform Load : D = 0.350, L = 0.40, S = 0.250 k/ft, Extent = 0.0 --> 0.20 ft, Tributary Width = 1.0 ft
- Uniform Load : D = 0.150, L = 0.40 k/ft, Extent = 0.20 --> 2.0 ft, Tributary Width = 1.0 ft
- Uniform Load : D = 0.150, L = 0.40 k/ft, Extent = 2.0 --> 3.40 ft, Tributary Width = 1.0 ft
- Uniform Load : D = 0.150, L = 0.40 k/ft, Extent = 3.50 --> 8.20 ft, Tributary Width = 1.0 ft
- Uniform Load : D = 0.350, L = 0.40, S = 0.250 k/ft, Extent = 8.20 --> 8.70 ft, Tributary Width = 1.0 ft
- Uniform Load : D = 0.150, L = 0.40 k/ft, Extent = 8.70 --> 16.70 ft, Tributary Width = 1.0 ft
- Uniform Load : D = 0.350, L = 0.40, S = 0.250 k/ft, Extent = 16.70 --> 18.0 ft, Tributary Width = 1.0 ft
- Point Load : D = 0.40, S = 1.0 k @ 8.20 ft
- Point Load : D = 0.40, S = 1.0 k @ 8.70 ft
- Point Load : D = 0.40, S = 1.0 k @ 16.70 ft
- Point Load : D = 3.50, E = 2.10 k @ 16.70 ft

## DESIGN SUMMARY

				<b>Design OK</b>			
Maximum Bending Stress Ratio	=	<b>0.429</b>	1	Maximum Shear Stress Ratio	=	<b>0.241</b>	: 1
Section used for this span		<b>5.5x18</b>		Section used for this span		<b>5.5x18</b>	
fb: Actual	=	1,195.61 psi		fv: Actual	=	76.68 psi	
F'b	=	2,788.76psi		F'v	=	318.00 psi	
Load Combination		+D+L+H		Load Combination		+D+L+H	
Location of maximum on span	=	8.803ft		Location of maximum on span	=	0.000 ft	
Span # where maximum occurs	=	Span # 1		Span # where maximum occurs	=	Span # 1	
<b>Maximum Deflection</b>							
Max Downward Transient Deflection		0.197 in	Ratio =	<b>1098</b>	>=	360	Span: 1 : L Only
Max Upward Transient Deflection		0 in	Ratio =	<b>0</b>	<	360	n/a
Max Downward Total Deflection		0.399 in	Ratio =	<b>542</b>	>=	180	Span: 1 : +D+0.750L+0.750S+0.5250E+H
Max Upward Total Deflection		0 in	Ratio =	<b>0</b>	<	180	n/a

# Wood Beam

Project File: beam calcs with overstrength.ec6

LIC# : KW-06017913, Build:20.24.08.01

MULHERN & KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

## DESCRIPTION: B2-24 OS 304

### Maximum Forces & Stresses for Load Combinations

Load Combination	Segment Length	Span #	Max Stress Ratios									Moment Values			Shear Values			
			M	V	CD	CM	C <sub>t</sub>	CLx	C <sub>y</sub>	C <sub>fu</sub>	C <sub>i</sub>	C <sub>r</sub>	M	fb	F'b	V	fv	F'v
+D+H															0.0	0.00	0.0	0.0
Length = 18.0 ft	1		0.217	0.110	0.90	1.00	1.00	1.00	0.968	1.00	1.00	1.00	13.48	544.5	2,509.9	2.07	31.4	286.2
+D+L+H															0.0	0.00	0.0	0.0
Length = 18.0 ft	1		0.429	0.241	1.00	1.00	1.00	1.00	0.968	1.00	1.00	1.00	29.59	1,195.6	2,788.8	5.06	76.7	318.0
+D+Lr+H															0.0	0.00	0.0	0.0
Length = 18.0 ft	1		0.156	0.079	1.25	1.00	1.00	1.00	0.968	1.00	1.00	1.00	13.48	544.5	3,486.0	2.07	31.4	397.5
+D+S+H															0.0	0.00	0.0	0.0
Length = 18.0 ft	1		0.296	0.136	1.15	1.00	1.00	1.00	0.968	1.00	1.00	1.00	23.48	948.6	3,207.1	3.28	49.7	365.7
+D+0.750Lr+0.750L+H															0.0	0.00	0.0	0.0
Length = 18.0 ft	1		0.296	0.164	1.25	1.00	1.00	1.00	0.968	1.00	1.00	1.00	25.56	1,032.8	3,486.0	4.31	65.4	397.5
+D+0.750L+0.750S+H															0.0	0.00	0.0	0.0
Length = 18.0 ft	1		0.416	0.216	1.15	1.00	1.00	1.00	0.968	1.00	1.00	1.00	33.06	1,335.6	3,207.1	5.22	79.1	365.7
+D+0.60W+H															0.0	0.00	0.0	0.0
Length = 18.0 ft	1		0.122	0.062	1.60	1.00	1.00	1.00	0.968	1.00	1.00	1.00	13.48	544.5	4,462.0	2.07	31.4	508.8
+D+0.750Lr+0.750L+0.450W+															0.0	0.00	0.0	0.0
Length = 18.0 ft	1		0.231	0.128	1.60	1.00	1.00	1.00	0.968	1.00	1.00	1.00	25.56	1,032.8	4,462.0	4.31	65.4	508.8
+D+0.750L+0.750S+0.450W+															0.0	0.00	0.0	0.0
Length = 18.0 ft	1		0.299	0.155	1.60	1.00	1.00	1.00	0.968	1.00	1.00	1.00	33.06	1,335.6	4,462.0	5.22	79.1	508.8
+0.60D+0.60W+0.60H															0.0	0.00	0.0	0.0
Length = 18.0 ft	1		0.073	0.037	1.60	1.00	1.00	1.00	0.968	1.00	1.00	1.00	8.09	326.7	4,462.0	1.24	18.8	508.8
+D+0.70E+0.60H															0.0	0.00	0.0	0.0
Length = 18.0 ft	1		0.130	0.065	1.60	1.00	1.00	1.00	0.968	1.00	1.00	1.00	14.40	582.0	4,462.0	2.18	33.0	508.8
+D-0.70E+0.60H															0.0	0.00	0.0	0.0
Length = 18.0 ft	1		0.114	0.059	1.60	1.00	1.00	1.00	0.968	1.00	1.00	1.00	12.55	507.0	4,462.0	1.97	29.8	508.8
+D+0.750L+0.750S+0.5250E+															0.0	0.00	0.0	0.0
Length = 18.0 ft	1		0.306	0.158	1.60	1.00	1.00	1.00	0.968	1.00	1.00	1.00	33.75	1,363.5	4,462.0	5.30	80.3	508.8
+D+0.750L+0.750S-0.5250E+															0.0	0.00	0.0	0.0
Length = 18.0 ft	1		0.293	0.153	1.60	1.00	1.00	1.00	0.968	1.00	1.00	1.00	32.36	1,307.7	4,462.0	5.14	77.9	508.8
+0.60D+0.70E+H															0.0	0.00	0.0	0.0
Length = 18.0 ft	1		0.082	0.040	1.60	1.00	1.00	1.00	0.968	1.00	1.00	1.00	9.03	364.8	4,462.0	1.35	20.4	508.8
+0.60D-0.70E+H															0.0	0.00	0.0	0.0
Length = 18.0 ft	1		0.065	0.034	1.60	1.00	1.00	1.00	0.968	1.00	1.00	1.00	7.16	289.3	4,462.0	1.14	17.2	508.8
+1.140D+0.70E															0.0	0.00	0.0	0.0
Length = 18.0 ft	1		0.148	0.073	1.60	1.00	1.00	1.00	0.968	1.00	1.00	1.00	16.29	658.2	4,462.0	2.47	37.4	508.8
+1.140D-0.70E															0.0	0.00	0.0	0.0
Length = 18.0 ft	1		0.131	0.067	1.60	1.00	1.00	1.00	0.968	1.00	1.00	1.00	14.43	583.2	4,462.0	2.26	34.2	508.8
+1.105D+0.750L+0.750S+0.52															0.0	0.00	0.0	0.0
Length = 18.0 ft	1		0.318	0.164	1.60	1.00	1.00	1.00	0.968	1.00	1.00	1.00	35.16	1,420.6	4,462.0	5.52	83.6	508.8
+1.105D+0.750L+0.750S-0.52															0.0	0.00	0.0	0.0
Length = 18.0 ft	1		0.306	0.160	1.60	1.00	1.00	1.00	0.968	1.00	1.00	1.00	33.78	1,364.8	4,462.0	5.36	81.2	508.8
+0.460D+0.70E															0.0	0.00	0.0	0.0
Length = 18.0 ft	1		0.065	0.032	1.60	1.00	1.00	1.00	0.968	1.00	1.00	1.00	7.16	289.1	4,462.0	1.06	16.0	508.8
+0.460D-0.70E															0.0	0.00	0.0	0.0
Length = 18.0 ft	1		0.048	0.025	1.60	1.00	1.00	1.00	0.968	1.00	1.00	1.00	5.28	213.1	4,462.0	0.85	12.8	508.8

### Overall Maximum Deflections

Load Combination	Span	Max. "-" Defl	Location in Span	Load Combination	Max. "+" Defl	Location in Span
+D+0.750L+0.750S+0.5250E+H	1	0.3985	9.131		0.0000	0.000

**Wood Beam**

Project File: beam calcs with overstrength.ec6

LIC# : KW-06017913, Build:20.24.08.01

MULHERN &amp; KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

**DESCRIPTION: B2-24 OS 304****Vertical Reactions**

Support notation : Far left is #1

Values in KIPS

Load Combination	Support 1	Support 2
Max Upward from all Load Conditions	6.064	11.252
Max Upward from Load Combinations	6.064	11.252
Max Upward from Load Cases	3.568	5.855
Max Downward from all Load Conditio	-0.152	-1.948
Max Downward from Load Cases (Resis	-0.152	-1.948
+D+H	2.363	5.855
+D+L+H	5.930	9.448
+D+Lr+H	2.363	5.855
+D+S+H	3.624	8.094
+D+0.750Lr+0.750L+H	5.039	8.550
+D+0.750L+0.750S+H	5.984	10.229
+D+0.60W+H	2.363	5.855
+D+0.750Lr+0.750L+0.450W+H	5.039	8.550
+D+0.750L+0.750S+0.450W+H	5.984	10.229
+0.60D+0.60W+0.60H	1.418	3.513
+D+0.70E+0.60H	2.469	7.219
+D-0.70E+0.60H	2.257	4.492
+D+0.750L+0.750S+0.5250E+H	6.064	11.252
+D+0.750L+0.750S-0.5250E+H	5.905	9.206
+0.60D+0.70E+H	1.524	4.877
+0.60D-0.70E+H	1.311	2.149
D Only	2.363	5.855
L Only	3.568	3.592
S Only	1.261	2.239
E Only	0.152	1.948
E Only * -1.0	-0.152	-1.948
H Only		

# Wood Beam

Project File: beam calcs with overstrength.ec6

LIC#: KW-06017913, Build:20.24.08.01

MULHERN & KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

**DESCRIPTION:** B2-15 OS 312


## CODE REFERENCES

Calculations per NDS 2018, IBC 2021, ASCE 7-16

Load Combination Set : ASCE 7-16

## Material Properties

Analysis Method : Allowable Stress Design	Fb +	2,880.0 psi	E : Modulus of Elasticity	
Load Combination : ASCE 7-16	Fb -	2,220.0 psi	Ebend- xx	1,800.0ksi
	Fc - Prll	1,980.0 psi	Eminbend - xx	950.0ksi
Wood Species : 24F-V4 GLB OS	Fc - Perp	780.0 psi	Ebend- yy	ksi
Wood Grade : GLB - Western	Fv	318.0 psi	Eminbend - yy	ksi
	Ft	318.0 psi	Density	35.0pcf
Beam Bracing : Beam is Fully Braced against lateral-torsional buckling				



## Applied Loads

Service loads entered. Load Factors will be applied for calculations.

Beam self weight calculated and added to loading

Load for Span Number 1

Uniform Load : D = 0.10, S = 0.240 k/ft, Extent = 0.0 --> 2.10 ft, Tributary Width = 1.0 ft

Uniform Load : D = 0.10, S = 0.220 k/ft, Extent = 2.10 --> 18.70 ft, Tributary Width = 1.0 ft

Point Load : D = 2.40, L = 3.60, S = 2.120 k @ 2.10 ft

Point Load : D = 0.80, E = 3.0 k @ 4.630 ft

## DESIGN SUMMARY

**Design OK**

Maximum Bending Stress Ratio	=	<b>0.436</b>	1	Maximum Shear Stress Ratio	=	<b>0.571</b>	: 1
Section used for this span		<b>3.5x18</b>		Section used for this span		<b>3.5x18</b>	
fb: Actual	=	1,445.04psi		fv: Actual	=	208.76 psi	
F'b	=	3,312.00psi		F'v	=	365.70 psi	
Load Combination		+D+0.750L+0.750S+H		Load Combination		+D+0.750L+0.750S+H	
Location of maximum on span	=	5.938ft		Location of maximum on span	=	0.000 ft	
Span # where maximum occurs	=	Span # 1		Span # where maximum occurs	=	Span # 1	
<b>Maximum Deflection</b>							
Max Downward Transient Deflection		0.254 in	Ratio =	883	>=	360	Span: 1 : S Only
Max Upward Transient Deflection		0 in	Ratio =	0	<	360	n/a
Max Downward Total Deflection		0.554 in	Ratio =	404	>=	180	Span: 1 : +D+0.750L+0.750S+0.5250E+H
Max Upward Total Deflection		0 in	Ratio =	0	<	180	n/a

## Maximum Forces & Stresses for Load Combinations

Load Combination	Segment Length	Span #	Max Stress Ratios										Moment Values			Shear Values				
			M	V	CD	CM	C <sub>t</sub>	CLx	C <sub>v</sub>	C <sub>fu</sub>	C <sub>i</sub>	C <sub>r</sub>	M	fb	F'b	V	fv	F'v		
+D+H	Length = 18.70 ft	1	0.254	0.303	0.90	1.00	1.00	1.00	1.000	1.00	1.00	1.00	10.36	657.8	2,592.0	0.0	0.00	0.0	0.0	286.2
+D+L+H	Length = 18.70 ft	1	0.353	0.512	1.00	1.00	1.00	1.00	1.000	1.00	1.00	1.00	16.02	1,017.1	2,880.0	0.0	0.00	0.0	0.0	318.0
+D+Lr+H	Length = 18.70 ft	1	0.183	0.218	1.25	1.00	1.00	1.00	1.000	1.00	1.00	1.00	10.36	657.8	3,600.0	0.0	0.00	0.0	0.0	397.5

# Wood Beam

Project File: beam calcs with overstrength.ec6

LIC# : KW-06017913, Build:20.24.08.01

MULHERN & KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

## DESCRIPTION: B2-15 OS 312

### Maximum Forces & Stresses for Load Combinations

Load Combination	Segment Length	Span #	Max Stress Ratios									Moment Values			Shear Values			
			M	V	CD	CM	C <sub>t</sub>	CLx	C <sub>y</sub>	C <sub>fu</sub>	C <sub>i</sub>	C <sub>r</sub>	M	fb	F'b	V	fv	F'v
+D+S+H						1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.70 ft	1		0.422	0.474	1.15	1.00	1.00	1.00	1.000	1.00	1.00	1.00	22.02	1,398.4	3,312.0	7.28	173.3	365.7
+D+0.750Lr+0.750L+H						1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.70 ft	1		0.257	0.362	1.25	1.00	1.00	1.00	1.000	1.00	1.00	1.00	14.60	926.9	3,600.0	6.04	143.9	397.5
+D+0.750L+0.750S+H						1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.70 ft	1		0.436	0.571	1.15	1.00	1.00	1.00	1.000	1.00	1.00	1.00	22.76	1,445.0	3,312.0	8.77	208.8	365.7
+D+0.60W+H						1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.70 ft	1		0.143	0.171	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	10.36	657.8	4,608.0	3.65	86.8	508.8
+D+0.750Lr+0.750L+0.450W+						1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.70 ft	1		0.201	0.283	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	14.60	926.9	4,608.0	6.04	143.9	508.8
+D+0.750L+0.750S+0.450W+l						1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.70 ft	1		0.314	0.410	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	22.76	1,445.0	4,608.0	8.77	208.8	508.8
+0.60D+0.60W+0.60H						1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.70 ft	1		0.086	0.102	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	6.22	394.7	4,608.0	2.19	52.1	508.8
+D+0.70E+0.60H						1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.70 ft	1		0.243	0.245	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	17.65	1,120.4	4,608.0	5.23	124.4	508.8
+D-0.70E+0.60H						1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.70 ft	1		0.063	0.097	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	4.56	289.7	4,608.0	2.07	49.2	508.8
+D+0.750L+0.750S+0.5250E+						1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.70 ft	1		0.386	0.466	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	28.00	1,777.7	4,608.0	9.95	237.0	508.8
+D+0.750L+0.750S-0.5250E+l						1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.70 ft	1		0.249	0.355	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	18.06	1,146.8	4,608.0	7.58	180.5	508.8
+0.60D+0.70E+H						1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.70 ft	1		0.186	0.176	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	13.51	857.9	4,608.0	3.77	89.7	508.8
+0.60D-0.70E+H						1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.70 ft	1		0.018	0.049	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	1.32	83.6	4,608.0	1.05	25.0	508.8
+1.140D+0.70E						1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.70 ft	1		0.263	0.268	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	19.09	1,212.2	4,608.0	5.74	136.6	508.8
+1.140D-0.70E						1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.70 ft	1		0.081	0.121	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	5.87	372.7	4,608.0	2.58	61.3	508.8
+1.105D+0.750L+0.750S+0.52						1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.70 ft	1		0.401	0.484	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	29.08	1,846.6	4,608.0	10.34	246.1	508.8
+1.105D+0.750L+0.750S-0.52						1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.70 ft	1		0.264	0.373	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	19.12	1,214.3	4,608.0	7.97	189.7	508.8
+0.460D+0.70E						1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.70 ft	1		0.166	0.152	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	12.06	766.0	4,608.0	3.26	77.5	508.8
+0.460D-0.70E						1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 18.70 ft	1		0.046	0.055	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	2.56	162.3	3,552.0	1.17	27.9	508.8

### Overall Maximum Deflections

Load Combination	Span	Max. "-" Defl	Location in Span	Load Combination	Max. "+" Defl	Location in Span
+D+0.750L+0.750S+0.5250E+H	1	0.5542	8.736		0.0000	0.000

### Vertical Reactions

Support notation : Far left is #1

Values in KIPS

Load Combination	Support 1	Support 2
Max Upward from all Load Conditions	10.376	3.962
Max Upward from Load Combinations	10.376	3.962
Max Upward from Load Cases	3.979	2.297
Max Downward from all Load Conditio	-2.257	-0.743
Max Downward from Load Cases (Resis	-2.257	-0.743

**Wood Beam**

Project File: beam calcs with overstrength.ec6

LIC# : KW-06017913, Build:20.24.08.01

MULHERN &amp; KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

**DESCRIPTION: B2-15 OS 312****Vertical Reactions**

Support notation : Far left is #1

Values in KIPS

Load Combination	Support 1	Support 2
+D+H	3.811	1.546
+D+L+H	7.006	1.950
+D+Lr+H	3.811	1.546
+D+S+H	7.789	3.843
+D+0.750Lr+0.750L+H	6.207	1.849
+D+0.750L+0.750S+H	9.191	3.572
+D+0.60W+H	3.811	1.546
+D+0.750Lr+0.750L+0.450W+H	6.207	1.849
+D+0.750L+0.750S+0.450W+H	9.191	3.572
+0.60D+0.60W+0.60H	2.286	0.927
+D+0.70E+0.60H	5.391	2.066
+D-0.70E+0.60H	2.231	1.026
+D+0.750L+0.750S+0.5250E+H	10.376	3.962
+D+0.750L+0.750S-0.5250E+H	8.006	3.182
+0.60D+0.70E+H	3.866	1.447
+0.60D-0.70E+H	0.706	0.408
D Only	3.811	1.546
L Only	3.196	0.404
S Only	3.979	2.297
E Only	2.257	0.743
E Only * -1.0	-2.257	-0.743
H Only		

# Wood Beam

Project File: beam calcs with overstrength.ec6

LIC# : KW-06017913, Build:20.24.08.01

MULHERN & KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

**DESCRIPTION:** B2-13 OS 313

## CODE REFERENCES


Calculations per NDS 2018, IBC 2021, ASCE 7-16

Load Combination Set : ASCE 7-16

## Material Properties

Analysis Method : Allowable Stress Design	Fb +	2,880.0 psi	<i>E : Modulus of Elasticity</i>
Load Combination : ASCE 7-16	Fb -	2,220.0 psi	Ebend- xx
	Fc - Prll	1,980.0 psi	Eminbend - xx
Wood Species : 24F-V4 GLB OS	Fc - Perp	780.0 psi	Ebend- yy
Wood Grade : GLB - Western	Fv	318.0 psi	Eminbend - yy
	Ft	318.0 psi	Density
			35.0pcf

Beam Bracing : Beam is Fully Braced against lateral-torsional buckling



## Applied Loads

Service loads entered. Load Factors will be applied for calculations.

Beam self weight calculated and added to loading

Point Load : D = 0.40, L = 1.290 k @ 3.0 ft

Point Load : D = 0.90, E = 2.80 k @ 3.0 ft

## DESIGN SUMMARY

**Design OK**

Maximum Bending Stress Ratio	=	<b>0.065</b> : 1	Maximum Shear Stress Ratio	=	<b>0.122</b> : 1
Section used for this span		<b>3.5x18</b>	Section used for this span		<b>3.5x18</b>
fb: Actual	=	187.36psi	fv: Actual	=	38.87 psi
F'b	=	2,880.00psi	F'v	=	318.00 psi
Load Combination		+D+L+H	Load Combination		+D+L+H
Location of maximum on span	=	2.996ft	Location of maximum on span	=	3.311 ft
Span # where maximum occurs	=	Span # 1	Span # where maximum occurs	=	Span # 1
<b>Maximum Deflection</b>					
Max Downward Transient Deflection		0.003 in	Ratio =	<b>17110</b>	>=360
Max Upward Transient Deflection		0 in	Ratio =	<b>0</b>	<360
Max Downward Total Deflection		0.005 in	Ratio =	<b>12650</b>	>=180
Max Upward Total Deflection		0 in	Ratio =	<b>0</b>	<180

## Maximum Forces & Stresses for Load Combinations

Load Combination	Segment Length	Span #	Max Stress Ratios										Moment Values			Shear Values					
			M	V	CD	CM	C <sub>t</sub>	CLx	C <sub>v</sub>	C <sub>fu</sub>	C <sub>i</sub>	C <sub>r</sub>	M	fb	F'b	V	fv	F'v			
+D+H																					
Length = 4.80 ft	1	0.037	0.069	0.90	1.00	1.00	1.00	1.000	1.00	1.00	1.00	1.50	95.3	2,592.0	0.0	0.00	0.0	0.0	0.0	286.2	
+D+L+H																					
Length = 4.80 ft	1	0.065	0.122	1.00	1.00	1.00	1.00	1.000	1.00	1.00	1.00	2.95	187.4	2,880.0	1.63	0.00	0.0	0.0	0.0	318.0	
+D+Lr+H																					
Length = 4.80 ft	1	0.026	0.050	1.25	1.00	1.00	1.00	1.000	1.00	1.00	1.00	1.50	95.3	3,600.0	0.83	0.00	0.0	0.0	0.0	397.5	
+D+S+H																					
Length = 4.80 ft	1	0.029	0.054	1.15	1.00	1.00	1.00	1.000	1.00	1.00	1.00	1.50	95.3	3,312.0	0.83	0.00	0.0	0.0	0.0	365.7	
+D+0.750Lr+0.750L+H																					
					1.00	1.00	1.00	1.000	1.00	1.00	1.00				0.0	0.00	0.0	0.0	0.0	0.0	

# Wood Beam

Project File: beam calcs with overstrength.ec6

LIC# : KW-06017913, Build:20.24.08.01

MULHERN & KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

## DESCRIPTION: B2-13 OS 313

### Maximum Forces & Stresses for Load Combinations

Load Combination	Segment Length	Span #	Max Stress Ratios									Moment Values			Shear Values			
			M	V	CD	CM	C <sub>t</sub>	CLx	C <sub>y</sub>	C <sub>fu</sub>	C <sub>i</sub>	C <sub>r</sub>	M	fb	F'b	V	fv	F'v
Length = 4.80 ft	1		0.046	0.086	1.25	1.00	1.00	1.00	1.000	1.00	1.00	1.00	2.59	164.4	3,600.0	1.43	34.1	397.5
+D+0.750L+0.750S+H						1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 4.80 ft	1		0.050	0.093	1.15	1.00	1.00	1.00	1.000	1.00	1.00	1.00	2.59	164.4	3,312.0	1.43	34.1	365.7
+D+0.60W+H						1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 4.80 ft	1		0.021	0.039	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	1.50	95.3	4,608.0	0.83	19.7	508.8
+D+0.750Lr+0.750L+0.450W+						1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 4.80 ft	1		0.036	0.067	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	2.59	164.4	4,608.0	1.43	34.1	508.8
+D+0.750L+0.750S+0.450W+l						1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 4.80 ft	1		0.036	0.067	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	2.59	164.4	4,608.0	1.43	34.1	508.8
+0.60D+0.60W+0.60H						1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 4.80 ft	1		0.012	0.023	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	0.90	57.2	4,608.0	0.50	11.8	508.8
+D+0.70E+0.60H						1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 4.80 ft	1		0.051	0.096	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	3.70	235.1	4,608.0	2.05	48.8	508.8
+D-0.70E+0.60H						1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 4.80 ft	1		0.013	0.019	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	0.70	44.4	3,552.0	0.40	9.6	508.8
+D+0.750L+0.750S+0.5250E+						1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 4.80 ft	1		0.058	0.110	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	4.24	269.2	4,608.0	2.35	55.9	508.8
+D+0.750L+0.750S-0.5250E+l						1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 4.80 ft	1		0.013	0.024	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	0.94	59.5	4,608.0	0.51	12.2	508.8
+0.60D+0.70E+H						1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 4.80 ft	1		0.043	0.081	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	3.10	197.0	4,608.0	1.72	41.0	508.8
+0.60D-0.70E+H						1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 4.80 ft	1		0.023	0.034	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	1.30	82.6	3,552.0	0.73	17.4	508.8
+1.140D+0.70E						1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 4.80 ft	1		0.054	0.101	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	3.91	248.5	4,608.0	2.17	51.6	508.8
+1.140D-0.70E						1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 4.80 ft	1		0.009	0.013	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	0.49	31.1	3,552.0	0.29	6.9	508.8
+1.105D+0.750L+0.750S+0.52						1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 4.80 ft	1		0.061	0.114	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	4.40	279.2	4,608.0	2.44	58.0	508.8
+1.105D+0.750L+0.750S-0.52						1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 4.80 ft	1		0.015	0.028	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	1.09	69.5	4,608.0	0.60	14.3	508.8
+0.460D+0.70E						1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 4.80 ft	1		0.040	0.075	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	2.89	183.7	4,608.0	1.61	38.2	508.8
+0.460D-0.70E						1.00	1.00	1.00	1.000	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 4.80 ft	1		0.027	0.040	1.60	1.00	1.00	1.00	1.000	1.00	1.00	1.00	1.51	95.9	3,552.0	0.85	20.2	508.8

### Overall Maximum Deflections

Load Combination	Span	Max. "-" Defl	Location in Span	Load Combination	Max. "+" Defl	Location in Span
+D+0.750L+0.750S+0.5250E+H	1	0.0046	2.575		0.0000	0.000

### Vertical Reactions

Support notation : Far left is #1

Values in KIPS

Load Combination	Support 1	Support 2
Max Upward from all Load Conditions	1.438	2.373
Max Upward from Load Combinations	1.438	2.373
Max Upward from Load Cases	1.050	1.750
Max Downward from all Load Conditio	-1.050	-1.750
Max Downward from Load Combinations	-0.420	-0.715
Max Downward from Load Cases (Resis	-1.050	-1.750
+D+H	0.524	0.849
+D+L+H	1.008	1.656
+D+Lr+H	0.524	0.849

**Wood Beam**

Project File: beam calcs with overstrength.ec6

LIC# : KW-06017913, Build:20.24.08.01

MULHERN &amp; KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

**DESCRIPTION: B2-13 OS 313****Vertical Reactions**

Support notation : Far left is #1

Values in KIPS

Load Combination	Support 1	Support 2
+D+S+H	0.524	0.849
+D+0.750Lr+0.750L+H	0.887	1.454
+D+0.750L+0.750S+H	0.887	1.454
+D+0.60W+H	0.524	0.849
+D+0.750Lr+0.750L+0.450W+H	0.887	1.454
+D+0.750L+0.750S+0.450W+H	0.887	1.454
+0.60D+0.60W+0.60H	0.315	0.510
+D+0.70E+0.60H	1.259	2.074
+D-0.70E+0.60H	-0.211	-0.376
+D+0.750L+0.750S+0.5250E+H	1.438	2.373
+D+0.750L+0.750S-0.5250E+H	0.336	0.535
+0.60D+0.70E+H	1.050	1.735
+0.60D-0.70E+H	-0.420	-0.715
D Only	0.524	0.849
L Only	0.484	0.806
E Only	1.050	1.750
E Only * -1.0	-1.050	-1.750
H Only		

# Cantilevered Retaining Wall

Project File: Foundation Retaining.ec6

LIC# : KW-06017913, Build:20.24.08.01

MULHERN & KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

**DESCRIPTION:** 8'-9" Basement Wall

## Code Reference


Calculations per IBC 2021 1807.3, ASCE 7-16

### Criteria

Retained Height	=	8.75 ft
Wall height above soil	=	0.75 ft
Slope Behind Wall	=	0.00
Height of Soil over Toe	=	0.00 in
Water table above bottom of footing	=	0.0 ft

### Soil Data

Allow Soil Bearing	=	1,500.0 psf
Equivalent Fluid Pressure Method		
Active Heel Pressure	=	35.0 psf/ft
Passive Pressure	=	250.0 psf/ft
Soil Density, Heel	=	110.00 pcf
Soil Density, Toe	=	110.00 pcf
Footing  Soil Friction	=	0.400
Soil height to ignore for passive pressure	=	12.00 in



### Surcharge Loads

Surcharge Over Heel	=	0.0 psf
Used To Resist Sliding & Overturning		
Surcharge Over Toe	=	0.0 psf
Used for Sliding & Overturning		

### Axial Load Applied to Stem

Axial Dead Load	=	0.0 lbs
Axial Live Load	=	0.0 lbs
Axial Load Eccentricity	=	0.0 in

### Earth Pressure Seismic Load

Method	:	Uniform
Multiplier Used	=	7.000
(Multiplier used on soil density)		

### Lateral Load Applied to Stem

Lateral Load	=	0.0 #/ft
...Height to Top	=	0.00 ft
...Height to Bottom	=	0.00 ft
Load Type	=	Wind (W) (Service Level)
Wind on Exposed Stem	=	0.0 psf
(Strength Level)		

Uniform Seismic Force	=	68.250
Total Seismic Force	=	665.438

### Adjacent Footing Load

Adjacent Footing Load	=	0.0 lbs
Footing Width	=	0.00 ft
Eccentricity	=	0.00 in
Wall to Ftg CL Dist	=	0.00 ft
Footing Type	=	Spread Footing
Base Above/Below Soil at Back of Wall	=	0.0 ft
Poisson's Ratio	=	0.300

# Cantilevered Retaining Wall

Project File: Foundation Retaining.ec6

LIC# : KW-06017913, Build:20.24.08.01

MULHERN & KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

## DESCRIPTION: 8'-9" Basement Wall

### Design Summary

#### Wall Stability Ratios

Overturning	=	2.22	OK
Slab Resists All Sliding !			
Global Stability	=	1.70	
Total Bearing Load	=	5,161 lbs	
...resultant ecc.	=	8.19 in	
Eccentricity within middle third			
Soil Pressure @ Toe	=	1,877 psf	NG
Soil Pressure @ Heel	=	187 psf	OK
Allowable	=	1,500 psf	
Soil Pressure Exceeds Allowable!			
ACI Factored @ Toe	=	2,254 psf	
ACI Factored @ Heel	=	225 psf	
Footing Shear @ Toe	=	14.9 psi	OK
Footing Shear @ Heel	=	23.6 psi	OK
Allowable	=	75.0 psi	

#### Sliding Calcs

Lateral Sliding Force	=	2,129.4 lbs
-----------------------	---	-------------

SOIL PRESSURE @ TOE IS ADEQUATE  
DUE TO 33% INCREASE TO SOIL BEARING  
PRESSURE FROM SEISMIC SURCHARGE

Vertical component of active lateral soil pressure IS  
considered in the calculation of soil bearing pressures.

#### Load Factors

Building Code	
Dead Load	1.200
Live Load	1.600
Earth, H	1.600
Wind, W	1.600
Seismic, E	1.000

### Stem Construction

		2nd	Bottom		
<b>Design Height Above Ftg</b>	ft =	Stem OK 4.00	Stem OK 0.00		
Wall Material Above "Ht"	=	Concrete	Concrete		
Design Method	=	SD	SD	SD	SD
Thickness	=	8.00	8.00		
Rebar Size	=	# 5	# 5		
Rebar Spacing	=	16.00	8.00		
Rebar Placed at	=	6.5 in	6.5 in		
<b>Design Data</b>					
fb/FB + fa/Fa	=	0.271	0.711		
<b>Total Force @ Section</b>					
Service Level	lbs =				
Strength Level	lbs =	955.9	2,740.9		
<b>Moment....Actual</b>					
Service Level	ft-# =				
Strength Level	ft-# =	1,770.2	8,865.3		
Moment....Allowable	ft-# =	6,513.6	12,453.1		
<b>Shear.....Actual</b>					
Service Level	psi =				
Strength Level	psi =	12.3	35.1		
Shear.....Allowable	psi =	43.2	54.4		
Anet (Masonry)	in2 =				
Wall Weight	psf =	100.0	100.0		
Rebar Depth 'd'	in =	6.50	6.50		

#### Masonry Data

f'm	psi =	
Fs	psi =	
Solid Grouting	=	
Modular Ratio 'n'	=	
Equiv. Solid Thick.	=	
Masonry Block Type	=	
Masonry Design Method	=	ASD

#### Concrete Data

f'c	psi =	2,500.0	2,500.0
Fy	psi =	60,000.0	60,000.0

# Cantilevered Retaining Wall

Project File: Foundation Retaining.ec6

LIC# : KW-06017913, Build:20.24.08.01

MULHERN & KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

## DESCRIPTION: 8'-9" Basement Wall

### Concrete Stem Rebar Area Details

2nd Stem	<u>Vertical Reinforcing</u>	<u>Horizontal Reinforcing</u>
As (based on applied moment) :	0.0636 in <sup>2</sup> /ft	
0.0018bh : 0.0018(12)(8) :	0.1728 in <sup>2</sup> /ft	
	=====	
Required Area :	0.1728 in <sup>2</sup> /ft	Horizontal Reinforcing Options :
Provided Area :	0.2325 in <sup>2</sup> /ft	<u>One layer of :</u> <u>Two layers of :</u>
Maximum Area :	0.8805 in <sup>2</sup> /ft	#4@ 13.89 in    #4@ 27.78 in
		#5@ 21.53 in    #5@ 43.06 in
		#6@ 30.56 in    #6@ 61.11 in

Bottom Stem	<u>Vertical Reinforcing</u>	<u>Horizontal Reinforcing</u>
As (based on applied moment) :	0.3187 in <sup>2</sup> /ft	
0.0018bh : 0.0018(12)(8) :	0.1728 in <sup>2</sup> /ft	
	=====	
Required Area :	0.3187 in <sup>2</sup> /ft	Horizontal Reinforcing Options :
Provided Area :	0.465 in <sup>2</sup> /ft	<u>One layer of :</u> <u>Two layers of :</u>
Maximum Area :	0.8805 in <sup>2</sup> /ft	#4@ 13.89 in    #4@ 27.78 in
		#5@ 21.53 in    #5@ 43.06 in
		#6@ 30.56 in    #6@ 61.11 in

### Footing Data

Toe Width	=	1.50 ft
Heel Width	=	3.50
Total Footing Width	=	5.00
Footing Thickness	=	12.00 in

f'c =	2,500 psi	Fy =	60,000 psi
Footing Concrete Density	=	150.00 pcf	
Min. As %	=	0.0018	
Cover @ Top	2.00	@ Btm.=	3.00 in

### Footing Design Results

	<u>Toe</u>	<u>Heel</u>	
Factored Pressure	= 2,254	225	psf
Mu' : Upward	= 2,308	2,441	ft-#
Mu' : Downward	= 203	8,688	ft-#
Mu: Design	= 2,105	6,246	ft-#
φ Mn	= 17,034	13,005	ft-#
Actual 1-Way Shear	= 14.85	23.61	psi
Allow 1-Way Shear	= 49.38	41.60	psi
Toe Reinforcing	= # 5 @ 8.00 in		
Heel Reinforcing	= # 5 @ 12.00 in		
Key Reinforcing	= None Spec'd		
Footing Torsion, Tu	=	0.00	ft-lbs
Footing Allow. Torsion, φ Tn	=	0.00	ft-lbs

**If torsion exceeds allowable, provide supplemental design for footing torsion.**

#### Other Acceptable Sizes & Spacings

Toe: #4@ 9.25 in, #5@ 14.35 in, #6@ 20.37 in, #7@ 27.77 in, #8@ 36.57 in, #9@ 46.29 in, #10@ 58.79 in

Heel: #4@ 9.25 in, #5@ 14.35 in, #6@ 20.37 in, #7@ 27.77 in, #8@ 36.57 in, #9@ 46.29 in, #10@ 58.79 in

Key: No key defined

Min footing T&S reinf Area	1.30	in <sup>2</sup>
Min footing T&S reinf Area per foot	0.26	in <sup>2</sup> /ft

#### If one layer of horizontal bars:

#4@ 9.26 in  
#5@ 14.35 in  
#6@ 20.37 in

#### If two layers of horizontal bars:

#4@ 18.52 in  
#5@ 28.70 in  
#6@ 40.74 in

# Cantilevered Retaining Wall

Project File: Foundation Retaining.ec6

LIC# : KW-06017913, Build:20.24.08.01

MULHERN & KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

## DESCRIPTION: 8'-9" Basement Wall

### Summary of Overturning & Resisting Forces & Moments

Item	.....OVERTURNING.....				.....RESISTING.....			
	Force lbs	Distance ft	Moment ft-#		Force lbs	Distance ft	Moment ft-#	
HL Act Pres (ab water tbl)	1,663.6	3.25	5,406.7	Soil Over HL (ab. water tbl)	2,727.1	3.58	9,772.0	
HL Act Pres (be water tbl)				Soil Over HL (bel. water tbl)		3.58	9,772.0	
Hydrostatic Force				Water Table				
Buoyant Force	=			Sloped Soil Over Heel	=			
Surcharge over Heel	=			Surcharge Over Heel	=			
Surcharge Over Toe	=			Adjacent Footing Load	=			
Adjacent Footing Load	=			Axial Dead Load on Stem	=			
Added Lateral Load	=			* Axial Live Load on Stem	=			
Load @ Stem Above Soil	=			Soil Over Toe	=			
Seismic Earth Load	=	465.8	4.88	2,270.8	Surcharge Over Toe	=		
	=			Stem Weight(s)	=	950.0	1.83	1,741.7
<b>Total</b>	=	2,129.4	<b>O.T.M. =</b>	7,677.5	Earth @ Stem Transitions	=		
				Footing Weight	=	750.0	2.50	1,875.0
				Key Weight	=			
				Vert. Component	=	734.3	5.00	3,671.7
				<b>Total =</b>	<b>5,161.4 lbs</b>	<b>R.M.=</b>	<b>17,060.4</b>	

#### Resisting/Overturning Ratio

= **2.22**  
Vertical Loads used for Soil Pressure = 5,161.4 lbs

\* Axial live load NOT included in total displayed, or used for overturning resistance, but is included for soil pressure calculation.

If seismic is included, the OTM and sliding ratios may be 1.1 per section 1807.2.3 of IBC.

Vertical component of active lateral soil pressure IS considered in the calculation of Sliding Resistance.

Vertical component of active lateral soil pressure IS considered in the calculation of Overturning Resistance.

### Tilt

#### Horizontal Deflection at Top of Wall due to settlement of soil

(Deflection due to wall bending not considered)

Soil Spring Reaction Modulus 250.0 pci  
Horizontal Defl @ Top of Wall (approximate only) 0.099 in

The above calculation is not valid if the heel soil bearing pressure exceeds that of the toe, because the wall would then tend to rotate into the retained soil.

## Cantilevered Retaining Wall

Project File: Foundation Retaining.ec6

LIC# : KW-06017913, Build:20.24.08.01

MULHERN & KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

### DESCRIPTION: 8'-9" Basement Wall

---

#### Rebar Lap & Embedment Lengths Information

##### Stem Design Segment: 2nd

Stem Design Height: 4.00 ft above top of footing

Lap Splice length for #5 bar specified in this stem design segment (25.4.2.4a) = 23.40 in  
Development length for #5 bar specified in this stem design segment = 18.00 in

---

##### Stem Design Segment: Bottom

Stem Design Height: 0.00 ft above top of footing

Lap Splice length for #5 bar specified in this stem design segment (25.4.2.4a) = 23.40 in  
Development length for #5 bar specified in this stem design segment = 18.00 in

Hooked embedment length into footing for #5 bar specified in this stem design segment = 6.00 in  
As Provided = 0.4650 in<sup>2</sup>/ft  
As Required = 0.3187 in<sup>2</sup>/ft

# Cantilevered Retaining Wall


Project File: Foundation Retaining.ec6

LIC# : KW-06017913, Build:20.24.08.01

MULHERN & KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

**DESCRIPTION:** 8'-9" Basement Wall



# Cantilevered Retaining Wall

Project File: Foundation Retaining.ec6

LIC# : KW-06017913, Build:20.24.08.01

MULHERN & KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

**DESCRIPTION:** 8'-9" Basement Wall



## Concrete Beam

Project File: Foundation Retaining.ec6

LIC#: KW-06017913, Build:20.24.08.01

MULHERN &amp; KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

### DESCRIPTION: Beam Spanning Wall

### CODE REFERENCES



Calculations per ACI 318-19, IBC 2021, ASCE 7-16

Load Combination Set : ASCE 7-22 / IBC 2024 (L&lt;=100psf)

### General Information

$f'_c$	=	3.0 ksi	$\phi$ Phi Values	Flexure :	0.90
$f_r = f'_c^{1/2} * 7.50$	=	410.792 psi		Shear :	0.750
$\psi$ Density	=	145.0 pcf	$\beta_1$	=	0.850
$\lambda$ LtWt Factor	=	1.0			
Elastic Modulus	=	3,122.0 ksi	Fy - Stirrups	=	40.0 ksi
$f_y$ - Main Rebar	=	60.0 ksi	E - Stirrups	=	29,000.0 ksi
E - Main Rebar	=	29,000.0 ksi	Stirrup Bar Size #	=	3
		Number of Resisting Legs Per Stirrup =			2

Seismic Design Category = A



### Cross Section & Reinforcing Details

Rectangular Section, Width = 16.0 in, Height = 8.0 in

Span #1 Reinforcing....

1-#5 at 1.50 in from Bottom, from 0.0 to 4.250 ft in this span

### Load for Span Number 1

Uniform Load : E = 0.06520, H = 0.2172 k/ft, Tributary Width = 1.0 ft

### DESIGN SUMMARY

Design OK

Maximum Bending Stress Ratio =	0.107 : 1
Section used for this span	Typical Section
Mu : Applied	0.9318 k-ft
Mn * Phi : Allowable	8.750 k-ft
Location of maximum on span	2.121 ft
Span # where maximum occurs	Span # 1

### Maximum Deflection

Max Downward Transient Deflection	0.000 in	Ratio =	0 <360.0	E Only
Max Upward Transient Deflection	0.000 in	Ratio =	0 <360.0	E Only
Max Downward Total Deflection	0.000 in	Ratio =	0 <180.0	Span: 1 : +0.70E+H
Max Upward Total Deflection	0.000 in	Ratio =	0 <180.0	Span: 1 : +0.70E+H

### Vertical Reactions

Support notation : Far left is #1

Load Combination	Support 1	Support 2
Max Upward from all Load Conditions	0.559	0.559
Max Upward from Load Combinations	0.559	0.559
Max Upward from Load Cases	0.462	0.462
H Only	0.462	0.462
+0.60H	0.277	0.277
+0.70E+H	0.559	0.559
+0.5250E+H	0.534	0.534
+0.70E+0.60H	0.374	0.374

# Concrete Beam

Project File: Foundation Retaining.ec6

LIC#: KW-06017913, Build:20.24.08.01

MULHERN & KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

## DESCRIPTION: Beam Spanning Wall

### Vertical Reactions

Support notation : Far left is #1

Load Combination	Support 1	Support 2
E Only	0.139	0.139

### Shear Stirrup Requirements

Between 0.00 to 4.24 ft, Ties Not Req'd, Stirrups are not required.

### Detailed Shear Information

Load Combination	Span Number	Distance (ft)	'd' (in)	Vu (k)	Av, min Req'd?	Spacing Req'd (in)	Φ Vc (k)	Φ Vs (k)	Φ Vn (k)	Vu / Φ Vn	Vc Eqn (T22.5.5.1)	Spacing Provision
+E+1.60H	1	0.00	6.50	0.88	No	N/A	4.92	0.00	4.92	0.178	Eqn (b)	Ties Not Req'd
+E+1.60H	1	0.05	6.50	0.86	No	N/A	4.92	0.00	4.92	0.174	Eqn (b)	Ties Not Req'd
+E+1.60H	1	0.09	6.50	0.84	No	N/A	4.92	0.00	4.92	0.171	Eqn (b)	Ties Not Req'd
+E+1.60H	1	0.14	6.50	0.82	No	N/A	4.92	0.00	4.92	0.167	Eqn (b)	Ties Not Req'd
+E+1.60H	1	0.19	6.50	0.80	No	N/A	4.92	0.00	4.92	0.163	Eqn (b)	Ties Not Req'd
+E+1.60H	1	0.23	6.50	0.78	No	N/A	4.92	0.00	4.92	0.159	Eqn (b)	Ties Not Req'd
+E+1.60H	1	0.28	6.50	0.76	No	N/A	4.92	0.00	4.92	0.155	Eqn (b)	Ties Not Req'd
+E+1.60H	1	0.33	6.50	0.74	No	N/A	4.92	0.00	4.92	0.151	Eqn (b)	Ties Not Req'd
+E+1.60H	1	0.37	6.50	0.72	No	N/A	4.92	0.00	4.92	0.147	Eqn (b)	Ties Not Req'd
+E+1.60H	1	0.42	6.50	0.70	No	N/A	4.92	0.00	4.92	0.143	Eqn (b)	Ties Not Req'd
+E+1.60H	1	0.46	6.50	0.69	No	N/A	4.92	0.00	4.92	0.139	Eqn (b)	Ties Not Req'd
+E+1.60H	1	0.51	6.50	0.67	No	N/A	4.92	0.00	4.92	0.135	Eqn (b)	Ties Not Req'd
+E+1.60H	1	0.56	6.50	0.65	No	N/A	4.92	0.00	4.92	0.132	Eqn (b)	Ties Not Req'd
+E+1.60H	1	0.60	6.50	0.63	No	N/A	4.92	0.00	4.92	0.128	Eqn (b)	Ties Not Req'd
+E+1.60H	1	0.65	6.50	0.61	No	N/A	4.92	0.00	4.92	0.124	Eqn (b)	Ties Not Req'd
+E+1.60H	1	0.70	6.50	0.59	No	N/A	4.92	0.00	4.92	0.120	Eqn (b)	Ties Not Req'd
+E+1.60H	1	0.74	6.50	0.57	No	N/A	4.92	0.00	4.92	0.116	Eqn (b)	Ties Not Req'd
+E+1.60H	1	0.79	6.50	0.55	No	N/A	4.92	0.00	4.92	0.112	Eqn (b)	Ties Not Req'd
+E+1.60H	1	0.84	6.50	0.53	No	N/A	4.92	0.00	4.92	0.108	Eqn (b)	Ties Not Req'd
+E+1.60H	1	0.88	6.50	0.51	No	N/A	4.92	0.00	4.92	0.104	Eqn (b)	Ties Not Req'd
+E+1.60H	1	0.93	6.50	0.49	No	N/A	4.92	0.00	4.92	0.100	Eqn (b)	Ties Not Req'd
+E+1.60H	1	0.98	6.50	0.47	No	N/A	4.92	0.00	4.92	0.096	Eqn (b)	Ties Not Req'd
+E+1.60H	1	1.02	6.50	0.46	No	N/A	4.92	0.00	4.92	0.093	Eqn (b)	Ties Not Req'd
+E+1.60H	1	1.07	6.50	0.44	No	N/A	4.92	0.00	4.92	0.089	Eqn (b)	Ties Not Req'd
+E+1.60H	1	1.11	6.50	0.42	No	N/A	4.92	0.00	4.92	0.085	Eqn (b)	Ties Not Req'd
+E+1.60H	1	1.16	6.50	0.40	No	N/A	4.92	0.00	4.92	0.081	Eqn (b)	Ties Not Req'd
+E+1.60H	1	1.21	6.50	0.38	No	N/A	4.92	0.00	4.92	0.077	Eqn (b)	Ties Not Req'd
+E+1.60H	1	1.25	6.50	0.36	No	N/A	4.92	0.00	4.92	0.073	Eqn (b)	Ties Not Req'd
+E+1.60H	1	1.30	6.50	0.34	No	N/A	4.92	0.00	4.92	0.069	Eqn (b)	Ties Not Req'd
+E+1.60H	1	1.35	6.50	0.32	No	N/A	4.92	0.00	4.92	0.065	Eqn (b)	Ties Not Req'd
+E+1.60H	1	1.39	6.50	0.30	No	N/A	4.92	0.00	4.92	0.061	Eqn (b)	Ties Not Req'd
+E+1.60H	1	1.44	6.50	0.28	No	N/A	4.92	0.00	4.92	0.057	Eqn (b)	Ties Not Req'd
+E+1.60H	1	1.49	6.50	0.26	No	N/A	4.92	0.00	4.92	0.054	Eqn (b)	Ties Not Req'd
+E+1.60H	1	1.53	6.50	0.24	No	N/A	4.92	0.00	4.92	0.050	Eqn (b)	Ties Not Req'd
+E+1.60H	1	1.58	6.50	0.23	No	N/A	4.92	0.00	4.92	0.046	Eqn (b)	Ties Not Req'd
+E+1.60H	1	1.63	6.50	0.21	No	N/A	4.92	0.00	4.92	0.042	Eqn (b)	Ties Not Req'd
+E+1.60H	1	1.67	6.50	0.19	No	N/A	4.92	0.00	4.92	0.038	Eqn (b)	Ties Not Req'd
+E+1.60H	1	1.72	6.50	0.17	No	N/A	4.92	0.00	4.92	0.034	Eqn (b)	Ties Not Req'd
+E+1.60H	1	1.77	6.50	0.15	No	N/A	4.92	0.00	4.92	0.030	Eqn (b)	Ties Not Req'd
+E+1.60H	1	1.81	6.50	0.13	No	N/A	4.92	0.00	4.92	0.026	Eqn (b)	Ties Not Req'd
+E+1.60H	1	1.86	6.50	0.11	No	N/A	4.92	0.00	4.92	0.022	Eqn (b)	Ties Not Req'd
+E+1.60H	1	1.90	6.50	0.09	No	N/A	4.92	0.00	4.92	0.019	Eqn (b)	Ties Not Req'd
+E+1.60H	1	1.95	6.50	0.07	No	N/A	4.92	0.00	4.92	0.015	Eqn (b)	Ties Not Req'd
+E+1.60H	1	2.00	6.50	0.05	No	N/A	4.92	0.00	4.92	0.011	Eqn (b)	Ties Not Req'd
+E+1.60H	1	2.04	6.50	0.03	No	N/A	4.92	0.00	4.92	0.007	Eqn (b)	Ties Not Req'd
+E+1.60H	1	2.09	6.50	0.01	No	N/A	4.92	0.00	4.92	0.003	Eqn (b)	Ties Not Req'd
+E+1.60H	1	2.14	6.50	-0.00	No	N/A	4.92	0.00	4.92	0.001	Eqn (b)	Ties Not Req'd
+E+1.60H	1	2.18	6.50	-0.02	No	N/A	4.92	0.00	4.92	0.005	Eqn (b)	Ties Not Req'd
+E+1.60H	1	2.23	6.50	-0.04	No	N/A	4.92	0.00	4.92	0.009	Eqn (b)	Ties Not Req'd
+E+1.60H	1	2.28	6.50	-0.06	No	N/A	4.92	0.00	4.92	0.013	Eqn (b)	Ties Not Req'd
+E+1.60H	1	2.32	6.50	-0.08	No	N/A	4.92	0.00	4.92	0.017	Eqn (b)	Ties Not Req'd
+E+1.60H	1	2.37	6.50	-0.10	No	N/A	4.92	0.00	4.92	0.020	Eqn (b)	Ties Not Req'd
+E+1.60H	1	2.42	6.50	-0.12	No	N/A	4.92	0.00	4.92	0.024	Eqn (b)	Ties Not Req'd
+E+1.60H	1	2.46	6.50	-0.14	No	N/A	4.92	0.00	4.92	0.028	Eqn (b)	Ties Not Req'd
+E+1.60H	1	2.51	6.50	-0.16	No	N/A	4.92	0.00	4.92	0.032	Eqn (b)	Ties Not Req'd
+E+1.60H	1	2.55	6.50	-0.18	No	N/A	4.92	0.00	4.92	0.036	Eqn (b)	Ties Not Req'd
+E+1.60H	1	2.60	6.50	-0.20	No	N/A	4.92	0.00	4.92	0.040	Eqn (b)	Ties Not Req'd
+E+1.60H	1	2.65	6.50	-0.22	No	N/A	4.92	0.00	4.92	0.044	Eqn (b)	Ties Not Req'd
+E+1.60H	1	2.69	6.50	-0.23	No	N/A	4.92	0.00	4.92	0.048	Eqn (b)	Ties Not Req'd
+E+1.60H	1	2.74	6.50	-0.25	No	N/A	4.92	0.00	4.92	0.052	Eqn (b)	Ties Not Req'd

# Concrete Beam

Project File: Foundation Retaining.ec6

LIC# : KW-06017913, Build:20.24.08.01

MULHERN & KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

## DESCRIPTION: Beam Spanning Wall

### Detailed Shear Information

Load Combination	Span Number	Distance (ft)	'd' (in)	Vu (k)	Av, min Req'd?	Spacing Req'd (in)	$\phi Vc$ (k)	$\phi Vs$ (k)	$\phi Vn$ (k)	Vu / $\phi Vn$	Vc Eqn (T22.5.5.1)	Spacing Provision
+E+1.60H	1	2.79	6.50	-0.27	No	N/A	4.92	0.00	4.92	0.056	Eqn (b)	Ties Not Req'd
+E+1.60H	1	2.83	6.50	-0.29	No	N/A	4.92	0.00	4.92	0.059	Eqn (b)	Ties Not Req'd
+E+1.60H	1	2.88	6.50	-0.31	No	N/A	4.92	0.00	4.92	0.063	Eqn (b)	Ties Not Req'd
+E+1.60H	1	2.93	6.50	-0.33	No	N/A	4.92	0.00	4.92	0.067	Eqn (b)	Ties Not Req'd
+E+1.60H	1	2.97	6.50	-0.35	No	N/A	4.92	0.00	4.92	0.071	Eqn (b)	Ties Not Req'd
+E+1.60H	1	3.02	6.50	-0.37	No	N/A	4.92	0.00	4.92	0.075	Eqn (b)	Ties Not Req'd
+E+1.60H	1	3.07	6.50	-0.39	No	N/A	4.92	0.00	4.92	0.079	Eqn (b)	Ties Not Req'd
+E+1.60H	1	3.11	6.50	-0.41	No	N/A	4.92	0.00	4.92	0.083	Eqn (b)	Ties Not Req'd
+E+1.60H	1	3.16	6.50	-0.43	No	N/A	4.92	0.00	4.92	0.087	Eqn (b)	Ties Not Req'd
+E+1.60H	1	3.20	6.50	-0.45	No	N/A	4.92	0.00	4.92	0.091	Eqn (b)	Ties Not Req'd
+E+1.60H	1	3.25	6.50	-0.46	No	N/A	4.92	0.00	4.92	0.095	Eqn (b)	Ties Not Req'd
+E+1.60H	1	3.30	6.50	-0.48	No	N/A	4.92	0.00	4.92	0.098	Eqn (b)	Ties Not Req'd
+E+1.60H	1	3.34	6.50	-0.50	No	N/A	4.92	0.00	4.92	0.102	Eqn (b)	Ties Not Req'd
+E+1.60H	1	3.39	6.50	-0.52	No	N/A	4.92	0.00	4.92	0.106	Eqn (b)	Ties Not Req'd
+E+1.60H	1	3.44	6.50	-0.54	No	N/A	4.92	0.00	4.92	0.110	Eqn (b)	Ties Not Req'd
+E+1.60H	1	3.48	6.50	-0.56	No	N/A	4.92	0.00	4.92	0.114	Eqn (b)	Ties Not Req'd
+E+1.60H	1	3.53	6.50	-0.58	No	N/A	4.92	0.00	4.92	0.118	Eqn (b)	Ties Not Req'd
+E+1.60H	1	3.58	6.50	-0.60	No	N/A	4.92	0.00	4.92	0.122	Eqn (b)	Ties Not Req'd
+E+1.60H	1	3.62	6.50	-0.62	No	N/A	4.92	0.00	4.92	0.126	Eqn (b)	Ties Not Req'd
+E+1.60H	1	3.67	6.50	-0.64	No	N/A	4.92	0.00	4.92	0.130	Eqn (b)	Ties Not Req'd
+E+1.60H	1	3.72	6.50	-0.66	No	N/A	4.92	0.00	4.92	0.133	Eqn (b)	Ties Not Req'd
+E+1.60H	1	3.76	6.50	-0.68	No	N/A	4.92	0.00	4.92	0.137	Eqn (b)	Ties Not Req'd
+E+1.60H	1	3.81	6.50	-0.69	No	N/A	4.92	0.00	4.92	0.141	Eqn (b)	Ties Not Req'd
+E+1.60H	1	3.86	6.50	-0.71	No	N/A	4.92	0.00	4.92	0.145	Eqn (b)	Ties Not Req'd
+E+1.60H	1	3.90	6.50	-0.73	No	N/A	4.92	0.00	4.92	0.149	Eqn (b)	Ties Not Req'd
+E+1.60H	1	3.95	6.50	-0.75	No	N/A	4.92	0.00	4.92	0.153	Eqn (b)	Ties Not Req'd
+E+1.60H	1	3.99	6.50	-0.77	No	N/A	4.92	0.00	4.92	0.157	Eqn (b)	Ties Not Req'd
+E+1.60H	1	4.04	6.50	-0.79	No	N/A	4.92	0.00	4.92	0.161	Eqn (b)	Ties Not Req'd
+E+1.60H	1	4.09	6.50	-0.81	No	N/A	4.92	0.00	4.92	0.165	Eqn (b)	Ties Not Req'd
+E+1.60H	1	4.13	6.50	-0.83	No	N/A	4.92	0.00	4.92	0.169	Eqn (b)	Ties Not Req'd
+E+1.60H	1	4.18	6.50	-0.85	No	N/A	4.92	0.00	4.92	0.172	Eqn (b)	Ties Not Req'd
+E+1.60H	1	4.23	6.50	-0.87	No	N/A	4.92	0.00	4.92	0.176	Eqn (b)	Ties Not Req'd

### Maximum Forces & Stresses for Load Combinations

Load Combination Segment	Span #	Location (ft) along Beam	Bending Stress Results (k-ft)		
			Mu : Max	Phi*Mnx	Stress Ratio
MAXimum BENDING Envelope					
Span # 1	1	4.250	0.93	8.75	0.11
+1.60H					
Span # 1	1	4.250	0.78	8.75	0.09
+0.90H					
Span # 1	1	4.250	0.44	8.75	0.05
+E+1.60H					
Span # 1	1	4.250	0.93	8.75	0.11
+E+0.90H					
Span # 1	1	4.250	0.59	8.75	0.07

### Overall Maximum Deflections

Load Combination	Span	Max. "-" Defl (in)	Location in Span (ft)	Load Combination	Max. "+" Defl (in)	Location in Span (ft)
+0.70E+H	1	0.0009	2.125		0.0000	0.000

# Cantilevered Retaining Wall

Project File: Foundation Retaining.ec6

LIC# : KW-06017913, Build:20.24.08.01

MULHERN & KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

**DESCRIPTION:** 5'-9" Crawspace Wall

## Code Reference


Calculations per IBC 2021 1807.3, ASCE 7-16

### Criteria

Retained Height	=	5.75 ft
Wall height above soil	=	0.75 ft
Slope Behind Wall	=	0.00
Height of Soil over Toe	=	0.00 in
Water table above bottom of footing	=	0.0 ft

### Soil Data

Allow Soil Bearing	=	1,500.0 psf
Equivalent Fluid Pressure Method		
Active Heel Pressure	=	35.0 psf/ft
Passive Pressure	=	250.0 psf/ft
Soil Density, Heel	=	110.00 pcf
Soil Density, Toe	=	110.00 pcf
Footing  Soil Friction	=	0.400
Soil height to ignore for passive pressure	=	12.00 in



### Surcharge Loads

Surcharge Over Heel	=	0.0 psf
Used To Resist Sliding & Overturning		
Surcharge Over Toe	=	0.0 psf
Used for Sliding & Overturning		

### Axial Load Applied to Stem

Axial Dead Load	=	0.0 lbs
Axial Live Load	=	0.0 lbs
Axial Load Eccentricity	=	0.0 in

### Earth Pressure Seismic Load

Method	:	Uniform
Multiplier Used	=	7.000
(Multiplier used on soil density)		

### Lateral Load Applied to Stem

Lateral Load	=	0.0 #/ft
...Height to Top	=	0.00 ft
...Height to Bottom	=	0.00 ft
Load Type	=	Wind (W) (Service Level)
Wind on Exposed Stem	=	0.0 psf
(Strength Level)		

Uniform Seismic Force	=	47.250
Total Seismic Force	=	318.938

### Adjacent Footing Load

Adjacent Footing Load	=	0.0 lbs
Footing Width	=	0.00 ft
Eccentricity	=	0.00 in
Wall to Ftg CL Dist	=	0.00 ft
Footing Type	=	Spread Footing
Base Above/Below Soil at Back of Wall	=	0.0 ft
Poisson's Ratio	=	0.300

# Cantilevered Retaining Wall

Project File: Foundation Retaining.ec6

LIC# : KW-06017913, Build:20.24.08.01

MULHERN & KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

## DESCRIPTION: 5'-9" Crawspace Wall

### Design Summary

#### Wall Stability Ratios

Overturing	=	1.68	OK
Slab Resists All Sliding !			
Global Stability	=	0.99	
Total Bearing Load	=	1,979 lbs	
...resultant ecc.	=	7.47 in	
Eccentricity outside middle third			
Soil Pressure @ Toe	=	1,503 psf	NG
Soil Pressure @ Heel	=	0 psf	OK
Allowable	=	1,500 psf	
Soil Pressure Exceeds Allowable!			
ACI Factored @ Toe	=	1,731 psf	
ACI Factored @ Heel	=	0 psf	
Footing Shear @ Toe	=	8.5 psi	OK
Footing Shear @ Heel	=	10.6 psi	OK
Allowable	=	75.0 psi	

#### Sliding Calcs

Lateral Sliding Force	=	1,020.6 lbs
-----------------------	---	-------------

SOIL PRESSURE @ TOE IS ADEQUATE  
DUE TO 33% INCREASE TO SOIL BEARING  
PRESSURE FROM SEISMIC SURCHARGE

Vertical component of active lateral soil pressure IS  
considered in the calculation of soil bearing pressures.

#### Load Factors

Building Code	
Dead Load	1.200
Live Load	1.600
Earth, H	1.600
Wind, W	1.600
Seismic, E	1.000

### Stem Construction

		2nd	Bottom		
<b>Design Height Above Ftg</b>	ft =	Stem OK 4.00	Stem OK 0.00		
Wall Material Above "Ht"	=	Concrete	Concrete		
Design Method	=	SD	SD	SD	SD
Thickness	=	8.00	8.00		
Rebar Size	=	# 5	# 5		
Rebar Spacing	=	16.00	16.00		
Rebar Placed at	=	6.5 in	6.5 in		
<b>Design Data</b>					
fb/FB + fa/Fa	=	<b>0.018</b>	<b>0.392</b>		
<b>Total Force @ Section</b>					
Service Level	lbs =				
Strength Level	lbs =	168.4	1,197.4		
<b>Moment....Actual</b>					
Service Level	ft-# =				
Strength Level	ft-# =	122.4	2,555.5		
Moment....Allowable	ft-# =	6,513.6	6,513.6		
<b>Shear.....Actual</b>					
Service Level	psi =				
Strength Level	psi =	2.2	15.4		
Shear.....Allowable	psi =	43.2	43.2		
Anet (Masonry)	in2 =				
Wall Weight	psf =	100.0	100.0		
Rebar Depth 'd'	in =	6.50	6.50		

#### Masonry Data

f'm	psi =
Fs	psi =
Solid Grouting	=
Modular Ratio 'n'	=
Equiv. Solid Thick.	=
Masonry Block Type	=
Masonry Design Method	= ASD

#### Concrete Data

f'c	psi =	2,500.0	2,500.0
Fy	psi =	60,000.0	60,000.0

# Cantilevered Retaining Wall

Project File: Foundation Retaining.ec6

LIC# : KW-06017913, Build:20.24.08.01

MULHERN & KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

## DESCRIPTION: 5'-9" Crawspace Wall

### Concrete Stem Rebar Area Details

2nd Stem	<u>Vertical Reinforcing</u>	<u>Horizontal Reinforcing</u>	
As (based on applied moment) :	0.0044 in2/ft	Horizontal Reinforcing Options :	
0.0018bh : 0.0018(12)(8) :	0.1728 in2/ft	<u>One layer of :</u> <u>Two layers of :</u>	
	=====	#4@ 13.89 in	#4@ 27.78 in
Required Area :	0.1728 in2/ft	#5@ 21.53 in	#5@ 43.06 in
Provided Area :	0.2325 in2/ft	#6@ 30.56 in	#6@ 61.11 in
Maximum Area :	0.8805 in2/ft		

Bottom Stem	<u>Vertical Reinforcing</u>	<u>Horizontal Reinforcing</u>	
As (based on applied moment) :	0.0919 in2/ft	Horizontal Reinforcing Options :	
0.0018bh : 0.0018(12)(8) :	0.1728 in2/ft	<u>One layer of :</u> <u>Two layers of :</u>	
	=====	#4@ 13.89 in	#4@ 27.78 in
Required Area :	0.1728 in2/ft	#5@ 21.53 in	#5@ 43.06 in
Provided Area :	0.2325 in2/ft	#6@ 30.56 in	#6@ 61.11 in
Maximum Area :	0.8805 in2/ft		

### Footing Data

Toe Width	=	1.50 ft
Heel Width	=	1.50
Total Footing Width	=	3.00
Footing Thickness	=	12.00 in
f'c =	2,500 psi	Fy = 60,000 psi
Footing Concrete Density	=	150.00 pcf
Min. As %	=	0.0018
Cover @ Top	2.00	@ Btm.= 3.00 in

### Footing Design Results

		<u>Toe</u>	<u>Heel</u>	
Factored Pressure	=	1,731	0	psf
Mu' : Upward	=	1,577	11	ft-#
Mu' : Downward	=	203	795	ft-#
Mu: Design	=	1,375	784	ft-#
φ Mn	=	2,500	2,500	ft-#
Actual 1-Way Shear	=	8.51	10.62	psi
Allow 1-Way Shear	=	40.00	40.00	psi
Toe Reinforcing	=	None Spec'd		
Heel Reinforcing	=	None Spec'd		
Key Reinforcing	=	None Spec'd		
Footing Torsion, Tu	=	0.00 ft-lbs		
Footing Allow. Torsion, φ Tn	=	0.00 ft-lbs		

**If torsion exceeds allowable, provide supplemental design for footing torsion.**

#### Other Acceptable Sizes & Spacings

Toe:  $\phi Mn = \phi * 5 * \lambda * \sqrt{fc} * Sm$

Heel:  $\phi Mn = \phi * 5 * \lambda * \sqrt{fc} * Sm$

Key: No key defined

Min footing T&S reinf Area	0.78	in2
Min footing T&S reinf Area per foot	0.26	in2 /ft

#### If one layer of horizontal bars:

#4@	9.26 in
#5@	14.35 in
#6@	20.37 in

#### If two layers of horizontal bars:

#4@	18.52 in
#5@	28.70 in
#6@	40.74 in

# Cantilevered Retaining Wall

Project File: Foundation Retaining.ec6

LIC# : KW-06017913, Build:20.24.08.01

MULHERN & KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

## DESCRIPTION: 5'-9" Crawspace Wall

### Summary of Overturning & Resisting Forces & Moments

Item	.....OVERTURNING.....			.....RESISTING.....			
	Force lbs	Distance ft	Moment ft-#	Force lbs	Distance ft	Moment ft-#	
HL Act Pres (ab water tbl)	797.3	2.25	1,794.0	Soil Over HL (ab. water tbl)	527.1	2.58	1,361.6
HL Act Pres (be water tbl)				Soil Over HL (bel. water tbl)		2.58	1,361.6
Hydrostatic Force				Water Table			
Buoyant Force =				Sloped Soil Over Heel =			
Surcharge over Heel =				Surcharge Over Heel =			
Surcharge Over Toe =				Adjacent Footing Load =			
Adjacent Footing Load =				Axial Dead Load on Stem =			
Added Lateral Load =				* Axial Live Load on Stem =			
Load @ Stem Above Soil =				Soil Over Toe =			
Seismic Earth Load =	223.3	3.38	753.5	Surcharge Over Toe =			
				Stem Weight(s) =	650.0	1.83	1,191.7
				Earth @ Stem Transitions =			
<b>Total</b>	<b>= 1,020.6</b>	<b>O.T.M. =</b>	<b>2,547.5</b>	Footing Weight =	450.0	1.50	675.0
				Key Weight =			
<b>Resisting/Overturning Ratio</b>		<b>= 1.68</b>		Vert. Component =	352.0	3.00	1,055.9
Vertical Loads used for Soil Pressure =		1,979.0 lbs		<b>Total =</b>	<b>1,979.0 lbs</b>	<b>R.M.=</b>	<b>4,284.2</b>

\* Axial live load NOT included in total displayed, or used for overturning resistance, but is included for soil pressure calculation.

If seismic is included, the OTM and sliding ratios may be 1.1 per section 1807.2.3 of IBC.

Vertical component of active lateral soil pressure IS considered in the calculation of Sliding Resistance.

Vertical component of active lateral soil pressure IS considered in the calculation of Overturning Resistance.

### Tilt

#### Horizontal Deflection at Top of Wall due to settlement of soil

(Deflection due to wall bending not considered)

Soil Spring Reaction Modulus 250.0 pci  
 Horizontal Defl @ Top of Wall (approximate only) 0.090 in

The above calculation is not valid if the heel soil bearing pressure exceeds that of the toe, because the wall would then tend to rotate into the retained soil.

## Cantilevered Retaining Wall

Project File: Foundation Retaining.ec6

LIC# : KW-06017913, Build:20.24.08.01

MULHERN & KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

**DESCRIPTION:** 5'-9" Crawlspace Wall

---

### Rebar Lap & Embedment Lengths Information

#### Stem Design Segment: 2nd

Stem Design Height: 4.00 ft above top of footing

Lap Splice length for #5 bar specified in this stem design segment (25.4.2.4a) = 23.40 in  
Development length for #5 bar specified in this stem design segment = 18.00 in

---

#### Stem Design Segment: Bottom

Stem Design Height: 0.00 ft above top of footing

Lap Splice length for #5 bar specified in this stem design segment (25.4.2.4a) = 23.40 in  
Development length for #5 bar specified in this stem design segment = 18.00 in

Hooked embedment length into footing for #5 bar specified in this stem design segment = 6.00 in  
As Provided = 0.2325 in<sup>2</sup>/ft  
As Required = 0.1728 in<sup>2</sup>/ft

# Cantilevered Retaining Wall


Project File: Foundation Retaining.ec6

LIC# : KW-06017913, Build:20.24.08.01

MULHERN & KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

**DESCRIPTION:** 5'-9" Crawlspace Wall



# Cantilevered Retaining Wall


Project File: Foundation Retaining.ec6

LIC# : KW-06017913, Build:20.24.08.01

MULHERN & KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

**DESCRIPTION:** 5'-9" Crawlspace Wall



# Cantilevered Retaining Wall

Project File: Foundation Retaining.ec6

LIC# : KW-06017913, Build:20.24.08.01

MULHERN & KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

**DESCRIPTION:** 9'-9" Basement Wall

## Code Reference


Calculations per IBC 2021 1807.3, ASCE 7-16

### Criteria

Retained Height	=	9.75 ft
Wall height above soil	=	1.25 ft
Slope Behind Wall	=	0.00
Height of Soil over Toe	=	0.00 in
Water table above bottom of footing	=	0.0 ft

### Soil Data

Allow Soil Bearing	=	1,500.0 psf
Equivalent Fluid Pressure Method		
Active Heel Pressure	=	35.0 psf/ft
Passive Pressure	=	250.0 psf/ft
Soil Density, Heel	=	110.00 pcf
Soil Density, Toe	=	110.00 pcf
Footing  Soil Friction	=	0.400
Soil height to ignore for passive pressure	=	12.00 in



### Surcharge Loads

Surcharge Over Heel	=	0.0 psf
Used To Resist Sliding & Overturning		
Surcharge Over Toe	=	0.0 psf
Used for Sliding & Overturning		

### Axial Load Applied to Stem

Axial Dead Load	=	0.0 lbs
Axial Live Load	=	0.0 lbs
Axial Load Eccentricity	=	0.0 in

### Earth Pressure Seismic Load

Method	:	Uniform
Multiplier Used	=	7.000
(Multiplier used on soil density)		

### Lateral Load Applied to Stem

Lateral Load	=	0.0 #/ft
...Height to Top	=	0.00 ft
...Height to Bottom	=	0.00 ft
Load Type	=	Wind (W) (Service Level)
Wind on Exposed Stem	=	0.0 psf (Strength Level)

Uniform Seismic Force	=	75.250
Total Seismic Force	=	808.938

### Adjacent Footing Load

Adjacent Footing Load	=	0.0 lbs
Footing Width	=	0.00 ft
Eccentricity	=	0.00 in
Wall to Ftg CL Dist	=	0.00 ft
Footing Type	=	Spread Footing
Base Above/Below Soil at Back of Wall	=	0.0 ft
Poisson's Ratio	=	0.300

# Cantilevered Retaining Wall

Project File: Foundation Retaining.ec6

LIC# : KW-06017913, Build:20.24.08.01

MULHERN & KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

## DESCRIPTION: 9'-9" Basement Wall

### Design Summary

#### Wall Stability Ratios

Overturning	=	2.15	OK
Slab Resists All Sliding !			
Global Stability	=	1.59	
Total Bearing Load	=	5,856	lbs
...resultant ecc.	=	8.69	in
Eccentricity within middle third			
Soil Pressure @ Toe	=	1,906	psf NG
Soil Pressure @ Heel	=	223	psf OK
Allowable	=	1,500	psf
Soil Pressure Exceeds Allowable!			
ACI Factored @ Toe	=	2,262	psf
ACI Factored @ Heel	=	265	psf
Footing Shear @ Toe	=	23.4	psi OK
Footing Shear @ Heel	=	29.6	psi OK
Allowable	=	75.0	psi

#### Sliding Calcs

Lateral Sliding Force	=	2,588.6	lbs
-----------------------	---	---------	-----

SOIL PRESSURE @ TOE IS ADEQUATE  
DUE TO 33% INCREASE TO SOIL BEARING  
PRESSURE FROM SEISMIC SURCHARGE

Vertical component of active lateral soil pressure IS  
considered in the calculation of soil bearing pressures.

#### Load Factors

Building Code	
Dead Load	1.200
Live Load	1.600
Earth, H	1.600
Wind, W	1.600
Seismic, E	1.000

### Stem Construction

		2nd	Bottom		
<b>Design Height Above Ftg</b>	ft =	Stem OK 4.00	Stem OK 0.00		
Wall Material Above "Ht"	=	Concrete	Concrete		
Design Method	=	SD	SD	SD	SD
Thickness	=	8.00	8.00		
Rebar Size	=	# 5	# 5		
Rebar Spacing	=	16.00	8.00		
Rebar Placed at	=	6.5 in	6.5 in		
<b>Design Data</b>					
fb/FB + fa/Fa	=	<b>0.463</b>	<b>0.981</b>		
<b>Total Force @ Section</b>					
Service Level	lbs =				
Strength Level	lbs =	1,358.4	3,395.4		
<b>Moment....Actual</b>					
Service Level	ft-# =				
Strength Level	ft-# =	3,018.3	12,227.4		
Moment.....Allowable	ft-# =	6,513.6	12,453.1		
<b>Shear.....Actual</b>					
Service Level	psi =				
Strength Level	psi =	17.4	43.5		
Shear.....Allowable	psi =	43.2	54.4		
Anet (Masonry)	in2 =				
Wall Weight	psf =	100.0	100.0		
Rebar Depth 'd'	in =	6.50	6.50		

#### Masonry Data

f'm	psi =
Fs	psi =
Solid Grouting	=
Modular Ratio 'n'	=
Equiv. Solid Thick.	=
Masonry Block Type	=
Masonry Design Method	= ASD

#### Concrete Data

f'c	psi =	2,500.0	2,500.0
Fy	psi =	60,000.0	60,000.0

# Cantilevered Retaining Wall

Project File: Foundation Retaining.ec6

LIC# : KW-06017913, Build:20.24.08.01

MULHERN & KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

## DESCRIPTION: 9'-9" Basement Wall

### Concrete Stem Rebar Area Details

2nd Stem	<u>Vertical Reinforcing</u>	<u>Horizontal Reinforcing</u>
As (based on applied moment) :	0.1085 in <sup>2</sup> /ft	
0.0018bh : 0.0018(12)(8) :	0.1728 in <sup>2</sup> /ft	
	=====	
Required Area :	0.1728 in <sup>2</sup> /ft	Horizontal Reinforcing Options :
Provided Area :	0.2325 in <sup>2</sup> /ft	<u>One layer of :</u> <u>Two layers of :</u>
Maximum Area :	0.8805 in <sup>2</sup> /ft	#4@ 13.89 in    #4@ 27.78 in
		#5@ 21.53 in    #5@ 43.06 in
		#6@ 30.56 in    #6@ 61.11 in

---

Bottom Stem	<u>Vertical Reinforcing</u>	<u>Horizontal Reinforcing</u>
As (based on applied moment) :	0.4396 in <sup>2</sup> /ft	
0.0018bh : 0.0018(12)(8) :	0.1728 in <sup>2</sup> /ft	
	=====	
Required Area :	0.4396 in <sup>2</sup> /ft	Horizontal Reinforcing Options :
Provided Area :	0.465 in <sup>2</sup> /ft	<u>One layer of :</u> <u>Two layers of :</u>
Maximum Area :	0.8805 in <sup>2</sup> /ft	#4@ 13.89 in    #4@ 27.78 in
		#5@ 21.53 in    #5@ 43.06 in
		#6@ 30.56 in    #6@ 61.11 in

### Footing Data

Toe Width	=	2.00 ft
Heel Width	=	3.50
Total Footing Width	=	5.50
Footing Thickness	=	12.00 in

f'c =	2,500 psi	Fy =	60,000 psi
Footing Concrete Density	=	150.00 pcf	
Min. As %	=	0.0018	
Cover @ Top	2.00	@ Btm.=	3.00 in

### Footing Design Results

	<u>Toe</u>	<u>Heel</u>	
Factored Pressure	= 2,262	265	psf
Mu' : Upward	= 4,040	2,440	ft-#
Mu' : Downward	= 360	9,935	ft-#
Mu: Design	= 3,680	7,495	ft-#
φ Mn	= 17,034	13,005	ft-#
Actual 1-Way Shear	= 23.39	29.62	psi
Allow 1-Way Shear	= 49.38	41.60	psi
Toe Reinforcing	= # 5 @ 8.00 in		
Heel Reinforcing	= # 5 @ 12.00 in		
Key Reinforcing	= None Spec'd		
Footing Torsion, Tu	=	0.00	ft-lbs
Footing Allow. Torsion, φ Tn	=	0.00	ft-lbs

**If torsion exceeds allowable, provide supplemental design for footing torsion.**

#### Other Acceptable Sizes & Spacings

Toe: #4@ 9.25 in, #5@ 14.35 in, #6@ 20.37 in, #7@ 27.77 in, #8@ 36.57 in, #9@ 46.29 in, #10@ 58.79 in

Heel: #4@ 9.25 in, #5@ 14.35 in, #6@ 20.37 in, #7@ 27.77 in, #8@ 36.57 in, #9@ 46.29 in, #10@ 58.79 in

Key: No key defined

Min footing T&S reinf Area	1.43	in <sup>2</sup>
Min footing T&S reinf Area per foot	0.26	in <sup>2</sup> /ft

#### If one layer of horizontal bars:

#4@ 9.26 in  
#5@ 14.35 in  
#6@ 20.37 in

#### If two layers of horizontal bars:

#4@ 18.52 in  
#5@ 28.70 in  
#6@ 40.74 in

# Cantilevered Retaining Wall

Project File: Foundation Retaining.ec6

LIC# : KW-06017913, Build:20.24.08.01

MULHERN & KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

## DESCRIPTION: 9'-9" Basement Wall

### Summary of Overturning & Resisting Forces & Moments

Item	.....OVERTURNING.....			.....RESISTING.....				
	Force lbs	Distance ft	Moment ft-#	Force lbs	Distance ft	Moment ft-#		
HL Act Pres (ab water tbl)	2,022.3	3.58	7,246.7	Soil Over HL (ab. water tbl)	3,038.8	4.08	12,408.2	
HL Act Pres (be water tbl)				Soil Over HL (bel. water tbl)		4.08	12,408.2	
Hydrostatic Force				Water Table				
Buoyant Force	=			Sloped Soil Over Heel	=			
Surcharge over Heel	=			Surcharge Over Heel	=			
Surcharge Over Toe	=			Adjacent Footing Load	=			
Adjacent Footing Load	=			Axial Dead Load on Stem	=			
Added Lateral Load	=			* Axial Live Load on Stem	=			
Load @ Stem Above Soil	=			Soil Over Toe	=			
Seismic Earth Load	=	566.3	5.38	3,043.6	Surcharge Over Toe	=		
	=			Stem Weight(s)	=	1,100.0	2.33	2,566.7
<b>Total</b>	=	2,588.6	<b>O.T.M. =</b>	10,290.4	Earth @ Stem Transitions	=		
				Footing Weight	=	825.0	2.75	2,268.8
				Key Weight	=			
				Vert. Component	=	892.7	5.50	4,909.9
				<b>Total =</b>	<b>5,856.5 lbs</b>	<b>R.M.=</b>	<b>22,153.5</b>	

**Resisting/Overturning Ratio** = **2.15**  
 Vertical Loads used for Soil Pressure = 5,856.5 lbs

\* Axial live load NOT included in total displayed, or used for overturning resistance, but is included for soil pressure calculation.

If seismic is included, the OTM and sliding ratios may be 1.1 per section 1807.2.3 of IBC.

Vertical component of active lateral soil pressure IS considered in the calculation of Sliding Resistance.

Vertical component of active lateral soil pressure IS considered in the calculation of Overturning Resistance.

### Tilt

#### Horizontal Deflection at Top of Wall due to settlement of soil

(Deflection due to wall bending not considered)

Soil Spring Reaction Modulus 250.0 pci  
 Horizontal Defl @ Top of Wall (approximate only) 0.106 in

The above calculation is not valid if the heel soil bearing pressure exceeds that of the toe, because the wall would then tend to rotate into the retained soil.

## Cantilevered Retaining Wall

Project File: Foundation Retaining.ec6

LIC# : KW-06017913, Build:20.24.08.01

MULHERN & KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

**DESCRIPTION:** 9'-9" Basement Wall

---

### Rebar Lap & Embedment Lengths Information

#### Stem Design Segment: 2nd

Stem Design Height: 4.00 ft above top of footing

Lap Splice length for #5 bar specified in this stem design segment (25.4.2.4a) = 23.40 in  
Development length for #5 bar specified in this stem design segment = 18.00 in

---

#### Stem Design Segment: Bottom

Stem Design Height: 0.00 ft above top of footing

Lap Splice length for #5 bar specified in this stem design segment (25.4.2.4a) = 23.40 in  
Development length for #5 bar specified in this stem design segment = 18.00 in

Hooked embedment length into footing for #5 bar specified in this stem design segment = 6.00 in  
As Provided = 0.4650 in<sup>2</sup>/ft  
As Required = 0.4396 in<sup>2</sup>/ft

# Cantilevered Retaining Wall


Project File: Foundation Retaining.ec6

LIC# : KW-06017913, Build:20.24.08.01

MULHERN & KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

**DESCRIPTION:** 9'-9" Basement Wall



# Cantilevered Retaining Wall


Project File: Foundation Retaining.ec6


LIC# : KW-06017913, Build:20.24.08.01

MULHERN & KULP STRUCTURAL ENGINEERING INC

(c) ENERCALC INC 1983-2023

**DESCRIPTION:** 9'-9" Basement Wall





**MULHERN+KULP**  
RESIDENTIAL STRUCTURAL ENGINEERING

# SHEAR WALL CALCULATIONS WIND

DESIGN BUILT HOMES

86H AVE SE - LOT 2

*MERCER ISLAND*

*PARAMETERS:*

*SINGLE FAMILY HOME*

*DESIGN WIND SPEED: 100 MPH*

*WIND EXPOSURE CATEGORY: B*

*SEISMIC DESIGN CATEGORY: D1*

*CODE & DESIGN STANDARD: 2021 IBC CH. 1609, ASCE 7-16 CH. 26-30*

MULHERN & KULP STRUCTURAL ENGINEERING, INC.

NICHOLAS MARTIGNETTI, P.E., PROJECT MANAGER

RYAN CHAN, STAFF ENGINEER



**WIND DESIGN SUMMARY PER ASCE 7-16**

M+K PROJECT #: 244-24010  
ENGINEER: RSC

**PARAMETERS:**

WIND SPEED	100
EXPOSURE CATEGORY	B
RISK CATEGORY	II
WIND DIRECTIONALITY FACTOR, $K_d$	0.85
TOPOGRAPHIC FACTOR, $K_{zt}$	1.60
GUST FACTOR, $G$	0.85
GROUND ELEV. ABOVE SEA LEVEL (FT)	0
DESIGN TYPE	ASD 0.60

**ROOF GEOMETRY:**


TRANS. ROOF PITCH	0.0	:12
LONGS. ROOF PITCH	0.0	:12
MEAN ROOF HEIGHT, H	33.87	FT

**BUILDING GEOMETRY:**

LENGTH	80	FT
WIDTH	44	FT
NUMBER OF STORIES	3	


**TRANSVERSE DIRECTION (PERPENDICULAR TO MAIN RIDGE LINE)**


DIAPHRAGM LEVEL	FLOOR-TO-FLOOR HEIGHT	SURFACE	TRIBUTARY DESIGN AREA:			SQ FT	SECTION	TRIBUTARY DESIGN LOADS: (0.6W)			KIPS	
			A	O	B			A	O	B		
3	9.08 FT	ROOF SURFACE	0	0	0	SQ FT	SECTION	STORY SHEAR	0.00	8.01	0.00	KIPS
		WALL SURFACE	0	485	0			TOTAL SHEAR	0.00	8.01	0.00	
2	11.65 FT	ROOF SURFACE	0	0	0	SQ FT	SECTION	STORY SHEAR	0.00	12.71	0.00	KIPS
		WALL SURFACE	0	816	0			TOTAL SHEAR	0.00	20.73	0.00	
1	10.64 FT	ROOF SURFACE	0	0	0	SQ FT	SECTION	STORY SHEAR	0.00	0.00	0.00	KIPS
		WALL SURFACE	0	0	0			TOTAL SHEAR	0.00	20.73	0.00	
FND		ROOF SURFACE	0	0	0	SQ FT	SECTION	STORY SHEAR	0.00	0.00	0.00	KIPS
		WALL SURFACE	0	0	0			TOTAL SHEAR	0.00	20.73	0.00	



**LONGITUDINAL DIRECTION (PARALLEL TO MAIN RIDGE LINE)**

DIAPHRAGM LEVEL	FLOOR-TO-FLOOR HEIGHT	SURFACE	TRIBUTARY DESIGN AREA:			SQ FT	SECTION	TRIBUTARY DESIGN LOADS: (0.6W)			KIPS	
			A	O	B			A	O	B		
3	9.08 FT	ROOF SURFACE	0	0	0	SQ FT	SECTION	STORY SHEAR	0.00	4.29	0.00	KIPS
		WALL SURFACE	0	298	0			TOTAL SHEAR	0.00	4.29	0.00	
2	11.65 FT	ROOF SURFACE	0	0	0	SQ FT	SECTION	STORY SHEAR	0.00	6.14	0.00	KIPS
		WALL SURFACE	0	456	0			TOTAL SHEAR	0.00	10.44	0.00	
1	10.64 FT	ROOF SURFACE	0	0	0	SQ FT	SECTION	STORY SHEAR	0.00	2.75	0.00	KIPS
		WALL SURFACE	0	220	0			TOTAL SHEAR	0.00	13.19	0.00	
FND		ROOF SURFACE	0	0	0	SQ FT	SECTION	STORY SHEAR	0.00	0.00	0.00	KIPS
		WALL SURFACE	0	0	0			TOTAL SHEAR	0.00	13.19	0.00	





# BASEMENT FLOOR PLAN

SCALE 1/4" = 1'-0" 700 SF

### GENERAL NOTES:

1. PLATE HEIGHT @ UPPER FLOOR IS 9'-1", U.N.O.
2. PLATE HEIGHT @ MAIN FLOOR IS 10'-0", U.N.O.
3. PLATE HEIGHT @ LOWER FLOOR IS 9'-1" U.N.P.
4. DIMENSION LINES ARE TO FACE OF STUD U.N.O.
5. WINDOW SIZES & ROUGH OPENINGS TO BE VERIFIED BY CONTRACTOR.
6. WINDOW HEAD HEIGHT AT MAIN FLOOR IS 8'-0" ABOVE SUBFLOOR, U.N.O. IF NOMINAL DOOR AND WINDOW HEIGHTS ARE SIMILAR, COORDINATE WITH DOOR AND WINDOW SPEC'S TO LOCATE FINAL ELEVATION OF THE HEAD HEIGHTS SO THAT ALL DOOR AND WINDOW TRIM ALIGN.
7. WINDOW AND DOOR SIZES ARE DIMENSIONED IN FEET AND INCHES (E.G. 2828= 2'-8" W X 2'-8" H)
8. EXTERIOR WALLS TO BE 2X6 STUDS AT 16" O.C., INTERIOR WALLS TO BE 2X4 STUDS AT 16" O.C., U.N.O.
9. FIREBLOCK ALL PLUMBING PENETRATIONS AND STAIR RUNS PER IRC SEC. R302.11.
10. SAFETY GLAZING PER IRC SEC. R308.4.
11. ALL WOOD IN CONTACT WITH CONCRETE TO BE PRESSURE TREATED PER IRC SEC. R317.1.
12. PROVIDE UNDER-STAIR PROTECTION (1/2" GWB) PER IRC SEC. R302.7.
13. PROVIDE (1) LAYER OF 1/2" GWB AT THE GARAGE SIDE OF ALL WALLS SEPARATING THE GARAGE FROM THE RESIDENCE, ALL WALLS SUPPORTING A FLOOR CEILING ASSEMBLY BETWEEN THE GARAGE AND RESIDENCE, AND BETWEEN THE GARAGE AND ITS ATTIC. PROVIDE (1) LAYER 5/8" TYPE X GWB TO GARAGE CEILING IF BELOW HABITABLE ROOMS.
14. HOUSE/GARAGE DOOR SHALL BE 1-3/4" THICK WOOD SOLID CORE, OR 1-3/4" THICK SOLID OR HONEYCOMB CORE STEEL DOOR, OR 20-MINUTE RATED FIRE DOOR W/ SELF CLOSING DEVICE.
15. DUCTS IN THE GARAGE AND DUCTS PENETRATING THE WALLS AND CEILINGS SEPARATING THE DWELLING FROM THE GARAGE SHALL BE MIN. 26 GAUGE GALVANIZED STEEL.
16. PER IRC SEC R311.7.5. MAX. RISER HEIGHT SHALL BE 7-3/4". MIN. TREAD DEPTH SHALL BE 10". STAIR NOSINGS: 3/4" MIN., 1-1/4" MAX. RADIUS @ LEADING EDGE OF TREAD. 9/16" MAX.
17. PROVIDE HANDRAILS PER IRC SEC. R311.7.3. TOP OF HANDRAIL SHALL BE NOT LESS THAN 34" OR MORE THAN 38" ABOVE THE TREAD NOSINGS. HANDRAILS SHALL BE CONTINUOUS THE FULL LENGTH OF THE FLIGHT PER R311.7.2. THE HANDRAIL GRIP-SIZE SHALL BE PROVIDED PER R311.7.3.
18. PROVIDE GUARDS (MIN. 36" HEIGHT) IN LOCATIONS PER IRC SEC. R312.
19. FACTORY BUILT FIREPLACES & CHIMNEYS SHALL BE LISTED & LABELED AND SHALL BE INSTALLED & TERMINATED IN ACCORDANCE TO THE CONDITIONS OF THE LISTINGS. FACTORY BUILT FIREPLACES SHALL MEET EMISSION STANDARDS PER CH. 51-51 WAC.
20. PROVIDE EXTERIOR AIR SUPPLY TO ANY FACTORY-BUILT FIREPLACE PER IRC SEC R1006.


### STRUCTURAL NOTES:

1. PROVIDE 7/16" OSB OR 15/32" PLYWOOD SHEATHING & FASTEN PER STANDARD EXTERIOR WALL SHEATHING SPECIFICATIONS.
2. PROVIDE 3" SCHEDULE 40 PIPE COLUMN CONT. TO FOUNDATION BELOW WITH 4"X12"X1/2" BASE PLATE FASTENED TO FOUNDATION WALL WITH (4)1/2" TITEN HD ANCHORS WITH 7" MIN. EMBED.
3. STEEL BEAM OPT: PROVIDE 8"X7"X1/2" OFFSET CAP PLATE FASTENED TO BOTTOM FLANGE OF STEEL BEAM W/ (2) 3/4" A325 THRU BOLTS.
4. GLB BEAM OPT: PROVIDE 12"X5 1/2"X1/2" OFFSET CAP PLATE FASTENED TO BOTTOM OF BEAM W/ (4) 1/4"X2 1/2" LONG SDS SCREWS
5. PACKOUT STEEL BEAM AS REQUIRED W/ SOLID 2X MATERIAL THRU-BOLTED TO WEB WITH (2) 3/8" DIAMETER THRU-BOLTS @ 24" O.C. STAGGERED. FASTEN TOP PLATE TO STEEL BEAM PER SPEC ON S-0


**McCULLOUGH ARCHITECTS**  
 5601 6th Ave South  
 Suite 371  
 Seattle, WA, 98108  
 206.443.1181  
 mccullougharchitects.com  
 UNPUBLISHED WORK  
 2021 © McCullough Architects

Revisions	Comment
00.00.2024	X

Date: 09.27.2024  
 Job No: xx-xxx  
 Project No: 0000  
 Drawn: BAK  
 Approved: APM  
 Owner: Design Built Homes



**XXXX 86th Ave SE**  
 Mercer Island, Washington




- GENERAL NOTES:**
1. PLATE HEIGHT @ UPPER FLOOR IS 9'-1", U.N.O.
  2. PLATE HEIGHT @ MAIN FLOOR IS 10'-0", U.N.O.
  3. PLATE HEIGHT @ LOWER FLOOR IS 9'-1" U.N.P.
  4. DIMENSION LINES ARE TO FACE OF STUD U.N.O.
  5. WINDOW SIZES & ROUGH OPENINGS TO BE VERIFIED BY CONTRACTOR.
  6. WINDOW HEAD HEIGHT AT MAIN FLOOR IS 8'-0" ABOVE SUBFLOOR, U.N.O. IF NOMINAL DOOR AND WINDOW HEIGHTS ARE SIMILAR, COORDINATE WITH DOOR AND WINDOW SPEC'S TO LOCATE FINAL ELEVATION OF THE HEAD HEIGHTS SO THAT ALL DOOR AND WINDOW TRIM ALIGN.
  7. WINDOW AND DOOR SIZES ARE DIMENSIONED IN FEET AND INCHES (E.G. 2828= 2'-8" W X 2'-8" H)
  8. EXTERIOR WALLS TO BE 2X6 STUDS AT 16" O.C., INTERIOR WALLS TO BE 2X4 STUDS AT 16" O.C., U.N.O.
  9. FIREBLOCK ALL PLUMBING PENETRATIONS AND STAIR RUNS PER IRC SEC. R302.11.
  10. SAFETY GLAZING PER IRC SEC. R308.4.
  11. ALL WOOD IN CONTACT WITH CONCRETE TO BE PRESSURE TREATED PER IRC SEC. R317.1.
  12. PROVIDE UNDER-STAIR PROTECTION (1/2" GWB) PER IRC SEC. R302.7.
  13. PROVIDE (1) LAYER OF 1/2" GWB AT THE GARAGE SIDE OF ALL WALLS SEPARATING THE GARAGE FROM THE RESIDENCE, ALL WALLS SUPPORTING A FLOOR CEILING ASSEMBLY BETWEEN THE GARAGE AND RESIDENCE, AND BETWEEN THE GARAGE AND ITS ATTIC. PROVIDE (1) LAYER 5/8" TYPE X GWB TO GARAGE CEILING IF BELOW HABITABLE ROOMS.
  14. HOUSE/GARAGE DOOR SHALL BE 1-3/4" THICK WOOD SOLID CORE, OR 1-3/4" THICK SOLID OR HONEYCOMB CORE STEEL DOOR, OR 20-MINUTE RATED FIRE DOOR W/ SELF CLOSING DEVICE.
  15. DUCTS IN THE GARAGE AND DUCTS PENETRATING THE WALLS AND CEILING SEPARATING THE DWELLING FROM THE GARAGE SHALL BE MIN. 26 GAUGE GALVANIZED STEEL.
  16. PER IRC SEC R311.7.5. MAX. RISER HEIGHT SHALL BE 7-3/4". MIN. TREAD DEPTH SHALL BE 10". STAIR NOSINGS: 3/4" MIN., 1-1/4" MAX. RADIUS @ LEADING EDGE OF TREAD. 9/16" MAX.
  17. PROVIDE HANDRAILS PER IRC SEC. R311.7.3. TOP OF HANDRAIL SHALL BE NOT LESS THAN 34" OR MORE THAN 38" ABOVE THE TREAD NOSINGS. HANDRAILS SHALL BE CONTINUOUS THE FULL LENGTH PER R311.7.2. THE HANDRAIL GRIP-SIZE SHALL BE 1 1/2" DIA PER R311.7.3.
  18. PROVIDE GUARDS (MIN. 36" HEIGHT) IN LOCATIONS PER IRC SEC. R312.1.
  19. REFRIGERATORS & CHIMNEYS SHALL BE LISTED & LABELED AND SHALL BE INSTALLED & TERMINATED IN ACCORDANCE TO THE CONDITIONS OF THE LISTINGS. FACTORY BUILT FIREPLACES SHALL MEET EMISSION STANDARDS PER CH. 51-51 WAC.
  20. PROVIDE EXTERIOR AIR SUPPLY TO ANY FACTORY-BUILT FIREPLACE PER IRC SEC R1006.

- STRUCTURAL NOTES:**
1. PROVIDE 7/16" OSB OR 15/32" PLYWOOD SHEATHING & FASTEN PER STANDARD EXTERIOR WALL SHEATHING SPECIFICATIONS.
  2. PROVIDE 3" SCHEDULE 40 PIPE COLUMN CONT. TO FOUNDATION LOW WITH 4"X12"X1/2" BASE PLATE FASTENED TO FOUNDATION WALL WITH (4)1/2" TITEN HD ANCHORS WITH 7" MIN. EMBED.
  3. STEEL BEAM OPT: PROVIDE 8"X7"X1/2" OFFSET CAP PLATE FASTENED TO BOTTOM FLANGE OF STEEL BEAM W/ (2) 3/4" A325 THRU BOLTS.
  4. GLB BEAM OPT: PROVIDE 12"X5 1/2"X1/2" OFFSET CAP PLATE FASTENED TO BOTTOM OF BEAM W/ (4) 1/4"X2 1/2" LONG SDS SCREWS
  5. PACKOUT STEEL BEAM AS REQUIRED W/ SOLID 2X MATERIAL THRU-BOLTED TO WEB WITH (2) 3/8" DIAMETER THRU-BOLTS @ 24" O.C. STAGGERED. FASTEN TOP PLATE TO STEEL BEAM PER SPEC ON S-0

**McCULLOUGH ARCHITECTS**  
 5601 6th Ave South  
 Suite 371  
 Seattle, WA, 98108  
 206.443.1181  
 mccullougharchitects.com  
 UNPUBLISHED WORK  
 2021 © McCullough Architects


Revisions  
 Comment  
 00.00.2024 X  
 09.27.2024  
 Job No: xx-xxx  
 Project No: 0000  
 Drawn: BAK  
 Approved: APM  
 Owner: Design Built Homes



**XXXX 86th Ave SE**  
 Mercer Island, Washington

**MAIN FLOOR PLAN**

SCALE 1/4" = 1'-0" 2,183 SF TOTAL = 4,827 SF



**UPPER FLOOR PLAN**


SCALE 1/4" = 1'-0" 1,933 SF

- GENERAL NOTES:**
1. PLATE HEIGHT @ UPPER FLOOR IS 9'-1", U.N.O. PLATE HEIGHT @ MAIN FLOOR IS 10'-0", U.N.O. PLATE HEIGHT @ LOWER FLOOR IS 9'-1" U.N.P.
  2. DIMENSION LINES ARE TO FACE OF STUD U.N.O.
  3. WINDOW SIZES & ROUGH OPENINGS TO BE VERIFIED BY CONTRACTOR.
  4. WINDOW HEAD HEIGHT AT MAIN FLOOR IS 8'-0" ABOVE SUBFLOOR, U.N.O. IF NOMINAL DOOR AND WINDOW HEIGHTS ARE SIMILAR, COORDINATE WITH DOOR AND WINDOW SPECS TO LOCATE FINAL ELEVATION OF THE HEAD HEIGHTS SO THAT ALL DOOR AND WINDOW TRIM ALIGN.
  5. WINDOW AND DOOR SIZES ARE DIMENSIONED IN FEET AND INCHES (E.G. 2828= 2'-8" W X 2'-8" H)
  6. EXTERIOR WALLS TO BE 2X6 STUDS AT 16" O.C., INTERIOR WALLS TO BE 2X4 STUDS AT 16" O.C., U.N.O.
  7. FIREBLOCK ALL PLUMBING PENETRATIONS AND STAIR RUNS PER IRC SEC. R302.11.
  8. SAFETY GLAZING PER IRC SEC. R308.4.
  9. ALL WOOD IN CONTACT WITH CONCRETE TO BE PRESSURE TREATED PER IRC SEC. R317.1.
  10. PROVIDE UNDER-STAIR PROTECTION (1/2" GWB) PER IRC SEC. R302.7.
  11. PROVIDE (1) LAYER OF 1/2" GWB AT THE GARAGE SIDE OF ALL WALLS SEPARATING THE GARAGE FROM THE RESIDENCE. ALL WALLS SUPPORTING A FLOOR CEILING ASSEMBLY BETWEEN THE GARAGE AND RESIDENCE, AND BETWEEN THE GARAGE AND ITS ATTIC. PROVIDE (1) LAYER 5/8" TYPE X GWB TO GARAGE CEILING IF BELOW HABITABLE ROOMS.
  12. HOUSE/GARAGE DOOR SHALL BE 1-3/4" THICK WOOD SOLID CORE, OR 1-3/4" THICK SOLID OR HONEYCOMB CORE STEEL DOOR, OR 20-MINUTE RATED FIRE DOOR W/ SELF CLOSING DEVICE.
  13. DUCTS IN THE GARAGE AND DUCTS PENETRATING THE WALLS AND CEILINGS SEPARATING THE DWELLING FROM THE GARAGE SHALL BE MIN. 26 GAUGE GALVANIZED STEEL
  14. PER IRC SEC. R311.7.5, MAX. RISER HEIGHT SHALL BE 7-3/4", MIN. TREAD DEPTH SHALL BE 10", STAIR NOSINGS: 3/4" MIN., 1-1/4" MAX. RADIUS @ LEADING EDGE OF TREAD; 9/16" MAX. HANDRAIL SHALL BE NOT LESS THAN 34" OR MORE THAN 38" ABOVE THE TREAD NOSINGS. HANDRAILS SHALL BE CONTINUOUS THE FULL LENGTH OF THE FLIGHT PER R311.7.2. THE HANDRAIL GRIP-SIZE SHALL BE PROVIDED PER R311.7.3.
  15. PROVIDE HANDRAILS PER IRC SEC. R311.7.8. TOP OF HANDRAIL SHALL BE NOT LESS THAN 34" OR MORE THAN 38" ABOVE THE TREAD NOSINGS. HANDRAILS SHALL BE CONTINUOUS THE FULL LENGTH OF THE FLIGHT PER R311.7.2. THE HANDRAIL GRIP-SIZE SHALL BE PROVIDED PER R311.7.3.
  16. PROVIDE GUARDS (MIN. 36" HEIGHT) IN LOCATIONS PER IRC SEC. R312.
  17. FACTORY BUILT FIREPLACES & CHIMNEYS SHALL BE LISTED & LABELED AND SHALL BE INSTALLED & TERMINATED IN ACCORDANCE TO THE CONDITIONS OF THE LISTINGS. FACTORY BUILT FIREPLACES SHALL MEET EMISSION STANDARDS PER CH. 51-51 WAC.
  18. PROVIDE EXTERIOR AIR SUPPLY TO ANY FACTORY-BUILT FIREPLACE PER IRC SEC R1006.

**McCULLOUGH ARCHITECTS**  
 5601 6th Ave South  
 Suite 371  
 Seattle, WA, 98108  
 206.443.1181  
 mccullougharchitects.com  
 UNPUBLISHED WORK  
 2021 © McCullough Architects


Revisions	Comment
00.00.2024	X

Date: 09.27.2024  
 Job No: xx-xxx  
 Project No: 0000  
 Drawn: BAK  
 Approved: APW  
 Owner: Design Built Homes



**XXXX 86th Ave SE**  
 Mercer Island, Washington

Progress Set Upper Floor Plan  
**A8**





**SHEARWALL DESIGN SUMMARY**

M+K PROJECT #: 244-24010

ENGINEER: RSC

**SHEARWALL 301:** 3RD - FRONT B.F. WALL @ GREAT RM

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H	<input type="text" value="16.0"/> FT.	MAX WALL OPENING HT, H <sub>c</sub>	<input type="text" value="0.0"/> FT.	
WALL LENGTH, L	<input type="text" value="4.8"/> FT.	QUALIFYING WALL LENGTH, L	<input type="text" value="4.8"/> FT.	SHEARWALL ASSEMBLY <input type="text" value="P1"/>

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL	<input type="text" value="600"/> LBS	<	ALLOWABLE SHEARWALL CAPACITY	<input type="text" value="1322"/> LBS
--------------------------	--------------------------------------	---	------------------------------	---------------------------------------

**SHEARWALL ASSEMBLY SPECIFICATION**

P1 - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 6"O.C. PANEL EDGES & 12"O.C. PANEL FIELD - EDGES BLOCKED  
**ADEQUATE**

**OVERTURNING EVALUATION:**

RESISTIVE DL	<input type="text" value="213"/> PLF	OVERTURNING MOMENT	<input type="text" value="9.6"/> K-FT	HOLD DOWN DESIGN LOAD	<input type="text" value="1296"/> LBS
DL AT ENDS OF WALL	<input type="text" value="300"/> LBS	RESISTIVE MOMENT	<input type="text" value="3.4"/> K-FT	HOLDOWN CAPACITY	<input type="text" value="1705"/> LBS

**HOLD-DOWN SPECIFICATION**

**SIMPSON CS16 STRAP TIE (14" END LENGTH)**

**SHEARWALL 302:** 3RD - FRONT EXT. WALL @ W.I.C.

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H	<input type="text" value="9.1"/> FT.	MAX WALL OPENING HT, H <sub>c</sub>	<input type="text" value="0.0"/> FT.	
WALL LENGTH, L	<input type="text" value="4.0"/> FT.	QUALIFYING WALL LENGTH, L	<input type="text" value="4.0"/> FT.	SHEARWALL ASSEMBLY <input type="text" value="P1"/>

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL	<input type="text" value="300"/> LBS	<	ALLOWABLE SHEARWALL CAPACITY	<input type="text" value="1281"/> LBS
--------------------------	--------------------------------------	---	------------------------------	---------------------------------------

**SHEARWALL ASSEMBLY SPECIFICATION**

P1 - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 6"O.C. PANEL EDGES & 12"O.C. PANEL FIELD - EDGES BLOCKED  
**ADEQUATE**

**OVERTURNING EVALUATION:**

RESISTIVE DL	<input type="text" value="251"/> PLF	OVERTURNING MOMENT	<input type="text" value="2.7"/> K-FT	HOLD DOWN DESIGN LOAD	<input type="text" value="0"/> LBS
DL AT ENDS OF WALL	<input type="text" value="400"/> LBS	RESISTIVE MOMENT	<input type="text" value="3.2"/> K-FT	HOLDOWN CAPACITY	<input type="text" value="0"/> LBS

**HOLD-DOWN SPECIFICATION**

**NO HOLDOWN REQUIRED**



**SHEARWALL DESIGN SUMMARY**

M+K PROJECT #: 244-24010  
ENGINEER: RSC

**SHEARWALL 303:** 3RD - FRONT EXT. WALL @ BA 6

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H	<input type="text" value="9.1"/>	FT.	MAX WALL OPENING HT, H <sub>c</sub>	<input type="text" value="0.0"/>	FT.		
WALL LENGTH, L	<input type="text" value="8.3"/>	FT.	QUALIFYING WALL LENGTH, L	<input type="text" value="8.3"/>	FT.	SHEARWALL ASSEMBLY	<input type="text" value="P1"/>

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL	<input type="text" value="400"/>	LBS	<	ALLOWABLE SHEARWALL CAPACITY	<input type="text" value="2790"/>	LBS
--------------------------	----------------------------------	-----	---	------------------------------	-----------------------------------	-----

**SHEARWALL ASSEMBLY SPECIFICATION**

P1 - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 6"O.C. PANEL EDGES & 12"O.C. PANEL FIELD - EDGES BLOCKED  
**ADEQUATE**

**OVERTURNING EVALUATION:**

RESISTIVE DL	<input type="text" value="214"/>	PLF	OVERTURNING MOMENT	<input type="text" value="3.6"/>	K-FT	HOLD DOWN DESIGN LOAD	<input type="text" value="0"/>	LBS
DL AT ENDS OF WALL	<input type="text" value="400"/>	LBS	RESISTIVE MOMENT	<input type="text" value="9.6"/>	K-FT	HOLD DOWN CAPACITY	<input type="text" value="0"/>	LBS

**HOLD-DOWN SPECIFICATION**

**NO HOLDOWN REQUIRED**

**SHEARWALL 304:** 3RD - REAR EXT. WALL @ M BED - BED 4

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H	<input type="text" value="9.1"/>	FT.	MAX WALL OPENING HT, H <sub>c</sub>	<input type="text" value="5.0"/>	FT.		
WALL LENGTH, L	<input type="text" value="36.1"/>	FT.	QUALIFYING WALL LENGTH, L	<input type="text" value="25.1"/>	FT.	SHEARWALL ASSEMBLY	<input type="text" value="P1"/>

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL	<input type="text" value="1000"/>	LBS	<	ALLOWABLE SHEARWALL CAPACITY	<input type="text" value="8422"/>	LBS
--------------------------	-----------------------------------	-----	---	------------------------------	-----------------------------------	-----

**SHEARWALL ASSEMBLY SPECIFICATION**

P1 - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 6"O.C. PANEL EDGES & 12"O.C. PANEL FIELD - EDGES BLOCKED  
**ADEQUATE**

**OVERTURNING EVALUATION:**

RESISTIVE DL	<input type="text" value="194"/>	PLF	OVERTURNING MOMENT	<input type="text" value="9.1"/>	K-FT	HOLD DOWN DESIGN LOAD	<input type="text" value="0"/>	LBS
DL AT ENDS OF WALL	<input type="text" value="400"/>	LBS	RESISTIVE MOMENT	<input type="text" value="126.6"/>	K-FT	HOLD DOWN CAPACITY	<input type="text" value="0"/>	LBS

**HOLD-DOWN SPECIFICATION**

**NO HOLDOWN REQUIRED**



**SHEARWALL DESIGN SUMMARY**

M+K PROJECT #: 244-24010  
ENGINEER: RSC

**SHEARWALL 305: 3RD - FRONT INT. WALL @ M BED**

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H  FT.      MAX WALL OPENING HT, H<sub>c</sub>  FT.  
WALL LENGTH, L  FT.      QUALIFYING WALL LENGTH, L  FT.      SHEARWALL ASSEMBLY

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL  LBS < ALLOWABLE SHEARWALL CAPACITY  LBS

**SHEARWALL ASSEMBLY SPECIFICATION**

P1 - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 6" O.C. PANEL EDGES & 12" O.C. PANEL FIELD - EDGES BLOCKED  
**ADEQUATE**

**OVERTURNING EVALUATION:**

RESISTIVE DL  PLF      OVERTURNING MOMENT  K-FT      HOLD DOWN DESIGN LOAD  LBS  
DL AT ENDS OF WALL  LBS      RESISTIVE MOMENT  K-FT      HOLDDOWN CAPACITY  LBS

**HOLD-DOWN SPECIFICATION**

**NO HOLDOWN REQUIRED**

**SHEARWALL : BASEMENT - NOT USED**

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H  FT.      MAX WALL OPENING HT, H<sub>c</sub>  FT.  
WALL LENGTH, L  FT.      QUALIFYING WALL LENGTH, L  FT.      SHEARWALL ASSEMBLY

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL  LBS      ALLOWABLE SHEARWALL CAPACITY  LBS  
 LBS      **###**       LBS

**SHEARWALL ASSEMBLY SPECIFICATION**


P0 - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 6" O.C. PANEL EDGES & 12" O.C. PANEL FIELD - UNBLOCKED  
**#DIV/0!**

**OVERTURNING EVALUATION:**

RESISTIVE DL  PLF      OVERTURNING MOMENT  K-FT      HOLD DOWN DESIGN LOAD  LBS  
DL AT ENDS OF WALL  LBS      RESISTIVE MOMENT  K-FT      HOLDDOWN CAPACITY  LBS

**HOLD-DOWN SPECIFICATION**

**NO HOLDOWN REQUIRED**



**SHEARWALL DESIGN SUMMARY**

M+K PROJECT #: 244-24010  
ENGINEER: RSC

**SHEARWALL 307: 3RD - SIDE EXT. WALL @ M BED**

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H	<input type="text" value="9.1"/>	FT.	MAX WALL OPENING HT, H <sub>c</sub>	<input type="text" value="0.0"/>	FT.		
WALL LENGTH, L	<input type="text" value="11.1"/>	FT.	QUALIFYING WALL LENGTH, L	<input type="text" value="11.1"/>	FT.	SHEARWALL ASSEMBLY	<input type="text" value="P1"/>

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL	<input type="text" value="800"/>	LBS	<	ALLOWABLE SHEARWALL CAPACITY	<input type="text" value="3724"/>	LBS
--------------------------	----------------------------------	-----	---	------------------------------	-----------------------------------	-----

**SHEARWALL ASSEMBLY SPECIFICATION**

P1 - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 6"O.C. PANEL EDGES & 12"O.C. PANEL FIELD - EDGES BLOCKED  
**ADEQUATE**

**OVERTURNING EVALUATION:**

RESISTIVE DL	<input type="text" value="113"/>	PLF	OVERTURNING MOMENT	<input type="text" value="7.3"/>	K-FT	HOLD DOWN DESIGN LOAD	<input type="text" value="0"/>	LBS
DL AT ENDS OF WALL	<input type="text" value="300"/>	LBS	RESISTIVE MOMENT	<input type="text" value="9.2"/>	K-FT	HOLD DOWN CAPACITY	<input type="text" value="0"/>	LBS

**HOLD-DOWN SPECIFICATION**

**NO HOLD DOWN REQUIRED**

**SHEARWALL 308: 3RD - SIDE EXT. B.F. WALL @ GREAT RM**

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H	<input type="text" value="16.0"/>	FT.	MAX WALL OPENING HT, H <sub>c</sub>	<input type="text" value="0.0"/>	FT.		
WALL LENGTH, L	<input type="text" value="8.0"/>	FT.	QUALIFYING WALL LENGTH, L	<input type="text" value="8.0"/>	FT.	SHEARWALL ASSEMBLY	<input type="text" value="P1"/>

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL	<input type="text" value="1100"/>	LBS	<	ALLOWABLE SHEARWALL CAPACITY	<input type="text" value="2686"/>	LBS
--------------------------	-----------------------------------	-----	---	------------------------------	-----------------------------------	-----

**SHEARWALL ASSEMBLY SPECIFICATION**

P1 - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 6"O.C. PANEL EDGES & 12"O.C. PANEL FIELD - EDGES BLOCKED  
**ADEQUATE**

**OVERTURNING EVALUATION:**

RESISTIVE DL	<input type="text" value="279"/>	PLF	OVERTURNING MOMENT	<input type="text" value="17.6"/>	K-FT	HOLD DOWN DESIGN LOAD	<input type="text" value="791"/>	LBS
DL AT ENDS OF WALL	<input type="text" value="450"/>	LBS	RESISTIVE MOMENT	<input type="text" value="11.3"/>	K-FT	HOLD DOWN CAPACITY	<input type="text" value="1705"/>	LBS

**HOLD-DOWN SPECIFICATION**

**SIMPSON CS16 STRAP TIE (14" END LENGTH)**



**SHEARWALL DESIGN SUMMARY**

M+K PROJECT #: 244-24010  
ENGINEER: RSC

**SHEARWALL 309: 3RD - SIDE EXT. WALL @ W.I.C.**

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H	<input type="text" value="9.1"/>	FT.	MAX WALL OPENING HT, H <sub>c</sub>	<input type="text" value="0.0"/>	FT.		
WALL LENGTH, L	<input type="text" value="8.1"/>	FT.	QUALIFYING WALL LENGTH, L	<input type="text" value="8.1"/>	FT.	SHEARWALL ASSEMBLY	<input type="text" value="P1"/>

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL	<input type="text" value="600"/>	LBS	<	ALLOWABLE SHEARWALL CAPACITY	<input type="text" value="2713"/>	LBS
--------------------------	----------------------------------	-----	---	------------------------------	-----------------------------------	-----

**SHEARWALL ASSEMBLY SPECIFICATION**

**P1 - 1-SIDE 7/16" OSB**  
FASTENED W/ 8D NAILS AT 6"O.C. PANEL EDGES & 12"O.C. PANEL FIELD - EDGES BLOCKED  
**ADEQUATE**

**OVERTURNING EVALUATION:**

RESISTIVE DL	<input type="text" value="113"/>	PLF	OVERTURNING MOMENT	<input type="text" value="5.4"/>	K-FT	HOLD DOWN DESIGN LOAD	<input type="text" value="0"/>	LBS
DL AT ENDS OF WALL	<input type="text" value="450"/>	LBS	RESISTIVE MOMENT	<input type="text" value="6.6"/>	K-FT	HOLDDOWN CAPACITY	<input type="text" value="0"/>	LBS

**HOLD-DOWN SPECIFICATION**

**NO HOLDOWN REQUIRED**

**SHEARWALL 310: 3RD - SIDE EXT. WALL @ W.I.C.**

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H	<input type="text" value="9.1"/>	FT.	MAX WALL OPENING HT, H <sub>c</sub>	<input type="text" value="0.0"/>	FT.		
WALL LENGTH, L	<input type="text" value="7.2"/>	FT.	QUALIFYING WALL LENGTH, L	<input type="text" value="7.2"/>	FT.	SHEARWALL ASSEMBLY	<input type="text" value="P1"/>

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL	<input type="text" value="500"/>	LBS	<	ALLOWABLE SHEARWALL CAPACITY	<input type="text" value="2404"/>	LBS
--------------------------	----------------------------------	-----	---	------------------------------	-----------------------------------	-----

**SHEARWALL ASSEMBLY SPECIFICATION**

**P1 - 1-SIDE 7/16" OSB**  
FASTENED W/ 8D NAILS AT 6"O.C. PANEL EDGES & 12"O.C. PANEL FIELD - EDGES BLOCKED  
**ADEQUATE**

**OVERTURNING EVALUATION:**

RESISTIVE DL	<input type="text" value="113"/>	PLF	OVERTURNING MOMENT	<input type="text" value="4.5"/>	K-FT	HOLD DOWN DESIGN LOAD	<input type="text" value="0"/>	LBS
DL AT ENDS OF WALL	<input type="text" value="450"/>	LBS	RESISTIVE MOMENT	<input type="text" value="5.5"/>	K-FT	HOLDDOWN CAPACITY	<input type="text" value="0"/>	LBS

**HOLD-DOWN SPECIFICATION**

**NO HOLDOWN REQUIRED**



**SHEARWALL DESIGN SUMMARY**

M+K PROJECT #: 244-24010  
ENGINEER: RSC

**SHEARWALL 311: 3RD - SIDE EXT. WALL @ W.I.C. - BA 6**

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H	<input type="text" value="9.1"/>	FT.	MAX WALL OPENING HT, H <sub>c</sub>	<input type="text" value="2.0"/>	FT.		
WALL LENGTH, L	<input type="text" value="14.9"/>	FT.	QUALIFYING WALL LENGTH, L	<input type="text" value="14.9"/>	FT.	SHEARWALL ASSEMBLY	<input type="text" value="P1"/>

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL	<input type="text" value="1900"/>	LBS	<	ALLOWABLE SHEARWALL CAPACITY	<input type="text" value="5010"/>	LBS
--------------------------	-----------------------------------	-----	---	------------------------------	-----------------------------------	-----

**SHEARWALL ASSEMBLY SPECIFICATION**

**P1 - 1-SIDE 7/16" OSB**  
FASTENED W/ 8D NAILS AT 6"O.C. PANEL EDGES & 12"O.C. PANEL FIELD - EDGES BLOCKED  
**ADEQUATE**

**OVERTURNING EVALUATION:**

RESISTIVE DL	<input type="text" value="113"/>	PLF	OVERTURNING MOMENT	<input type="text" value="17.3"/>	K-FT	HOLD DOWN DESIGN LOAD	<input type="text" value="0"/>	LBS
DL AT ENDS OF WALL	<input type="text" value="450"/>	LBS	RESISTIVE MOMENT	<input type="text" value="17.4"/>	K-FT	HOLDDOWN CAPACITY	<input type="text" value="0"/>	LBS

**HOLD-DOWN SPECIFICATION**

**NO HOLDOWN REQUIRED**

**SHEARWALL 312: 3RD - SIDE INT. WALL @ LAUN.**

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H	<input type="text" value="9.1"/>	FT.	MAX WALL OPENING HT, H <sub>c</sub>	<input type="text" value="0.0"/>	FT.		
WALL LENGTH, L	<input type="text" value="14.6"/>	FT.	QUALIFYING WALL LENGTH, L	<input type="text" value="14.6"/>	FT.	SHEARWALL ASSEMBLY	<input type="text" value="P1"/>

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL	<input type="text" value="1400"/>	LBS	<	ALLOWABLE SHEARWALL CAPACITY	<input type="text" value="4903"/>	LBS
--------------------------	-----------------------------------	-----	---	------------------------------	-----------------------------------	-----

**SHEARWALL ASSEMBLY SPECIFICATION**

**P1 - 1-SIDE 7/16" OSB**  
FASTENED W/ 8D NAILS AT 6"O.C. PANEL EDGES & 12"O.C. PANEL FIELD - EDGES BLOCKED  
**ADEQUATE**

**OVERTURNING EVALUATION:**

RESISTIVE DL	<input type="text" value="113"/>	PLF	OVERTURNING MOMENT	<input type="text" value="12.7"/>	K-FT	HOLD DOWN DESIGN LOAD	<input type="text" value="0"/>	LBS
DL AT ENDS OF WALL	<input type="text" value="400"/>	LBS	RESISTIVE MOMENT	<input type="text" value="16.1"/>	K-FT	HOLDDOWN CAPACITY	<input type="text" value="0"/>	LBS

**HOLD-DOWN SPECIFICATION**

**NO HOLDOWN REQUIRED**



**SHEARWALL DESIGN SUMMARY**

M+K PROJECT #: 244-24010  
ENGINEER: RSC

**SHEARWALL 313: 3RD - SIDE INT. WALL @ BED 3**

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H	<input type="text" value="9.1"/>	FT.	MAX WALL OPENING HT, H <sub>c</sub>	<input type="text" value="0.0"/>	FT.		
WALL LENGTH, L	<input type="text" value="18.8"/>	FT.	QUALIFYING WALL LENGTH, L	<input type="text" value="18.8"/>	FT.	SHEARWALL ASSEMBLY	<input type="text" value="P1"/>

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL	<input type="text" value="1700"/>	LBS	<	ALLOWABLE SHEARWALL CAPACITY	<input type="text" value="6296"/>	LBS
--------------------------	-----------------------------------	-----	---	------------------------------	-----------------------------------	-----

**SHEARWALL ASSEMBLY SPECIFICATION**

P1 - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 6" O.C. PANEL EDGES & 12" O.C. PANEL FIELD - EDGES BLOCKED  
**ADEQUATE**

**OVERTURNING EVALUATION:**

RESISTIVE DL	<input type="text" value="100"/>	PLF	OVERTURNING MOMENT	<input type="text" value="15.4"/>	K-FT	HOLD DOWN DESIGN LOAD	<input type="text" value="0"/>	LBS
DL AT ENDS OF WALL	<input type="text" value="200"/>	LBS	RESISTIVE MOMENT	<input type="text" value="19.2"/>	K-FT	HOLD DOWN CAPACITY	<input type="text" value="0"/>	LBS

**HOLD-DOWN SPECIFICATION**

**NO HOLDOWN REQUIRED**

**SHEARWALL : BASEMENT - NOT USED**

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H	<input type="text" value="0.0"/>	FT.	MAX WALL OPENING HT, H <sub>c</sub>	<input type="text" value="0.0"/>	FT.		
WALL LENGTH, L	<input type="text" value="0.0"/>	FT.	QUALIFYING WALL LENGTH, L	<input type="text" value="0.0"/>	FT.	SHEARWALL ASSEMBLY	<input type="text" value="P0"/>

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL	<input type="text" value="0"/>	LBS	###	ALLOWABLE SHEARWALL CAPACITY	<input type="text" value="#DIV/0!"/>	LBS
--------------------------	--------------------------------	-----	-----	------------------------------	--------------------------------------	-----

**SHEARWALL ASSEMBLY SPECIFICATION**

P0 - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 6" O.C. PANEL EDGES & 12" O.C. PANEL FIELD - UNBLOCKED  
**#DIV/0!**

**OVERTURNING EVALUATION:**

RESISTIVE DL	<input type="text" value="0"/>	PLF	OVERTURNING MOMENT	<input type="text" value="#DIV/0!"/>	K-FT	HOLD DOWN DESIGN LOAD	<input type="text" value="0"/>	LBS
DL AT ENDS OF WALL	<input type="text" value="0"/>	LBS	RESISTIVE MOMENT	<input type="text" value="0.0"/>	K-FT	HOLD DOWN CAPACITY	<input type="text" value="0"/>	LBS

**HOLD-DOWN SPECIFICATION**

**NO HOLDOWN REQUIRED**



**SHEARWALL DESIGN SUMMARY**

M+K PROJECT #: 244-24010  
ENGINEER: RSC

**SHEARWALL 201: 2ND - REAR EXT. WALL @ KITCHEN**

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H	<input type="text" value="10.0"/>	FT.	MAX WALL OPENING HT, H <sub>c</sub>	<input type="text" value="0.0"/>	FT.		
WALL LENGTH, L	<input type="text" value="17.2"/>	FT.	QUALIFYING WALL LENGTH, L	<input type="text" value="17.2"/>	FT.	SHEARWALL ASSEMBLY	<input type="text" value="P3"/>

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL	<input type="text" value="2500"/>	LBS	<	ALLOWABLE SHEARWALL CAPACITY	<input type="text" value="10808"/>	LBS
--------------------------	-----------------------------------	-----	---	------------------------------	------------------------------------	-----

**SHEARWALL ASSEMBLY SPECIFICATION**

P3 - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 3"O.C. PANEL EDGES & 12"O.C. PANEL FIELD - EDGES BLOCKED  
**ADEQUATE**

**OVERTURNING EVALUATION:**

RESISTIVE DL	<input type="text" value="444"/>	PLF	OVERTURNING MOMENT	<input type="text" value="25.0"/>	K-FT	HOLD DOWN DESIGN LOAD	<input type="text" value="0"/>	LBS
DL AT ENDS OF WALL	<input type="text" value="800"/>	LBS	RESISTIVE MOMENT	<input type="text" value="71.1"/>	K-FT	HOLDDOWN CAPACITY	<input type="text" value="0"/>	LBS

**HOLD-DOWN SPECIFICATION**

**NO HOLDOWN REQUIRED**

**SHEARWALL 202: 2ND - REAR EXT. WALL @ GUEST SUITE**

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H	<input type="text" value="10.0"/>	FT.	MAX WALL OPENING HT, H <sub>c</sub>	<input type="text" value="0.0"/>	FT.		
WALL LENGTH, L	<input type="text" value="7.0"/>	FT.	QUALIFYING WALL LENGTH, L	<input type="text" value="7.0"/>	FT.	SHEARWALL ASSEMBLY	<input type="text" value="P1"/>

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL	<input type="text" value="500"/>	LBS	<	ALLOWABLE SHEARWALL CAPACITY	<input type="text" value="2337"/>	LBS
--------------------------	----------------------------------	-----	---	------------------------------	-----------------------------------	-----

**SHEARWALL ASSEMBLY SPECIFICATION**

P1 - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 6"O.C. PANEL EDGES & 12"O.C. PANEL FIELD - EDGES BLOCKED  
**ADEQUATE**

**OVERTURNING EVALUATION:**

RESISTIVE DL	<input type="text" value="208"/>	PLF	OVERTURNING MOMENT	<input type="text" value="5.0"/>	K-FT	HOLD DOWN DESIGN LOAD	<input type="text" value="0"/>	LBS
DL AT ENDS OF WALL	<input type="text" value="200"/>	LBS	RESISTIVE MOMENT	<input type="text" value="5.8"/>	K-FT	HOLDDOWN CAPACITY	<input type="text" value="0"/>	LBS

**HOLD-DOWN SPECIFICATION**

**NO HOLDOWN REQUIRED**



**SHEARWALL DESIGN SUMMARY**

M+K PROJECT #: 244-24010  
ENGINEER: RSC

**SHEARWALL 203: 2ND - REAR EXT. WALL @ GUEST BA**

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H	<input type="text" value="10.0"/> FT.	MAX WALL OPENING HT, H <sub>c</sub>	<input type="text" value="0.0"/> FT.	
WALL LENGTH, L	<input type="text" value="6.8"/> FT.	QUALIFYING WALL LENGTH, L	<input type="text" value="6.8"/> FT.	SHEARWALL ASSEMBLY <input type="text" value="P1"/>

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL	<input type="text" value="500"/> LBS	<	ALLOWABLE SHEARWALL CAPACITY	<input type="text" value="2294"/> LBS
--------------------------	--------------------------------------	---	------------------------------	---------------------------------------

**SHEARWALL ASSEMBLY SPECIFICATION**

P1 - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 6"O.C. PANEL EDGES & 12"O.C. PANEL FIELD - EDGES BLOCKED  
**ADEQUATE**

**OVERTURNING EVALUATION:**

RESISTIVE DL	<input type="text" value="208"/> PLF	OVERTURNING MOMENT	<input type="text" value="5.0"/> K-FT	HOLD DOWN DESIGN LOAD	<input type="text" value="0"/> LBS
DL AT ENDS OF WALL	<input type="text" value="200"/> LBS	RESISTIVE MOMENT	<input type="text" value="5.6"/> K-FT	HOLD DOWN CAPACITY	<input type="text" value="0"/> LBS

**HOLD-DOWN SPECIFICATION**

**NO HOLDOWN REQUIRED**

**SHEARWALL 204: 2ND - REAR INT. WALL @ HALL**

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H	<input type="text" value="10.0"/> FT.	MAX WALL OPENING HT, H <sub>c</sub>	<input type="text" value="0.0"/> FT.	
WALL LENGTH, L	<input type="text" value="12.0"/> FT.	QUALIFYING WALL LENGTH, L	<input type="text" value="12.0"/> FT.	SHEARWALL ASSEMBLY <input type="text" value="P3"/>

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL	<input type="text" value="2700"/> LBS	<	ALLOWABLE SHEARWALL CAPACITY	<input type="text" value="7562"/> LBS
--------------------------	---------------------------------------	---	------------------------------	---------------------------------------

**SHEARWALL ASSEMBLY SPECIFICATION**

P3 - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 3"O.C. PANEL EDGES & 12"O.C. PANEL FIELD - EDGES BLOCKED  
**ADEQUATE**

**OVERTURNING EVALUATION:**

RESISTIVE DL	<input type="text" value="289"/> PLF	OVERTURNING MOMENT	<input type="text" value="27.0"/> K-FT	HOLD DOWN DESIGN LOAD	<input type="text" value="0"/> LBS
DL AT ENDS OF WALL	<input type="text" value="800"/> LBS	RESISTIVE MOMENT	<input type="text" value="27.4"/> K-FT	HOLD DOWN CAPACITY	<input type="text" value="0"/> LBS

**HOLD-DOWN SPECIFICATION**

**NO HOLDOWN REQUIRED**



**SHEARWALL DESIGN SUMMARY**

M+K PROJECT #: 244-24010  
ENGINEER: RSC

**SHEARWALL 205: 2ND - REAR INT. WALL @ GARAGE**

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H	<input type="text" value="10.0"/>	FT.	MAX WALL OPENING HT, H <sub>c</sub>	<input type="text" value="0.0"/>	FT.		
WALL LENGTH, L	<input type="text" value="29.0"/>	FT.	QUALIFYING WALL LENGTH, L	<input type="text" value="29.0"/>	FT.	SHEARWALL ASSEMBLY	<input type="text" value="P1"/>

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL	<input type="text" value="1800"/>	LBS	<	ALLOWABLE SHEARWALL CAPACITY	<input type="text" value="9738"/>	LBS
--------------------------	-----------------------------------	-----	---	------------------------------	-----------------------------------	-----

**SHEARWALL ASSEMBLY SPECIFICATION**

P1 - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 6"O.C. PANEL EDGES & 12"O.C. PANEL FIELD - EDGES BLOCKED  
**ADEQUATE**

**OVERTURNING EVALUATION:**

RESISTIVE DL	<input type="text" value="338"/>	PLF	OVERTURNING MOMENT	<input type="text" value="18.0"/>	K-FT	HOLD DOWN DESIGN LOAD	<input type="text" value="0"/>	LBS
DL AT ENDS OF WALL	<input type="text" value="400"/>	LBS	RESISTIVE MOMENT	<input type="text" value="138.4"/>	K-FT	HOLDDOWN CAPACITY	<input type="text" value="0"/>	LBS

**HOLD-DOWN SPECIFICATION**

**NO HOLDOWN REQUIRED**

**SHEARWALL 206: 2ND - SIDE EXT. WALL @ OUTDOOR LIVING**

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H	<input type="text" value="10.0"/>	FT.	MAX WALL OPENING HT, H <sub>c</sub>	<input type="text" value="0.0"/>	FT.		
WALL LENGTH, L	<input type="text" value="6.0"/>	FT.	QUALIFYING WALL LENGTH, L	<input type="text" value="6.0"/>	FT.	SHEARWALL ASSEMBLY	<input type="text" value="P3"/>

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL	<input type="text" value="2400"/>	LBS	<	ALLOWABLE SHEARWALL CAPACITY	<input type="text" value="3781"/>	LBS
--------------------------	-----------------------------------	-----	---	------------------------------	-----------------------------------	-----

**SHEARWALL ASSEMBLY SPECIFICATION**

P3 - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 3"O.C. PANEL EDGES & 12"O.C. PANEL FIELD - EDGES BLOCKED  
**ADEQUATE**

**OVERTURNING EVALUATION:**

RESISTIVE DL	<input type="text" value="243"/>	PLF	OVERTURNING MOMENT	<input type="text" value="24.0"/>	K-FT	HOLD DOWN DESIGN LOAD	<input type="text" value="2984"/>	LBS
DL AT ENDS OF WALL	<input type="text" value="400"/>	LBS	RESISTIVE MOMENT	<input type="text" value="6.1"/>	K-FT	HOLDDOWN CAPACITY	<input type="text" value="5505"/>	LBS

**HOLD-DOWN SPECIFICATION**

**SIMPSON MSTC66 STRAP TIE (24" END LENGTH)**



**SHEARWALL DESIGN SUMMARY**

M+K PROJECT #: 244-24010  
ENGINEER: RSC

**SHEARWALL 207: 2ND - SIDE EXT. WALL @ OUTDOOR LIVING**

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H	<input type="text" value="10.0"/> FT.	MAX WALL OPENING HT, H <sub>c</sub>	<input type="text" value="8.0"/> FT.	
WALL LENGTH, L	<input type="text" value="19.5"/> FT.	QUALIFYING WALL LENGTH, L	<input type="text" value="7.5"/> FT.	SHEARWALL ASSEMBLY <input type="text" value="P3"/>

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL	<input type="text" value="3100"/> LBS	<	ALLOWABLE SHEARWALL CAPACITY	<input type="text" value="4654"/> LBS
--------------------------	---------------------------------------	---	------------------------------	---------------------------------------

**SHEARWALL ASSEMBLY SPECIFICATION**

P3 - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 3"O.C. PANEL EDGES & 12"O.C. PANEL FIELD - EDGES BLOCKED  
**ADEQUATE**

**OVERTURNING EVALUATION:**

RESISTIVE DL	<input type="text" value="130"/> PLF	OVERTURNING MOMENT	<input type="text" value="31.0"/> K-FT	HOLD DOWN DESIGN LOAD	<input type="text" value="0"/> LBS
DL AT ENDS OF WALL	<input type="text" value="1200"/> LBS	RESISTIVE MOMENT	<input type="text" value="43.3"/> K-FT	HOLD DOWN CAPACITY	<input type="text" value="0"/> LBS

**HOLD-DOWN SPECIFICATION**

**NO HOLDOWN REQUIRED**

**SHEARWALL 208: 2ND - SIDE EXT. WALL @ GARAGE**

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H	<input type="text" value="10.0"/> FT.	MAX WALL OPENING HT, H <sub>c</sub>	<input type="text" value="0.0"/> FT.	
WALL LENGTH, L	<input type="text" value="23.0"/> FT.	QUALIFYING WALL LENGTH, L	<input type="text" value="23.0"/> FT.	SHEARWALL ASSEMBLY <input type="text" value="P1"/>

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL	<input type="text" value="5200"/> LBS	<	ALLOWABLE SHEARWALL CAPACITY	<input type="text" value="7723"/> LBS
--------------------------	---------------------------------------	---	------------------------------	---------------------------------------

**SHEARWALL ASSEMBLY SPECIFICATION**

P1 - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 6"O.C. PANEL EDGES & 12"O.C. PANEL FIELD - EDGES BLOCKED  
**ADEQUATE**

**OVERTURNING EVALUATION:**

RESISTIVE DL	<input type="text" value="151"/> PLF	OVERTURNING MOMENT	<input type="text" value="52.0"/> K-FT	HOLD DOWN DESIGN LOAD	<input type="text" value="0"/> LBS
DL AT ENDS OF WALL	<input type="text" value="800"/> LBS	RESISTIVE MOMENT	<input type="text" value="52.5"/> K-FT	HOLD DOWN CAPACITY	<input type="text" value="0"/> LBS

**HOLD-DOWN SPECIFICATION**

**NO HOLDOWN REQUIRED**



**SHEARWALL DESIGN SUMMARY**

M+K PROJECT #: 244-24010  
ENGINEER: RSC

**SHEARWALL 209: 2ND - SIDE EXT. WALL @ GUEST BA - W.I.C.**

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H	<input type="text" value="10.0"/>	FT.	MAX WALL OPENING HT, H <sub>c</sub>	<input type="text" value="0.0"/>	FT.		
WALL LENGTH, L	<input type="text" value="14.0"/>	FT.	QUALIFYING WALL LENGTH, L	<input type="text" value="14.0"/>	FT.	SHEARWALL ASSEMBLY	<input type="text" value="P1"/>

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL	<input type="text" value="2500"/>	LBS	<	ALLOWABLE SHEARWALL CAPACITY	<input type="text" value="4701"/>	LBS
--------------------------	-----------------------------------	-----	---	------------------------------	-----------------------------------	-----

**SHEARWALL ASSEMBLY SPECIFICATION**

P1 - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 6"O.C. PANEL EDGES & 12"O.C. PANEL FIELD - EDGES BLOCKED  
**ADEQUATE**

**OVERTURNING EVALUATION:**

RESISTIVE DL	<input type="text" value="113"/>	PLF	OVERTURNING MOMENT	<input type="text" value="25.0"/>	K-FT	HOLD DOWN DESIGN LOAD	<input type="text" value="0"/>	LBS
DL AT ENDS OF WALL	<input type="text" value="1200"/>	LBS	RESISTIVE MOMENT	<input type="text" value="25.1"/>	K-FT	HOLDDOWN CAPACITY	<input type="text" value="0"/>	LBS

**HOLD-DOWN SPECIFICATION**

**NO HOLDOWN REQUIRED**

**SHEARWALL 210: 2ND - SIDE INT. WALL @ OFFICE**

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H	<input type="text" value="10.0"/>	FT.	MAX WALL OPENING HT, H <sub>c</sub>	<input type="text" value="0.0"/>	FT.		
WALL LENGTH, L	<input type="text" value="16.9"/>	FT.	QUALIFYING WALL LENGTH, L	<input type="text" value="16.9"/>	FT.	SHEARWALL ASSEMBLY	<input type="text" value="P1"/>

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL	<input type="text" value="2600"/>	LBS	<	ALLOWABLE SHEARWALL CAPACITY	<input type="text" value="5668"/>	LBS
--------------------------	-----------------------------------	-----	---	------------------------------	-----------------------------------	-----

**SHEARWALL ASSEMBLY SPECIFICATION**

P1 - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 6"O.C. PANEL EDGES & 12"O.C. PANEL FIELD - EDGES BLOCKED  
**ADEQUATE**

**OVERTURNING EVALUATION:**

RESISTIVE DL	<input type="text" value="230"/>	PLF	OVERTURNING MOMENT	<input type="text" value="39.9"/>	K-FT	HOLD DOWN DESIGN LOAD	<input type="text" value="0"/>	LBS
DL AT ENDS OF WALL	<input type="text" value="800"/>	LBS	RESISTIVE MOMENT	<input type="text" value="41.6"/>	K-FT	HOLDDOWN CAPACITY	<input type="text" value="0"/>	LBS

**HOLD-DOWN SPECIFICATION**

**NO HOLDOWN REQUIRED**



**SHEARWALL DESIGN SUMMARY**

M+K PROJECT #: 244-24010  
ENGINEER: RSC

**SHEARWALL 211: 2ND - SIDE INT. WALL @ GARAGE**

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H	<input type="text" value="10.0"/> FT.	MAX WALL OPENING HT, H <sub>c</sub>	<input type="text" value="8.0"/> FT.		
WALL LENGTH, L	<input type="text" value="22.1"/> FT.	QUALIFYING WALL LENGTH, L	<input type="text" value="19.4"/> FT.	SHEARWALL ASSEMBLY	<input type="text" value="P1"/>

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL	<input type="text" value="3800"/> LBS	<	ALLOWABLE SHEARWALL CAPACITY	<input type="text" value="6525"/> LBS
--------------------------	---------------------------------------	---	------------------------------	---------------------------------------

**SHEARWALL ASSEMBLY SPECIFICATION**

P1 - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 6" O.C. PANEL EDGES & 12" O.C. PANEL FIELD - EDGES BLOCKED  
**ADEQUATE**

**OVERTURNING EVALUATION:**

RESISTIVE DL	<input type="text" value="100"/> PLF	OVERTURNING MOMENT	<input type="text" value="38.0"/> K-FT	HOLD DOWN DESIGN LOAD	<input type="text" value="0"/> LBS
DL AT ENDS OF WALL	<input type="text" value="810"/> LBS	RESISTIVE MOMENT	<input type="text" value="38.1"/> K-FT	HOLD DOWN CAPACITY	<input type="text" value="0"/> LBS

**HOLD-DOWN SPECIFICATION**

**NO HOLDOWN REQUIRED**

**SHEARWALL : BASEMENT - NOT USED**

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H	<input type="text" value="0.0"/> FT.	MAX WALL OPENING HT, H <sub>c</sub>	<input type="text" value="0.0"/> FT.		
WALL LENGTH, L	<input type="text" value="0.0"/> FT.	QUALIFYING WALL LENGTH, L	<input type="text" value="0.0"/> FT.	SHEARWALL ASSEMBLY	<input type="text" value="P0"/>

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL	<input type="text" value="0"/> LBS	###	ALLOWABLE SHEARWALL CAPACITY	<input type="text" value="#DIV/0!"/> LBS
--------------------------	------------------------------------	-----	------------------------------	--

**SHEARWALL ASSEMBLY SPECIFICATION**

P0 - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 6" O.C. PANEL EDGES & 12" O.C. PANEL FIELD - UNBLOCKED  
**#DIV/0!**

**OVERTURNING EVALUATION:**

RESISTIVE DL	<input type="text" value="0"/> PLF	OVERTURNING MOMENT	<input type="text" value="#DIV/0!"/> K-FT	HOLD DOWN DESIGN LOAD	<input type="text" value="0"/> LBS
DL AT ENDS OF WALL	<input type="text" value="0"/> LBS	RESISTIVE MOMENT	<input type="text" value="0.0"/> K-FT	HOLD DOWN CAPACITY	<input type="text" value="0"/> LBS

**HOLD-DOWN SPECIFICATION**

**NO HOLDOWN REQUIRED**



**SHEARWALL DESIGN SUMMARY**

M+K PROJECT #: 244-24010  
ENGINEER: RSC

**SHEARWALL 101: 1ST - FRONT EXT. WALL @ COVERED PATIO**

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H	<input type="text" value="9.1"/>	FT.	MAX WALL OPENING HT, H <sub>c</sub>	<input type="text" value="0.0"/>	FT.		
WALL LENGTH, L	<input type="text" value="15.3"/>	FT.	QUALIFYING WALL LENGTH, L	<input type="text" value="15.3"/>	FT.	SHEARWALL ASSEMBLY	<input type="text" value="P3"/>

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL	<input type="text" value="5000"/>	LBS	<	ALLOWABLE SHEARWALL CAPACITY	<input type="text" value="9661"/>	LBS
--------------------------	-----------------------------------	-----	---	------------------------------	-----------------------------------	-----

**SHEARWALL ASSEMBLY SPECIFICATION**

P3 - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 3"O.C. PANEL EDGES & 12"O.C. PANEL FIELD - EDGES BLOCKED  
**ADEQUATE**

**OVERTURNING EVALUATION:**

RESISTIVE DL	<input type="text" value="312"/>	PLF	OVERTURNING MOMENT	<input type="text" value="45.4"/>	K-FT	HOLD DOWN DESIGN LOAD	<input type="text" value="0"/>	LBS
DL AT ENDS OF WALL	<input type="text" value="1200"/>	LBS	RESISTIVE MOMENT	<input type="text" value="49.6"/>	K-FT	HOLD DOWN CAPACITY	<input type="text" value="0"/>	LBS

**HOLD-DOWN SPECIFICATION**

**NO HOLDOWN REQUIRED**

**SHEARWALL 102: 1ST - SIDE EXT. WALL @ COVERED PATIO**

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H	<input type="text" value="9.1"/>	FT.	MAX WALL OPENING HT, H <sub>c</sub>	<input type="text" value="0.0"/>	FT.		
WALL LENGTH, L	<input type="text" value="6.0"/>	FT.	QUALIFYING WALL LENGTH, L	<input type="text" value="6.0"/>	FT.	SHEARWALL ASSEMBLY	<input type="text" value="P3"/>

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL	<input type="text" value="2400"/>	LBS	<	ALLOWABLE SHEARWALL CAPACITY	<input type="text" value="3781"/>	LBS
--------------------------	-----------------------------------	-----	---	------------------------------	-----------------------------------	-----

**SHEARWALL ASSEMBLY SPECIFICATION**

P3 - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 3"O.C. PANEL EDGES & 12"O.C. PANEL FIELD - EDGES BLOCKED  
**ADEQUATE**

**OVERTURNING EVALUATION:**

RESISTIVE DL	<input type="text" value="356"/>	PLF	OVERTURNING MOMENT	<input type="text" value="45.8"/>	K-FT	HOLD DOWN DESIGN LOAD	<input type="text" value="5591"/>	LBS
DL AT ENDS OF WALL	<input type="text" value="1200"/>	LBS	RESISTIVE MOMENT	<input type="text" value="12.2"/>	K-FT	HOLD DOWN CAPACITY	<input type="text" value="3105"/>	LBS

**HOLD-DOWN SPECIFICATION**

**HOLDOWN INADEQUATE**



**SHEARWALL DESIGN SUMMARY**

M+K PROJECT #: 244-24010  
ENGINEER: RSC

**SHEARWALL 103:** 1ST - SIDE EXT. WALL @ COVERED PATIO

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H	<input type="text" value="9.1"/>	FT.	MAX WALL OPENING HT, H <sub>c</sub>	<input type="text" value="8.0"/>	FT.		
WALL LENGTH, L	<input type="text" value="18.8"/>	FT.	QUALIFYING WALL LENGTH, L	<input type="text" value="5.8"/>	FT.	SHEARWALL ASSEMBLY	<input type="text" value="P3"/>

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL	<input type="text" value="3100"/>	LBS	<	ALLOWABLE SHEARWALL CAPACITY	<input type="text" value="3136"/>	LBS
--------------------------	-----------------------------------	-----	---	------------------------------	-----------------------------------	-----

**SHEARWALL ASSEMBLY SPECIFICATION**

P3 - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 3"O.C. PANEL EDGES & 12"O.C. PANEL FIELD - EDGES BLOCKED  
**ADEQUATE**

**OVERTURNING EVALUATION:**

RESISTIVE DL	<input type="text" value="247"/>	PLF	OVERTURNING MOMENT	<input type="text" value="58.0"/>	K-FT	HOLD DOWN DESIGN LOAD	<input type="text" value="0"/>	LBS
DL AT ENDS OF WALL	<input type="text" value="1200"/>	LBS	RESISTIVE MOMENT	<input type="text" value="59.6"/>	K-FT	HOLDDOWN CAPACITY	<input type="text" value="0"/>	LBS

**HOLD-DOWN SPECIFICATION**

**NO HOLDOWN REQUIRED**

**SHEARWALL 104:** 1ST - SIDE EXT. WALL @ PDR - MECH

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H	<input type="text" value="4.0"/>	FT.	MAX WALL OPENING HT, H <sub>c</sub>	<input type="text" value="0.0"/>	FT.		
WALL LENGTH, L	<input type="text" value="18.3"/>	FT.	QUALIFYING WALL LENGTH, L	<input type="text" value="18.3"/>	FT.	SHEARWALL ASSEMBLY	<input type="text" value="P1"/>

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL	<input type="text" value="4000"/>	LBS	<	ALLOWABLE SHEARWALL CAPACITY	<input type="text" value="6155"/>	LBS
--------------------------	-----------------------------------	-----	---	------------------------------	-----------------------------------	-----

**SHEARWALL ASSEMBLY SPECIFICATION**

P1 - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 6"O.C. PANEL EDGES & 12"O.C. PANEL FIELD - EDGES BLOCKED  
**ADEQUATE**

**OVERTURNING EVALUATION:**

RESISTIVE DL	<input type="text" value="117"/>	PLF	OVERTURNING MOMENT	<input type="text" value="16.0"/>	K-FT	HOLD DOWN DESIGN LOAD	<input type="text" value="0"/>	LBS
DL AT ENDS OF WALL	<input type="text" value="1200"/>	LBS	RESISTIVE MOMENT	<input type="text" value="37.5"/>	K-FT	HOLDDOWN CAPACITY	<input type="text" value="0"/>	LBS

**HOLD-DOWN SPECIFICATION**

**NO HOLDOWN REQUIRED**



**SHEARWALL DESIGN SUMMARY**

M+K PROJECT #: 244-24010  
ENGINEER: RSC

**SHEARWALL 105: 1ST - SIDE EXT. WALL @ GAME RM**

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H	<input type="text" value="4.0"/>	FT.	MAX WALL OPENING HT, H <sub>c</sub>	<input type="text" value="0.0"/>	FT.		
WALL LENGTH, L	<input type="text" value="26.3"/>	FT.	QUALIFYING WALL LENGTH, L	<input type="text" value="26.3"/>	FT.	SHEARWALL ASSEMBLY	<input type="text" value="P1"/>

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL	<input type="text" value="5000"/>	LBS	<	ALLOWABLE SHEARWALL CAPACITY	<input type="text" value="8815"/>	LBS
--------------------------	-----------------------------------	-----	---	------------------------------	-----------------------------------	-----

**SHEARWALL ASSEMBLY SPECIFICATION**

P1 - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 6" O.C. PANEL EDGES & 12" O.C. PANEL FIELD - EDGES BLOCKED  
**ADEQUATE**

**OVERTURNING EVALUATION:**

RESISTIVE DL	<input type="text" value="117"/>	PLF	OVERTURNING MOMENT	<input type="text" value="20.0"/>	K-FT	HOLD DOWN DESIGN LOAD	<input type="text" value="0"/>	LBS
DL AT ENDS OF WALL	<input type="text" value="1200"/>	LBS	RESISTIVE MOMENT	<input type="text" value="64.6"/>	K-FT	HOLD DOWN CAPACITY	<input type="text" value="0"/>	LBS

**HOLD-DOWN SPECIFICATION**

**NO HOLDOWN REQUIRED**

**SHEARWALL : BASEMENT - NOT USED**

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H	<input type="text" value="0.0"/>	FT.	MAX WALL OPENING HT, H <sub>c</sub>	<input type="text" value="0.0"/>	FT.		
WALL LENGTH, L	<input type="text" value="0.0"/>	FT.	QUALIFYING WALL LENGTH, L	<input type="text" value="0.0"/>	FT.	SHEARWALL ASSEMBLY	<input type="text" value="P0"/>

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL	<input type="text" value="0"/>	LBS	###	ALLOWABLE SHEARWALL CAPACITY	<input type="text" value="#DIV/0!"/>	LBS
--------------------------	--------------------------------	-----	-----	------------------------------	--------------------------------------	-----

**SHEARWALL ASSEMBLY SPECIFICATION**


P0 - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 6" O.C. PANEL EDGES & 12" O.C. PANEL FIELD - UNBLOCKED  
**#DIV/0!**

**OVERTURNING EVALUATION:**

RESISTIVE DL	<input type="text" value="0"/>	PLF	OVERTURNING MOMENT	<input type="text" value="#DIV/0!"/>	K-FT	HOLD DOWN DESIGN LOAD	<input type="text" value="0"/>	LBS
DL AT ENDS OF WALL	<input type="text" value="0"/>	LBS	RESISTIVE MOMENT	<input type="text" value="0.0"/>	K-FT	HOLD DOWN CAPACITY	<input type="text" value="0"/>	LBS

**HOLD-DOWN SPECIFICATION**

**NO HOLDOWN REQUIRED**



**MULHERN+KULP**  
RESIDENTIAL STRUCTURAL ENGINEERING

# SHEAR WALL CALCULATIONS SEISMIC

DESIGN BUILT HOMES

86H AVE SE - LOT 2

*MERCER ISLAND*

*PARAMETERS:*

*SINGLE FAMILY HOME*

*DESIGN WIND SPEED: 100 MPH*

*WIND EXPOSURE CATEGORY: B*

*SEISMIC DESIGN CATEGORY: D1*

*CODE & DESIGN STANDARD: 2021 IBC CH. 1609, ASCE 7-16 CH. 26-30*

MULHERN & KULP STRUCTURAL ENGINEERING, INC.

NICHOLAS MARTIGNETTI, P.E., PROJECT MANAGER

RYAN CHAN, STAFF ENGINEER



**SEISMIC CALCULATION - ASCE 7-16**

M+K PROJECT #: 244-24010  
ENGINEER: RSC

**SEISMIC DESIGN CATEGORY:**

USER INPUTS:

SITE CLASS	D
SPECTRAL RESPONSE ACCELERATION 0.2 SEC, $S_{0.2}$	1.405
SPECTRAL RESPONSE ACCELERATION 1.0 SEC, $S_{1.0}$	0.489
OCCUPANCY CATEGORY	II

VARIABLES:

SITE COEFFICIENT, $F_A$	1.20
SITE COEFFICIENT, $F_V$	1.81

CALCULATED VALUES:

MAXIMUM SPECTRAL RESPONSE ACCELERATION, $S_{M0}$	1.686
MAXIMUM SPECTRAL RESPONSE ACCELERATION, $S_{M1}$	0.886
DESIGN SPECTRAL RESPONSE ACCELERATION, $S_{D0}$	1.124
DESIGN SPECTRAL RESPONSE ACCELERATION, $S_{D1}$	0.590
SEISMIC DESIGN CATEGORY (SHORT TERM)	D
SEISMIC DESIGN CATEGORY (1.0 SECOND TERM)	D

**BUILDING PERIOD DETERMINATION:**

USER INPUTS:

BUILDING PERIOD COEFFICIENT, $C_T$	0.020
LONG-PERIOD TRANS PERIOD, $T_L$ (SEC)	6
HT. ABV BASE TO HIGHEST LEVEL, $h_N$	31

CALCULATED VALUES:

APPROXIMATE FUNDAMENTAL PERIOD, $T_a$	0.265
$T_0$	0.105
$T_B$	0.525
SPECTRAL RESPONSE ACC., $S_s$ (G)	1.124

**SITE CLASS ASSUMPTION**

Yes	PER ASCE 7-16 SECTION 11.4.3 THE SITE CLASS MAY BE ASSUMED TO BE D
-----	--

**EQUIVALENT LATERAL FORCE PROCEDURE**

DEAD LOAD CALCULATION:

LEVEL	STORY HT. (FT.)	AREA (FT <sup>2</sup> )	DEAD LOAD (PSF)	DL OF EXT WALL TRIB. TO LEVEL (KIPS)	TOTAL LEVEL DL
1	10.6	2330	15	24.4	59 K
2	11.7	2835	15	15.9	58 K
3	9.1	2955	10	6.5	36 K
4	0.0	0	0	0.0	0 K
5	0.0	0	0	0.0	0 K
6	0.0	0	0	0.0	0 K
7	0.0	0	0	0.0	0 K
8	0.0	0	0	0.0	0 K
9	0.0	0	0	0.0	0 K
10	0.0	0	0	0.0	0 K
11	0.0	0	0	0.0	0 K
12	0.0	0	0	0.0	0 K
13	0.0	0	0	0.0	0 K
14	0.0	0	0	0.0	0 K
15	0.0	0	0	0.0	0 K

**TOTAL DEAD LOAD OF STRUCTURE** 154 KIPS

SEISMIC RESPONSE COEFFICIENT:


	TRANSVERSE	LONGITUDINAL
RESPONSE MODIFICATION FACTOR, $R$	6.5	6.5
OCCUPANCY IMPORTANCE FACTOR, $I_e$	1.00	1.00
SEISMIC RESPONSE COEFFICIENT, $C_s$	0.173	0.173

BASE SHEARS:

	TRANSVERSE	LONGITUDINAL	TRANSVERSE	LONGITUDINAL
ULTIMATE LOADS	27 K	27 K	ALLOWABLE LOADS	18.6 K

STORY SHEAR CALCULATION:

LEVEL	VERT. DIST. FACTOR, $C_{vt}$	ULTIMATE LOADS		ALLOWABLE LOADS			
		TRANSVERSE STORY SHEAR, $F_x$	LONGITUDINAL STORY SHEAR, $F_y$	TRANSVERSE STORY SHEAR, $F_x$	$\sum$ STORY SHEAR	LONGITUDINAL STORY SHEAR, $F_y$	$\sum$ STORY SHEAR
1	0.206	5.5 K	5.5 K	3.8 K	18.6 K	3.8 K	18.6 K
2	0.425	11.3 K	11.3 K	7.9 K	14.8 K	7.9 K	14.8 K
3	0.369	9.8 K	9.8 K	6.9 K	6.9 K	6.9 K	6.9 K
4	0.000	0.0 K	0.0 K	0.0 K	0.0 K	0.0 K	0.0 K
5	0.00	0.0 K	0.0 K	0.0 K	0.0 K	0.0 K	0.0 K
6	0.00	0.0 K	0.0 K	0.0 K	0.0 K	0.0 K	0.0 K
7	0.00	0.0 K	0.0 K	0.0 K	0.0 K	0.0 K	0.0 K
8	0.00	0.0 K	0.0 K	0.0 K	0.0 K	0.0 K	0.0 K
9	0.00	0.0 K	0.0 K	0.0 K	0.0 K	0.0 K	0.0 K
10	0.00	0.0 K	0.0 K	0.0 K	0.0 K	0.0 K	0.0 K
11	0.00	0.0 K	0.0 K	0.0 K	0.0 K	0.0 K	0.0 K
12	0.00	0.0 K	0.0 K	0.0 K	0.0 K	0.0 K	0.0 K
13	0.00	0.0 K	0.0 K	0.0 K	0.0 K	0.0 K	0.0 K
14	0.00	0.0 K	0.0 K	0.0 K	0.0 K	0.0 K	0.0 K
15	0.00	0.0 K	0.0 K	0.0 K	0.0 K	0.0 K	0.0 K



- GENERAL NOTES:**
1. PLATE HEIGHT @ UPPER FLOOR IS 9'-1", U.N.O.
  2. PLATE HEIGHT @ MAIN FLOOR IS 10'-0", U.N.O.
  3. PLATE HEIGHT @ LOWER FLOOR IS 9'-1" U.N.P.
  4. DIMENSION LINES ARE TO FACE OF STUD U.N.O.
  5. WINDOW SIZES & ROUGH OPENINGS TO BE VERIFIED BY CONTRACTOR.
  6. WINDOW HEAD HEIGHT AT MAIN FLOOR IS 8'-0" ABOVE SUBFLOOR, U.N.O. IF NOMINAL DOOR AND WINDOW HEIGHTS ARE SIMILAR, COORDINATE WITH DOOR AND WINDOW SPEC'S TO LOCATE FINAL ELEVATION OF THE HEAD HEIGHTS SO THAT ALL DOOR AND WINDOW TRIM ALIGN.
  7. WINDOW AND DOOR SIZES ARE DIMENSIONED IN FEET AND INCHES (E.G. 2828= 2'-8" W X 2'-8" H)
  8. EXTERIOR WALLS TO BE 2X6 STUDS AT 16" O.C., INTERIOR WALLS TO BE 2X4 STUDS AT 16" O.C., U.N.O.
  9. FIREBLOCK ALL PLUMBING PENETRATIONS AND STAIR RUNS PER IRC SEC. R302.11.
  10. SAFETY GLAZING PER IRC SEC. R308.4.
  11. ALL WOOD IN CONTACT WITH CONCRETE TO BE PRESSURE TREATED PER IRC SEC. R317.1.
  12. PROVIDE UNDER-STAIR PROTECTION (1/2" GWB) PER IRC SEC. R302.7.
  13. PROVIDE (1) LAYER OF 1/2" GWB AT THE GARAGE SIDE OF ALL WALLS SEPARATING THE GARAGE FROM THE RESIDENCE, ALL WALLS SUPPORTING A FLOOR CEILING ASSEMBLY BETWEEN THE GARAGE AND RESIDENCE, AND BETWEEN THE GARAGE AND ITS ATTIC. PROVIDE (1) LAYER 5/8" TYPE X GWB TO GARAGE CEILING IF BELOW HABITABLE ROOMS.
  14. HOUSE/GARAGE DOOR SHALL BE 1-3/4" THICK WOOD SOLID CORE, OR 1-3/4" THICK SOLID OR HONEYCOMB CORE STEEL DOOR, OR 20-MINUTE RATED FIRE DOOR W/ SELF CLOSING DEVICE.
  15. DUCTS IN THE GARAGE AND DUCTS PENETRATING THE WALLS AND CEILINGS SEPARATING THE DWELLING FROM THE GARAGE SHALL BE MIN. 26 GAUGE GALVANIZED STEEL.
  16. PER IRC SEC R311.7.5. MAX. RISER HEIGHT SHALL BE 7-3/4". MIN. TREAD DEPTH SHALL BE 10". STAIR NOSINGS: 3/4" MIN., 1-1/4" MAX. RADIUS @ LEADING EDGE OF TREAD. 9/16" MAX.
  17. PROVIDE HANDRAILS PER IRC SEC. R311.7.3. TOP OF HANDRAIL SHALL BE NOT LESS THAN 34" OR MORE THAN 38" ABOVE THE TREAD NOSINGS. HANDRAILS SHALL BE CONTINUOUS THE FULL LENGTH OF THE FLIGHT PER R311.7.2. THE HANDRAIL GRIP-SIZE SHALL BE PROVIDED PER R311.7.3.
  18. PROVIDE GUARDS (MIN. 36" HEIGHT) IN LOCATIONS PER IRC SEC. R312.
  19. FACTORY BUILT FIREPLACES & CHIMNEYS SHALL BE LISTED & LABELED AND SHALL BE INSTALLED & TERMINATED IN ACCORDANCE TO THE CONDITIONS OF THE LISTINGS. FACTORY BUILT FIREPLACES SHALL MEET EMISSION STANDARDS PER CH. 51-51 WAC.
  20. PROVIDE EXTERIOR AIR SUPPLY TO ANY FACTORY-BUILT FIREPLACE PER IRC SEC R1006.

- STRUCTURAL NOTES:**
1. PROVIDE 7/16" OSB OR 15/32" PLYWOOD SHEATHING & FASTEN PER STANDARD EXTERIOR WALL SHEATHING SPECIFICATIONS.
  2. PROVIDE 3" SCHEDULE 40 PIPE COLUMN CONT. TO FOUNDATION BELOW WITH 4"X12"X1/2" BASE PLATE FASTENED TO FOUNDATION WALL WITH (4)1/2" TITEN HD ANCHORS WITH 7" MIN. EMBED.
  3. STEEL BEAM OPT: PROVIDE 8"X7"X1/2" OFFSET CAP PLATE FASTENED TO BOTTOM FLANGE OF STEEL BEAM W/ (2) 3/4" A325 THRU BOLTS.
  4. GLB BEAM OPT: PROVIDE 12"X5 1/2"X1/2" OFFSET CAP PLATE FASTENED TO BOTTOM OF BEAM W/ (4) 1/4"X2 1/2" LONG SDS SCREWS
  5. PACKOUT STEEL BEAM AS REQUIRED W/ SOLID 2X MATERIAL THRU-BOLTED TO WEB WITH (2) 3/4" DIAMETER THRU-BOLTS @ 24" O.C. STAGGERED. FASTEN TOP PLATE TO STEEL BEAM PER SPEC ON S-0

**McCULLOUGH ARCHITECTS**


5601 6th Ave South  
Suite 371  
Seattle, WA, 98108  
206.443.1181  
mccullougharchitects.com

UNPUBLISHED WORK  
2021 © McCullough Architects

Date: 09.27.2024  
Job No: xx-xx  
Project No: 0000  
Drawn: BAK  
Approved: APM

Revisions  
00.00.2024 X

Owner: Design Built Homes




**XXXX 86th Ave SE**

Mercer Island, Washington

**BASEMENT FLOOR PLAN**

SCALE 1/4" = 1'-0"

700 SF




- GENERAL NOTES:**
1. PLATE HEIGHT @ UPPER FLOOR IS 9'-1", U.N.O.
  2. PLATE HEIGHT @ MAIN FLOOR IS 10'-0", U.N.O.
  3. PLATE HEIGHT @ LOWER FLOOR IS 9'-1" U.N.P.
  4. DIMENSION LINES ARE TO FACE OF STUD U.N.O.
  5. WINDOW SIZES & ROUGH OPENINGS TO BE VERIFIED BY CONTRACTOR.
  6. WINDOW HEAD HEIGHT AT MAIN FLOOR IS 8'-0" ABOVE SUBFLOOR, U.N.O. IF NOMINAL DOOR AND WINDOW HEIGHTS ARE SIMILAR, COORDINATE WITH DOOR AND WINDOW SPEC'S TO LOCATE FINAL ELEVATION OF THE HEAD HEIGHTS SO THAT ALL DOOR AND WINDOW TRIM ALIGN.
  7. WINDOW AND DOOR SIZES ARE DIMENSIONED IN FEET AND INCHES (E.G. 2828= 2'-8" W X 2'-8" H)
  8. EXTERIOR WALLS TO BE 2X6 STUDS AT 16" O.C., INTERIOR WALLS TO BE 2X4 STUDS AT 16" O.C., U.N.O.
  9. FIREBLOCK ALL PLUMBING PENETRATIONS AND STAIR RUNS PER IRC SEC. R302.11.
  10. SAFETY GLAZING PER IRC SEC. R308.4.
  11. ALL WOOD IN CONTACT WITH CONCRETE TO BE PRESSURE TREATED PER IRC SEC. R317.1.
  12. PROVIDE UNDER-STAIR PROTECTION (1/2" GWB) PER IRC SEC. R302.7.
  13. PROVIDE (1) LAYER OF 1/2" GWB AT THE GARAGE SIDE OF ALL WALLS SEPARATING THE GARAGE FROM THE RESIDENCE, ALL WALLS SUPPORTING A FLOOR CEILING ASSEMBLY BETWEEN THE GARAGE AND RESIDENCE, AND BETWEEN THE GARAGE AND ITS ATTIC. PROVIDE (1) LAYER 5/8" TYPE X GWB TO GARAGE CEILING IF BELOW HABITABLE ROOMS.
  14. HOUSE/GARAGE DOOR SHALL BE 1-3/4" THICK WOOD SOLID CORE, OR 1-3/4" THICK SOLID OR HONEYCOMB CORE STEEL DOOR, OR 20-MINUTE RATED FIRE DOOR W/ SELF CLOSING DEVICE.
  15. DUCTS IN THE GARAGE AND DUCTS PENETRATING THE WALLS AND CEILINGS SEPARATING THE DWELLING FROM THE GARAGE SHALL BE MIN. 26 GAUGE GALVANIZED STEEL.
  16. PER IRC SEC R311.7.5. MAX. RISER HEIGHT SHALL BE 7-3/4". MIN. TREAD DEPTH SHALL BE 10". STAIR NOSINGS: 3/4" MIN., 1-1/4" MAX. RADIUS @ LEADING EDGE OF TREAD. 9/16" MAX.
  17. PROVIDE HANDRAILS PER IRC SEC. R311.7.3. TOP OF HANDRAIL SHALL BE NOT LESS THAN 34" OR MORE THAN 38" ABOVE THE TREAD NOSINGS. HANDRAILS SHALL BE CONTINUOUS THE FULL LENGTH PER R311.7.2. THE HANDRAIL GRIP-SIZE SHALL BE 1-1/2" DIA PER R311.7.3.
  18. PROVIDE GUARDS (MIN. 36" HEIGHT) IN LOCATIONS PER IRC SEC. R312.1.
  19. REFRIGERATORS & CHIMNEYS SHALL BE LISTED & LABELED AND SHALL BE INSTALLED & TERMINATED IN ACCORDANCE TO THE CONDITIONS OF THE LISTINGS. FACTORY BUILT FIREPLACES SHALL MEET EMISSION STANDARDS PER CH. 51-51 WAC.
  20. PROVIDE EXTERIOR AIR SUPPLY TO ANY FACTORY-BUILT FIREPLACE PER IRC SEC R1006.

- STRUCTURAL NOTES:**
1. PROVIDE 7/16" OSB OR 15/32" PLYWOOD SHEATHING & FASTEN PER STANDARD EXTERIOR WALL SHEATHING SPECIFICATIONS.
  2. PROVIDE 3" SCHEDULE 40 PIPE COLUMN CONT. TO FOUNDATION LOW WITH 4"X12"X1/2" BASE PLATE FASTENED TO FOUNDATION WALL WITH (4)1/2" TITEN HD ANCHORS WITH 7" MIN. EMBED.
  3. STEEL BEAM OPT: PROVIDE 8"X7"X1/2" OFFSET CAP PLATE FASTENED TO BOTTOM FLANGE OF STEEL BEAM W/ (2) 3/4" A325 THRU BOLTS.
  4. GLB BEAM OPT: PROVIDE 12"X5 1/2"X1/2" OFFSET CAP PLATE FASTENED TO BOTTOM OF BEAM W/ (4) 1/4"X2 1/2" LONG SDS SCREWS
  5. PACKOUT STEEL BEAM AS REQUIRED W/ SOLID 2X MATERIAL THRU-BOLTED TO WEB WITH (2) 3/4" DIAMETER THRU-BOLTS @ 24" O.C. STAGGERED. FASTEN TOP PLATE TO STEEL BEAM PER SPEC ON S-0

**MAIN FLOOR PLAN**


SCALE 1/4" = 1'-0" 2,183 SF TOTAL = 4,827 SF

Date:	Job No:	Project No:	Drawn:	Approved:	Owner:
09.27.2024	xx-xxx	0000	BAK	APM	Design Built Homes



**XXXX 86th Ave SE**  
 Mercer Island, Washington

Revisions  
 00.00.2024 X



**UPPER FLOOR PLAN**

SCALE 1/4" = 1'-0" 1,933 SF


**GENERAL NOTES:**

1. PLATE HEIGHT @ UPPER FLOOR IS 9'-1", U.N.O. PLATE HEIGHT @ MAIN FLOOR IS 10'-0", U.N.O. PLATE HEIGHT @ LOWER FLOOR IS 9'-1" U.N.P.
2. DIMENSION LINES ARE TO FACE OF STUD U.N.O.
3. WINDOW SIZES & ROUGH OPENINGS TO BE VERIFIED BY CONTRACTOR.
4. WINDOW HEAD HEIGHT AT MAIN FLOOR IS 8'-0" ABOVE SUBFLOOR, U.N.O. IF NOMINAL DOOR AND WINDOW HEIGHTS ARE SIMILAR, COORDINATE WITH DOOR AND WINDOW SPECS TO LOCATE FINAL ELEVATION OF THE HEAD HEIGHTS SO THAT ALL DOOR AND WINDOW TRIM ALIGN.
5. WINDOW AND DOOR SIZES ARE DIMENSIONED IN FEET AND INCHES (E.G. 2828= 2'-8" W X 2'-8" H)
6. EXTERIOR WALLS TO BE 2X6 STUDS AT 16" O.C., INTERIOR WALLS TO BE 2X4 STUDS AT 16" O.C., U.N.O.
7. FIREBLOCK ALL PLUMBING PENETRATIONS AND STAIR RUNS PER IRC SEC. R302.11.
8. SAFETY GLAZING PER IRC SEC. R308.4.
9. ALL WOOD IN CONTACT WITH CONCRETE TO BE PRESSURE TREATED PER IRC SEC. R317.1.
10. PROVIDE UNDER-STAIR PROTECTION (1/2" GWB) PER IRC SEC. R302.7.
11. PROVIDE (1) LAYER OF 1/2" GWB AT THE GARAGE SIDE OF ALL WALLS SEPARATING THE GARAGE FROM THE RESIDENCE. ALL WALLS SUPPORTING A FLOOR CEILING ASSEMBLY BETWEEN THE GARAGE AND RESIDENCE, AND BETWEEN THE GARAGE AND ITS ATTIC. PROVIDE (1) LAYER 5/8" TYPE X GWB TO GARAGE CEILING IF BELOW HABITABLE ROOMS.
12. HOUSE/GARAGE DOOR SHALL BE 1-3/4" THICK WOOD SOLID CORE, OR 1-3/4" THICK SOLID OR HONEYCOMB CORE STEEL DOOR, OR 20-MINUTE RATED FIRE DOOR W/ SELF CLOSING DEVICE.
13. DUCTS IN THE GARAGE AND DUCTS PENETRATING THE WALLS AND CEILINGS SEPARATING THE DWELLING FROM THE GARAGE SHALL BE MIN. 26 GAUGE GALVANIZED STEEL
14. PER IRC SEC. R311.7.5, MAX. RISER HEIGHT SHALL BE 7-3/4", MIN. TREAD DEPTH SHALL BE 10", STAIR NOSINGS: 3/4" MIN., 1-1/4" MAX. RADIUS @ LEADING EDGE OF TREAD; 9/16" MAX. HANDRAIL SHALL BE NOT LESS THAN 34" OR MORE THAN 38" ABOVE THE TREAD NOSINGS. HANDRAILS SHALL BE CONTINUOUS THE FULL LENGTH OF THE FLIGHT PER R311.7.2. THE HANDRAIL GRIP-SIZE SHALL BE PROVIDED PER R311.7.3.
15. PROVIDE HANDRAILS PER IRC SEC. R311.7.8. TOP OF HANDRAIL SHALL BE NOT LESS THAN 34" OR MORE THAN 38" ABOVE THE TREAD NOSINGS. HANDRAILS SHALL BE CONTINUOUS THE FULL LENGTH OF THE FLIGHT PER R311.7.2. THE HANDRAIL GRIP-SIZE SHALL BE PROVIDED PER R311.7.3.
16. PROVIDE GUARDS (MIN. 36" HEIGHT) IN LOCATIONS PER IRC SEC. R312.
17. FACTORY BUILT FIREPLACES & CHIMNEYS SHALL BE LISTED & LABELED AND SHALL BE INSTALLED & TERMINATED IN ACCORDANCE TO THE CONDITIONS OF THE LISTINGS. FACTORY BUILT FIREPLACES SHALL MEET EMISSION STANDARDS PER CH. 51-51 WAC.
18. PROVIDE EXTERIOR AIR SUPPLY TO ANY FACTORY-BUILT FIREPLACE PER IRC SEC R1006.


**McCULLOUGH ARCHITECTS**  
 5601 6th Ave South  
 Suite 371  
 Seattle, WA, 98108  
 206.443.1181  
 mccullougharchitects.com  
 UNPUBLISHED WORK  
 2021 © McCullough Architects

Revisions	Comment
00.00.2024	X

Date: 09.27.2024  
 Job No: xx-xxx  
 Project No: 0000  
 Drawn: BAK  
 Approved: APW  
 Owner: Design Built Homes



**XXXX 86th Ave SE**  
 Mercer Island, Washington





**SHEARWALL DESIGN SUMMARY**

M+K PROJECT #: 244-24010

ENGINEER: RSC

**SHEARWALL 301:** 3RD - FRONT B.F. WALL @ GREAT RM

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H	<input type="text" value="16.0"/> FT.	MAX WALL OPENING HT, H <sub>c</sub>	<input type="text" value="0.0"/> FT.	
WALL LENGTH, L	<input type="text" value="4.8"/> FT.	QUALIFYING WALL LENGTH, L	<input type="text" value="4.8"/> FT.	SHEARWALL ASSEMBLY <input type="text" value="P1"/>

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL	<input type="text" value="600"/> LBS	<	ALLOWABLE SHEARWALL CAPACITY	<input type="text" value="944"/> LBS
--------------------------	--------------------------------------	---	------------------------------	--------------------------------------

**SHEARWALL ASSEMBLY SPECIFICATION**

P1 - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 6"O.C. PANEL EDGES & 12"O.C. PANEL FIELD - EDGES BLOCKED  
**ADEQUATE**

**OVERTURNING EVALUATION:**

RESISTIVE DL	<input type="text" value="213"/> PLF	OVERTURNING MOMENT	<input type="text" value="9.6"/> K-FT	HOLD DOWN DESIGN LOAD	<input type="text" value="1486"/> LBS
DL AT ENDS OF WALL	<input type="text" value="300"/> LBS	RESISTIVE MOMENT	<input type="text" value="2.5"/> K-FT	HOLDOWN CAPACITY	<input type="text" value="1705"/> LBS

**HOLD-DOWN SPECIFICATION**

**SIMPSON CS16 STRAP TIE (14" END LENGTH)**

**SHEARWALL 302:** 3RD - FRONT EXT. WALL @ W.I.C.

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H	<input type="text" value="9.1"/> FT.	MAX WALL OPENING HT, H <sub>c</sub>	<input type="text" value="0.0"/> FT.	
WALL LENGTH, L	<input type="text" value="4.0"/> FT.	QUALIFYING WALL LENGTH, L	<input type="text" value="4.0"/> FT.	SHEARWALL ASSEMBLY <input type="text" value="P1"/>

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL	<input type="text" value="200"/> LBS	<	ALLOWABLE SHEARWALL CAPACITY	<input type="text" value="915"/> LBS
--------------------------	--------------------------------------	---	------------------------------	--------------------------------------

**SHEARWALL ASSEMBLY SPECIFICATION**

P1 - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 6"O.C. PANEL EDGES & 12"O.C. PANEL FIELD - EDGES BLOCKED  
**ADEQUATE**

**OVERTURNING EVALUATION:**

RESISTIVE DL	<input type="text" value="251"/> PLF	OVERTURNING MOMENT	<input type="text" value="1.8"/> K-FT	HOLD DOWN DESIGN LOAD	<input type="text" value="0"/> LBS
DL AT ENDS OF WALL	<input type="text" value="400"/> LBS	RESISTIVE MOMENT	<input type="text" value="2.4"/> K-FT	HOLDOWN CAPACITY	<input type="text" value="0"/> LBS

**HOLD-DOWN SPECIFICATION**

**NO HOLDOWN REQUIRED**



**SHEARWALL DESIGN SUMMARY**

M+K PROJECT #: 244-24010  
ENGINEER: RSC

**SHEARWALL 303: 3RD - FRONT EXT. WALL @ BA 6**

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H	<input type="text" value="9.1"/>	FT.	MAX WALL OPENING HT, H <sub>c</sub>	<input type="text" value="0.0"/>	FT.		
WALL LENGTH, L	<input type="text" value="8.3"/>	FT.	QUALIFYING WALL LENGTH, L	<input type="text" value="8.3"/>	FT.	SHEARWALL ASSEMBLY	<input type="text" value="P1"/>

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL	<input type="text" value="700"/>	LBS	<	ALLOWABLE SHEARWALL CAPACITY	<input type="text" value="1993"/>	LBS
--------------------------	----------------------------------	-----	---	------------------------------	-----------------------------------	-----

**SHEARWALL ASSEMBLY SPECIFICATION**

P1 - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 6"O.C. PANEL EDGES & 12"O.C. PANEL FIELD - EDGES BLOCKED  
**ADEQUATE**

**OVERTURNING EVALUATION:**

RESISTIVE DL	<input type="text" value="214"/>	PLF	OVERTURNING MOMENT	<input type="text" value="6.4"/>	K-FT	HOLD DOWN DESIGN LOAD	<input type="text" value="0"/>	LBS
DL AT ENDS OF WALL	<input type="text" value="400"/>	LBS	RESISTIVE MOMENT	<input type="text" value="7.1"/>	K-FT	HOLD DOWN CAPACITY	<input type="text" value="0"/>	LBS

**HOLD-DOWN SPECIFICATION**

**NO HOLDOWN REQUIRED**

**SHEARWALL 304: 3RD - REAR EXT. WALL @ M BED - BED 4**

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H	<input type="text" value="9.1"/>	FT.	MAX WALL OPENING HT, H <sub>c</sub>	<input type="text" value="5.0"/>	FT.		
WALL LENGTH, L	<input type="text" value="36.1"/>	FT.	QUALIFYING WALL LENGTH, L	<input type="text" value="25.1"/>	FT.	SHEARWALL ASSEMBLY	<input type="text" value="P1"/>

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL	<input type="text" value="1900"/>	LBS	<	ALLOWABLE SHEARWALL CAPACITY	<input type="text" value="6016"/>	LBS
--------------------------	-----------------------------------	-----	---	------------------------------	-----------------------------------	-----

**SHEARWALL ASSEMBLY SPECIFICATION**

P1 - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 6"O.C. PANEL EDGES & 12"O.C. PANEL FIELD - EDGES BLOCKED  
**ADEQUATE**

**OVERTURNING EVALUATION:**

RESISTIVE DL	<input type="text" value="194"/>	PLF	OVERTURNING MOMENT	<input type="text" value="17.3"/>	K-FT	HOLD DOWN DESIGN LOAD	<input type="text" value="0"/>	LBS
DL AT ENDS OF WALL	<input type="text" value="400"/>	LBS	RESISTIVE MOMENT	<input type="text" value="93.4"/>	K-FT	HOLD DOWN CAPACITY	<input type="text" value="0"/>	LBS

**HOLD-DOWN SPECIFICATION**

**NO HOLDOWN REQUIRED**



**SHEARWALL DESIGN SUMMARY**

M+K PROJECT #: 244-24010  
ENGINEER: RSC

**SHEARWALL 305: 3RD - FRONT INT. WALL @ M BED**

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H	<input type="text" value="9.1"/>	FT.	MAX WALL OPENING HT, H <sub>c</sub>	<input type="text" value="8.0"/>	FT.	SHEARWALL ASSEMBLY	<input type="text" value="P1"/>
WALL LENGTH, L	<input type="text" value="41.1"/>	FT.	QUALIFYING WALL LENGTH, L	<input type="text" value="38.1"/>	FT.		

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL	<input type="text" value="3500"/>	LBS	<	ALLOWABLE SHEARWALL CAPACITY	<input type="text" value="9143"/>	LBS
--------------------------	-----------------------------------	-----	---	------------------------------	-----------------------------------	-----

**SHEARWALL ASSEMBLY SPECIFICATION**

P1 - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 6" O.C. PANEL EDGES & 12" O.C. PANEL FIELD - EDGES BLOCKED  
**ADEQUATE**

**OVERTURNING EVALUATION:**

RESISTIVE DL	<input type="text" value="206"/>	PLF	OVERTURNING MOMENT	<input type="text" value="31.8"/>	K-FT	HOLD DOWN DESIGN LOAD	<input type="text" value="0"/>	LBS
DL AT ENDS OF WALL	<input type="text" value="200"/>	LBS	RESISTIVE MOMENT	<input type="text" value="121.0"/>	K-FT	HOLD DOWN CAPACITY	<input type="text" value="0"/>	LBS

**HOLD-DOWN SPECIFICATION**

**NO HOLD DOWN REQUIRED**

**SHEARWALL : BASEMENT - NOT USED**

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H	<input type="text" value="0.0"/>	FT.	MAX WALL OPENING HT, H <sub>c</sub>	<input type="text" value="0.0"/>	FT.	SHEARWALL ASSEMBLY	<input type="text" value="P0"/>
WALL LENGTH, L	<input type="text" value="0.0"/>	FT.	QUALIFYING WALL LENGTH, L	<input type="text" value="0.0"/>	FT.		

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL	<input type="text" value="0"/>	LBS	###	ALLOWABLE SHEARWALL CAPACITY	<input type="text" value="#DIV/0!"/>	LBS
--------------------------	--------------------------------	-----	-----	------------------------------	--------------------------------------	-----

**SHEARWALL ASSEMBLY SPECIFICATION**


P0 - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 6" O.C. PANEL EDGES & 12" O.C. PANEL FIELD - UNBLOCKED  
**#DIV/0!**

**OVERTURNING EVALUATION:**

RESISTIVE DL	<input type="text" value="0"/>	PLF	OVERTURNING MOMENT	<input type="text" value="0.0"/>	K-FT	HOLD DOWN DESIGN LOAD	<input type="text" value="0"/>	LBS
DL AT ENDS OF WALL	<input type="text" value="0"/>	LBS	RESISTIVE MOMENT	<input type="text" value="0.0"/>	K-FT	HOLD DOWN CAPACITY	<input type="text" value="0"/>	LBS

**HOLD-DOWN SPECIFICATION**

**NO HOLD DOWN REQUIRED**



**SHEARWALL DESIGN SUMMARY**

M+K PROJECT #: 244-24010  
ENGINEER: RSC

**SHEARWALL 307: 3RD - SIDE EXT. WALL @ M BED**

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H	<input type="text" value="9.1"/>	FT.	MAX WALL OPENING HT, H <sub>c</sub>	<input type="text" value="0.0"/>	FT.		
WALL LENGTH, L	<input type="text" value="11.1"/>	FT.	QUALIFYING WALL LENGTH, L	<input type="text" value="11.1"/>	FT.	SHEARWALL ASSEMBLY	<input type="text" value="P1"/>

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL	<input type="text" value="700"/>	LBS	<	ALLOWABLE SHEARWALL CAPACITY	<input type="text" value="2660"/>	LBS
--------------------------	----------------------------------	-----	---	------------------------------	-----------------------------------	-----

**SHEARWALL ASSEMBLY SPECIFICATION**

P1 - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 6"O.C. PANEL EDGES & 12"O.C. PANEL FIELD - EDGES BLOCKED  
**ADEQUATE**

**OVERTURNING EVALUATION:**

RESISTIVE DL	<input type="text" value="113"/>	PLF	OVERTURNING MOMENT	<input type="text" value="6.4"/>	K-FT	HOLD DOWN DESIGN LOAD	<input type="text" value="0"/>	LBS
DL AT ENDS OF WALL	<input type="text" value="300"/>	LBS	RESISTIVE MOMENT	<input type="text" value="6.8"/>	K-FT	HOLDDOWN CAPACITY	<input type="text" value="0"/>	LBS

**HOLD-DOWN SPECIFICATION**

**NO HOLDOWN REQUIRED**

**SHEARWALL 308: 3RD - SIDE EXT. B.F. WALL @ GREAT RM**

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H	<input type="text" value="16.0"/>	FT.	MAX WALL OPENING HT, H <sub>c</sub>	<input type="text" value="0.0"/>	FT.		
WALL LENGTH, L	<input type="text" value="8.0"/>	FT.	QUALIFYING WALL LENGTH, L	<input type="text" value="8.0"/>	FT.	SHEARWALL ASSEMBLY	<input type="text" value="P1"/>

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL	<input type="text" value="1200"/>	LBS	<	ALLOWABLE SHEARWALL CAPACITY	<input type="text" value="1919"/>	LBS
--------------------------	-----------------------------------	-----	---	------------------------------	-----------------------------------	-----

**SHEARWALL ASSEMBLY SPECIFICATION**

P1 - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 6"O.C. PANEL EDGES & 12"O.C. PANEL FIELD - EDGES BLOCKED  
**ADEQUATE**

**OVERTURNING EVALUATION:**

RESISTIVE DL	<input type="text" value="279"/>	PLF	OVERTURNING MOMENT	<input type="text" value="19.2"/>	K-FT	HOLD DOWN DESIGN LOAD	<input type="text" value="1360"/>	LBS
DL AT ENDS OF WALL	<input type="text" value="450"/>	LBS	RESISTIVE MOMENT	<input type="text" value="8.3"/>	K-FT	HOLDDOWN CAPACITY	<input type="text" value="1705"/>	LBS

**HOLD-DOWN SPECIFICATION**

**SIMPSON CS16 STRAP TIE (14" END LENGTH)**



**SHEARWALL DESIGN SUMMARY**

M+K PROJECT #: 244-24010  
ENGINEER: RSC

**SHEARWALL 309: 3RD - SIDE EXT. WALL @ W.I.C.**

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H	<input type="text" value="9.1"/>	FT.	MAX WALL OPENING HT, H <sub>c</sub>	<input type="text" value="0.0"/>	FT.		
WALL LENGTH, L	<input type="text" value="8.1"/>	FT.	QUALIFYING WALL LENGTH, L	<input type="text" value="8.1"/>	FT.	SHEARWALL ASSEMBLY	<input type="text" value="P1"/>

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL	<input type="text" value="500"/>	LBS	<	ALLOWABLE SHEARWALL CAPACITY	<input type="text" value="1938"/>	LBS
--------------------------	----------------------------------	-----	---	------------------------------	-----------------------------------	-----

**SHEARWALL ASSEMBLY SPECIFICATION**

P1 - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 6"O.C. PANEL EDGES & 12"O.C. PANEL FIELD - EDGES BLOCKED  
**ADEQUATE**

**OVERTURNING EVALUATION:**

RESISTIVE DL	<input type="text" value="113"/>	PLF	OVERTURNING MOMENT	<input type="text" value="4.5"/>	K-FT	HOLD DOWN DESIGN LOAD	<input type="text" value="0"/>	LBS
DL AT ENDS OF WALL	<input type="text" value="450"/>	LBS	RESISTIVE MOMENT	<input type="text" value="4.9"/>	K-FT	HOLDDOWN CAPACITY	<input type="text" value="0"/>	LBS

**HOLD-DOWN SPECIFICATION**

**NO HOLDOWN REQUIRED**

**SHEARWALL 310: 3RD - SIDE EXT. WALL @ W.I.C.**

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H	<input type="text" value="9.1"/>	FT.	MAX WALL OPENING HT, H <sub>c</sub>	<input type="text" value="0.0"/>	FT.		
WALL LENGTH, L	<input type="text" value="7.2"/>	FT.	QUALIFYING WALL LENGTH, L	<input type="text" value="7.2"/>	FT.	SHEARWALL ASSEMBLY	<input type="text" value="P1"/>

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL	<input type="text" value="400"/>	LBS	<	ALLOWABLE SHEARWALL CAPACITY	<input type="text" value="1717"/>	LBS
--------------------------	----------------------------------	-----	---	------------------------------	-----------------------------------	-----

**SHEARWALL ASSEMBLY SPECIFICATION**

P1 - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 6"O.C. PANEL EDGES & 12"O.C. PANEL FIELD - EDGES BLOCKED  
**ADEQUATE**

**OVERTURNING EVALUATION:**

RESISTIVE DL	<input type="text" value="113"/>	PLF	OVERTURNING MOMENT	<input type="text" value="3.6"/>	K-FT	HOLD DOWN DESIGN LOAD	<input type="text" value="0"/>	LBS
DL AT ENDS OF WALL	<input type="text" value="450"/>	LBS	RESISTIVE MOMENT	<input type="text" value="4.1"/>	K-FT	HOLDDOWN CAPACITY	<input type="text" value="0"/>	LBS

**HOLD-DOWN SPECIFICATION**

**NO HOLDOWN REQUIRED**



**SHEARWALL DESIGN SUMMARY**

M+K PROJECT #: 244-24010  
ENGINEER: RSC

**SHEARWALL 311: 3RD - SIDE EXT. WALL @ W.I.C. - BA 6**

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H	<input type="text" value="9.1"/>	FT.	MAX WALL OPENING HT, H <sub>c</sub>	<input type="text" value="2.0"/>	FT.		
WALL LENGTH, L	<input type="text" value="14.9"/>	FT.	QUALIFYING WALL LENGTH, L	<input type="text" value="14.9"/>	FT.	SHEARWALL ASSEMBLY	<input type="text" value="P1"/>

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL	<input type="text" value="1400"/>	LBS	<	ALLOWABLE SHEARWALL CAPACITY	<input type="text" value="3579"/>	LBS
--------------------------	-----------------------------------	-----	---	------------------------------	-----------------------------------	-----

**SHEARWALL ASSEMBLY SPECIFICATION**

P1 - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 6"O.C. PANEL EDGES & 12"O.C. PANEL FIELD - EDGES BLOCKED  
**ADEQUATE**

**OVERTURNING EVALUATION:**

RESISTIVE DL	<input type="text" value="113"/>	PLF	OVERTURNING MOMENT	<input type="text" value="12.7"/>	K-FT	HOLD DOWN DESIGN LOAD	<input type="text" value="0"/>	LBS
DL AT ENDS OF WALL	<input type="text" value="450"/>	LBS	RESISTIVE MOMENT	<input type="text" value="12.8"/>	K-FT	HOLDDOWN CAPACITY	<input type="text" value="0"/>	LBS

**HOLD-DOWN SPECIFICATION**

**NO HOLDOWN REQUIRED**

**SHEARWALL 312: 3RD - SIDE INT. WALL @ LAUN.**

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H	<input type="text" value="9.1"/>	FT.	MAX WALL OPENING HT, H <sub>c</sub>	<input type="text" value="0.0"/>	FT.		
WALL LENGTH, L	<input type="text" value="14.6"/>	FT.	QUALIFYING WALL LENGTH, L	<input type="text" value="14.6"/>	FT.	SHEARWALL ASSEMBLY	<input type="text" value="P1"/>

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL	<input type="text" value="1200"/>	LBS	<	ALLOWABLE SHEARWALL CAPACITY	<input type="text" value="3502"/>	LBS
--------------------------	-----------------------------------	-----	---	------------------------------	-----------------------------------	-----

**SHEARWALL ASSEMBLY SPECIFICATION**

P1 - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 6"O.C. PANEL EDGES & 12"O.C. PANEL FIELD - EDGES BLOCKED  
**ADEQUATE**

**OVERTURNING EVALUATION:**

RESISTIVE DL	<input type="text" value="113"/>	PLF	OVERTURNING MOMENT	<input type="text" value="10.9"/>	K-FT	HOLD DOWN DESIGN LOAD	<input type="text" value="0"/>	LBS
DL AT ENDS OF WALL	<input type="text" value="400"/>	LBS	RESISTIVE MOMENT	<input type="text" value="11.9"/>	K-FT	HOLDDOWN CAPACITY	<input type="text" value="0"/>	LBS

**HOLD-DOWN SPECIFICATION**

**NO HOLDOWN REQUIRED**



**SHEARWALL DESIGN SUMMARY**

M+K PROJECT #: 244-24010  
ENGINEER: RSC

**SHEARWALL 313: 3RD - SIDE INT. WALL @ BED 3**

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H	<input type="text" value="9.1"/>	FT.	MAX WALL OPENING HT, H <sub>c</sub>	<input type="text" value="0.0"/>	FT.		
WALL LENGTH, L	<input type="text" value="18.8"/>	FT.	QUALIFYING WALL LENGTH, L	<input type="text" value="18.8"/>	FT.	SHEARWALL ASSEMBLY	<input type="text" value="P1"/>

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL	<input type="text" value="1500"/>	LBS	<	ALLOWABLE SHEARWALL CAPACITY	<input type="text" value="4497"/>	LBS
--------------------------	-----------------------------------	-----	---	------------------------------	-----------------------------------	-----

**SHEARWALL ASSEMBLY SPECIFICATION**

P1 - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 6" O.C. PANEL EDGES & 12" O.C. PANEL FIELD - EDGES BLOCKED  
**ADEQUATE**

**OVERTURNING EVALUATION:**

RESISTIVE DL	<input type="text" value="100"/>	PLF	OVERTURNING MOMENT	<input type="text" value="13.6"/>	K-FT	HOLD DOWN DESIGN LOAD	<input type="text" value="0"/>	LBS
DL AT ENDS OF WALL	<input type="text" value="200"/>	LBS	RESISTIVE MOMENT	<input type="text" value="14.2"/>	K-FT	HOLD DOWN CAPACITY	<input type="text" value="0"/>	LBS

**HOLD-DOWN SPECIFICATION**

**NO HOLDOWN REQUIRED**

**SHEARWALL : BASEMENT - NOT USED**

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H	<input type="text" value="0.0"/>	FT.	MAX WALL OPENING HT, H <sub>c</sub>	<input type="text" value="0.0"/>	FT.		
WALL LENGTH, L	<input type="text" value="0.0"/>	FT.	QUALIFYING WALL LENGTH, L	<input type="text" value="0.0"/>	FT.	SHEARWALL ASSEMBLY	<input type="text" value="P0"/>

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL	<input type="text" value="0"/>	LBS	###	ALLOWABLE SHEARWALL CAPACITY	<input type="text" value="#DIV/0!"/>	LBS
--------------------------	--------------------------------	-----	-----	------------------------------	--------------------------------------	-----

**SHEARWALL ASSEMBLY SPECIFICATION**

P0 - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 6" O.C. PANEL EDGES & 12" O.C. PANEL FIELD - UNBLOCKED  
**#DIV/0!**

**OVERTURNING EVALUATION:**

RESISTIVE DL	<input type="text" value="0"/>	PLF	OVERTURNING MOMENT	<input type="text" value="#DIV/0!"/>	K-FT	HOLD DOWN DESIGN LOAD	<input type="text" value="0"/>	LBS
DL AT ENDS OF WALL	<input type="text" value="0"/>	LBS	RESISTIVE MOMENT	<input type="text" value="0.0"/>	K-FT	HOLD DOWN CAPACITY	<input type="text" value="0"/>	LBS

**HOLD-DOWN SPECIFICATION**

**NO HOLDOWN REQUIRED**



**SHEARWALL DESIGN SUMMARY**

M+K PROJECT #: 244-24010  
ENGINEER: RSC

**SHEARWALL 201: 2ND - REAR EXT. WALL @ KITCHEN**

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H	<input type="text" value="10.0"/>	FT.	MAX WALL OPENING HT, H <sub>c</sub>	<input type="text" value="0.0"/>	FT.		
WALL LENGTH, L	<input type="text" value="17.2"/>	FT.	QUALIFYING WALL LENGTH, L	<input type="text" value="17.2"/>	FT.	SHEARWALL ASSEMBLY	<input type="text" value="P3"/>

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL	<input type="text" value="5200"/>	LBS	<	ALLOWABLE SHEARWALL CAPACITY	<input type="text" value="7720"/>	LBS
--------------------------	-----------------------------------	-----	---	------------------------------	-----------------------------------	-----

**SHEARWALL ASSEMBLY SPECIFICATION**

P3 - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 3"O.C. PANEL EDGES & 12"O.C. PANEL FIELD - EDGES BLOCKED  
**ADEQUATE**

**OVERTURNING EVALUATION:**

RESISTIVE DL	<input type="text" value="444"/>	PLF	OVERTURNING MOMENT	<input type="text" value="52.0"/>	K-FT	HOLD DOWN DESIGN LOAD	<input type="text" value="0"/>	LBS
DL AT ENDS OF WALL	<input type="text" value="800"/>	LBS	RESISTIVE MOMENT	<input type="text" value="52.5"/>	K-FT	HOLDDOWN CAPACITY	<input type="text" value="0"/>	LBS

**HOLD-DOWN SPECIFICATION**

**NO HOLDOWN REQUIRED**

**SHEARWALL 202: 2ND - REAR EXT. WALL @ GUEST SUITE**

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H	<input type="text" value="10.0"/>	FT.	MAX WALL OPENING HT, H <sub>c</sub>	<input type="text" value="0.0"/>	FT.		
WALL LENGTH, L	<input type="text" value="7.0"/>	FT.	QUALIFYING WALL LENGTH, L	<input type="text" value="7.0"/>	FT.	SHEARWALL ASSEMBLY	<input type="text" value="P1"/>

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL	<input type="text" value="400"/>	LBS	<	ALLOWABLE SHEARWALL CAPACITY	<input type="text" value="1669"/>	LBS
--------------------------	----------------------------------	-----	---	------------------------------	-----------------------------------	-----

**SHEARWALL ASSEMBLY SPECIFICATION**

P1 - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 6"O.C. PANEL EDGES & 12"O.C. PANEL FIELD - EDGES BLOCKED  
**ADEQUATE**

**OVERTURNING EVALUATION:**

RESISTIVE DL	<input type="text" value="208"/>	PLF	OVERTURNING MOMENT	<input type="text" value="4.0"/>	K-FT	HOLD DOWN DESIGN LOAD	<input type="text" value="0"/>	LBS
DL AT ENDS OF WALL	<input type="text" value="200"/>	LBS	RESISTIVE MOMENT	<input type="text" value="4.3"/>	K-FT	HOLDDOWN CAPACITY	<input type="text" value="0"/>	LBS

**HOLD-DOWN SPECIFICATION**

**NO HOLDOWN REQUIRED**



**SHEARWALL DESIGN SUMMARY**

M+K PROJECT #: 244-24010  
ENGINEER: RSC

**SHEARWALL 203: 2ND - REAR EXT. WALL @ GUEST BA**

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H  FT.      MAX WALL OPENING HT, H<sub>c</sub>  FT.  
WALL LENGTH, L  FT.      QUALIFYING WALL LENGTH, L  FT.      SHEARWALL ASSEMBLY

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL  LBS < ALLOWABLE SHEARWALL CAPACITY  LBS

**SHEARWALL ASSEMBLY SPECIFICATION**

P1 - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 6"O.C. PANEL EDGES & 12"O.C. PANEL FIELD - EDGES BLOCKED  
**ADEQUATE**

**OVERTURNING EVALUATION:**

RESISTIVE DL  PLF      OVERTURNING MOMENT  K-FT      HOLD DOWN DESIGN LOAD  LBS  
DL AT ENDS OF WALL  LBS      RESISTIVE MOMENT  K-FT      HOLDDOWN CAPACITY  LBS

**HOLD-DOWN SPECIFICATION**

**NO HOLDOWN REQUIRED**

**SHEARWALL 204: 2ND - REAR INT. WALL @ HALL**

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H  FT.      MAX WALL OPENING HT, H<sub>c</sub>  FT.  
WALL LENGTH, L  FT.      QUALIFYING WALL LENGTH, L  FT.      SHEARWALL ASSEMBLY

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL  LBS < ALLOWABLE SHEARWALL CAPACITY  LBS

**SHEARWALL ASSEMBLY SPECIFICATION**

P3 - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 3"O.C. PANEL EDGES & 12"O.C. PANEL FIELD - EDGES BLOCKED  
**ADEQUATE**

**OVERTURNING EVALUATION:**

RESISTIVE DL  PLF      OVERTURNING MOMENT  K-FT      HOLD DOWN DESIGN LOAD  LBS  
DL AT ENDS OF WALL  LBS      RESISTIVE MOMENT  K-FT      HOLDDOWN CAPACITY  LBS

**HOLD-DOWN SPECIFICATION**

**NO HOLDOWN REQUIRED**



**SHEARWALL DESIGN SUMMARY**

M+K PROJECT #: 244-24010  
ENGINEER: RSC

**SHEARWALL 205: 2ND - REAR INT. WALL @ GARAGE**

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H	<input type="text" value="10.0"/> FT.	MAX WALL OPENING HT, H <sub>c</sub>	<input type="text" value="0.0"/> FT.	
WALL LENGTH, L	<input type="text" value="29.0"/> FT.	QUALIFYING WALL LENGTH, L	<input type="text" value="29.0"/> FT.	SHEARWALL ASSEMBLY <input type="text" value="P1"/>

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL	<input type="text" value="5000"/> LBS	<	ALLOWABLE SHEARWALL CAPACITY	<input type="text" value="6956"/> LBS
--------------------------	---------------------------------------	---	------------------------------	---------------------------------------

**SHEARWALL ASSEMBLY SPECIFICATION**

P1 - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 6"O.C. PANEL EDGES & 12"O.C. PANEL FIELD - EDGES BLOCKED  
**ADEQUATE**

**OVERTURNING EVALUATION:**

RESISTIVE DL	<input type="text" value="338"/> PLF	OVERTURNING MOMENT	<input type="text" value="50.0"/> K-FT	HOLD DOWN DESIGN LOAD	<input type="text" value="0"/> LBS
DL AT ENDS OF WALL	<input type="text" value="400"/> LBS	RESISTIVE MOMENT	<input type="text" value="102.1"/> K-FT	HOLD DOWN CAPACITY	<input type="text" value="0"/> LBS

**HOLD-DOWN SPECIFICATION**

**NO HOLD DOWN REQUIRED**

**SHEARWALL 206: 2ND - SIDE EXT. WALL @ OUTDOOR LIVING**

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H	<input type="text" value="10.0"/> FT.	MAX WALL OPENING HT, H <sub>c</sub>	<input type="text" value="0.0"/> FT.	
WALL LENGTH, L	<input type="text" value="6.0"/> FT.	QUALIFYING WALL LENGTH, L	<input type="text" value="6.0"/> FT.	SHEARWALL ASSEMBLY <input type="text" value="P3"/>

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL	<input type="text" value="2100"/> LBS	<	ALLOWABLE SHEARWALL CAPACITY	<input type="text" value="2701"/> LBS
--------------------------	---------------------------------------	---	------------------------------	---------------------------------------

**SHEARWALL ASSEMBLY SPECIFICATION**

P3 - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 3"O.C. PANEL EDGES & 12"O.C. PANEL FIELD - EDGES BLOCKED  
**ADEQUATE**

**OVERTURNING EVALUATION:**

RESISTIVE DL	<input type="text" value="243"/> PLF	OVERTURNING MOMENT	<input type="text" value="21.0"/> K-FT	HOLD DOWN DESIGN LOAD	<input type="text" value="2750"/> LBS
DL AT ENDS OF WALL	<input type="text" value="400"/> LBS	RESISTIVE MOMENT	<input type="text" value="4.5"/> K-FT	HOLD DOWN CAPACITY	<input type="text" value="5505"/> LBS

**HOLD-DOWN SPECIFICATION**

**SIMPSON MSTC66 STRAP TIE (24" END LENGTH)**



**SHEARWALL DESIGN SUMMARY**

M+K PROJECT #: 244-24010  
ENGINEER: RSC

**SHEARWALL 207: 2ND - SIDE EXT. WALL @ OUTDOOR LIVING**

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H	<input type="text" value="10.0"/> FT.	MAX WALL OPENING HT, H <sub>c</sub>	<input type="text" value="8.0"/> FT.	
WALL LENGTH, L	<input type="text" value="19.5"/> FT.	QUALIFYING WALL LENGTH, L	<input type="text" value="7.5"/> FT.	SHEARWALL ASSEMBLY <input type="text" value="P3"/>

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL	<input type="text" value="2100"/> LBS	<	ALLOWABLE SHEARWALL CAPACITY	<input type="text" value="3324"/> LBS
--------------------------	---------------------------------------	---	------------------------------	---------------------------------------

**SHEARWALL ASSEMBLY SPECIFICATION**

P3 - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 3"O.C. PANEL EDGES & 12"O.C. PANEL FIELD - EDGES BLOCKED  
**ADEQUATE**

**OVERTURNING EVALUATION:**

RESISTIVE DL	<input type="text" value="130"/> PLF	OVERTURNING MOMENT	<input type="text" value="21.0"/> K-FT	HOLD DOWN DESIGN LOAD	<input type="text" value="0"/> LBS
DL AT ENDS OF WALL	<input type="text" value="1200"/> LBS	RESISTIVE MOMENT	<input type="text" value="32.0"/> K-FT	HOLD DOWN CAPACITY	<input type="text" value="0"/> LBS

**HOLD-DOWN SPECIFICATION**

**NO HOLDOWN REQUIRED**

**SHEARWALL 208: 2ND - SIDE EXT. WALL @ GARAGE**

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H	<input type="text" value="10.0"/> FT.	MAX WALL OPENING HT, H <sub>c</sub>	<input type="text" value="0.0"/> FT.	
WALL LENGTH, L	<input type="text" value="23.0"/> FT.	QUALIFYING WALL LENGTH, L	<input type="text" value="23.0"/> FT.	SHEARWALL ASSEMBLY <input type="text" value="P1"/>

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL	<input type="text" value="3600"/> LBS	<	ALLOWABLE SHEARWALL CAPACITY	<input type="text" value="5517"/> LBS
--------------------------	---------------------------------------	---	------------------------------	---------------------------------------

**SHEARWALL ASSEMBLY SPECIFICATION**

P1 - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 6"O.C. PANEL EDGES & 12"O.C. PANEL FIELD - EDGES BLOCKED  
**ADEQUATE**

**OVERTURNING EVALUATION:**

RESISTIVE DL	<input type="text" value="151"/> PLF	OVERTURNING MOMENT	<input type="text" value="36.0"/> K-FT	HOLD DOWN DESIGN LOAD	<input type="text" value="0"/> LBS
DL AT ENDS OF WALL	<input type="text" value="800"/> LBS	RESISTIVE MOMENT	<input type="text" value="38.7"/> K-FT	HOLD DOWN CAPACITY	<input type="text" value="0"/> LBS

**HOLD-DOWN SPECIFICATION**

**NO HOLDOWN REQUIRED**



**SHEARWALL DESIGN SUMMARY**

M+K PROJECT #: 244-24010  
ENGINEER: RSC

**SHEARWALL 209: 2ND - SIDE EXT. WALL @ GUEST BA - W.I.C.**

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H	<input type="text" value="10.0"/>	FT.	MAX WALL OPENING HT, H <sub>c</sub>	<input type="text" value="0.0"/>	FT.		
WALL LENGTH, L	<input type="text" value="14.0"/>	FT.	QUALIFYING WALL LENGTH, L	<input type="text" value="14.0"/>	FT.	SHEARWALL ASSEMBLY	<input type="text" value="P1"/>

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL	<input type="text" value="1800"/>	LBS	<	ALLOWABLE SHEARWALL CAPACITY	<input type="text" value="3358"/>	LBS
--------------------------	-----------------------------------	-----	---	------------------------------	-----------------------------------	-----

**SHEARWALL ASSEMBLY SPECIFICATION**

P1 - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 6"O.C. PANEL EDGES & 12"O.C. PANEL FIELD - EDGES BLOCKED  
**ADEQUATE**

**OVERTURNING EVALUATION:**

RESISTIVE DL	<input type="text" value="113"/>	PLF	OVERTURNING MOMENT	<input type="text" value="18.0"/>	K-FT	HOLD DOWN DESIGN LOAD	<input type="text" value="0"/>	LBS
DL AT ENDS OF WALL	<input type="text" value="1200"/>	LBS	RESISTIVE MOMENT	<input type="text" value="18.5"/>	K-FT	HOLDDOWN CAPACITY	<input type="text" value="0"/>	LBS

**HOLD-DOWN SPECIFICATION**

**NO HOLDOWN REQUIRED**

**SHEARWALL 210: 2ND - SIDE INT. WALL @ OFFICE**

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H	<input type="text" value="10.0"/>	FT.	MAX WALL OPENING HT, H <sub>c</sub>	<input type="text" value="0.0"/>	FT.		
WALL LENGTH, L	<input type="text" value="16.9"/>	FT.	QUALIFYING WALL LENGTH, L	<input type="text" value="16.9"/>	FT.	SHEARWALL ASSEMBLY	<input type="text" value="P1"/>

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL	<input type="text" value="1800"/>	LBS	<	ALLOWABLE SHEARWALL CAPACITY	<input type="text" value="4049"/>	LBS
--------------------------	-----------------------------------	-----	---	------------------------------	-----------------------------------	-----

**SHEARWALL ASSEMBLY SPECIFICATION**

P1 - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 6"O.C. PANEL EDGES & 12"O.C. PANEL FIELD - EDGES BLOCKED  
**ADEQUATE**

**OVERTURNING EVALUATION:**

RESISTIVE DL	<input type="text" value="230"/>	PLF	OVERTURNING MOMENT	<input type="text" value="30.3"/>	K-FT	HOLD DOWN DESIGN LOAD	<input type="text" value="0"/>	LBS
DL AT ENDS OF WALL	<input type="text" value="800"/>	LBS	RESISTIVE MOMENT	<input type="text" value="30.7"/>	K-FT	HOLDDOWN CAPACITY	<input type="text" value="0"/>	LBS

**HOLD-DOWN SPECIFICATION**

**NO HOLDOWN REQUIRED**



**SHEARWALL DESIGN SUMMARY**

M+K PROJECT #: 244-24010  
ENGINEER: RSC

**SHEARWALL 211: 2ND - SIDE INT. WALL @ GARAGE**

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H  FT.      MAX WALL OPENING HT, H<sub>c</sub>  FT.  
WALL LENGTH, L  FT.      QUALIFYING WALL LENGTH, L  FT.      SHEARWALL ASSEMBLY

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL  LBS < ALLOWABLE SHEARWALL CAPACITY  LBS

**SHEARWALL ASSEMBLY SPECIFICATION**

P1 - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 6" O.C. PANEL EDGES & 12" O.C. PANEL FIELD - EDGES BLOCKED  
**ADEQUATE**

**OVERTURNING EVALUATION:**

RESISTIVE DL  PLF      OVERTURNING MOMENT  K-FT      HOLD DOWN DESIGN LOAD  LBS  
DL AT ENDS OF WALL  LBS      RESISTIVE MOMENT  K-FT      HOLDDOWN CAPACITY  LBS

**HOLD-DOWN SPECIFICATION**

**NO HOLDOWN REQUIRED**

**SHEARWALL : BASEMENT - NOT USED**

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H  FT.      MAX WALL OPENING HT, H<sub>c</sub>  FT.  
WALL LENGTH, L  FT.      QUALIFYING WALL LENGTH, L  FT.      SHEARWALL ASSEMBLY

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL  LBS      ALLOWABLE SHEARWALL CAPACITY  LBS  
 LBS      **#DIV/0!** LBS

**SHEARWALL ASSEMBLY SPECIFICATION**

P0 - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 6" O.C. PANEL EDGES & 12" O.C. PANEL FIELD - UNBLOCKED  
**#DIV/0!**

**OVERTURNING EVALUATION:**

RESISTIVE DL  PLF      OVERTURNING MOMENT  K-FT      HOLD DOWN DESIGN LOAD  LBS  
DL AT ENDS OF WALL  LBS      RESISTIVE MOMENT  K-FT      HOLDDOWN CAPACITY  LBS

**HOLD-DOWN SPECIFICATION**

**NO HOLDOWN REQUIRED**



**SHEARWALL DESIGN SUMMARY**

M+K PROJECT #: 244-24010  
ENGINEER: RSC

**SHEARWALL 101: 1ST - FRONT EXT. WALL @ COVERED PATIO**

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H	<input type="text" value="9.1"/>	FT.	MAX WALL OPENING HT, H <sub>c</sub>	<input type="text" value="0.0"/>	FT.		
WALL LENGTH, L	<input type="text" value="15.3"/>	FT.	QUALIFYING WALL LENGTH, L	<input type="text" value="15.3"/>	FT.	SHEARWALL ASSEMBLY	<input type="text" value="P3"/>

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL	<input type="text" value="4000"/>	LBS	<	ALLOWABLE SHEARWALL CAPACITY	<input type="text" value="6901"/>	LBS
--------------------------	-----------------------------------	-----	---	------------------------------	-----------------------------------	-----

**SHEARWALL ASSEMBLY SPECIFICATION**

P3 - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 3"O.C. PANEL EDGES & 12"O.C. PANEL FIELD - EDGES BLOCKED  
**ADEQUATE**

**OVERTURNING EVALUATION:**

RESISTIVE DL	<input type="text" value="312"/>	PLF	OVERTURNING MOMENT	<input type="text" value="36.3"/>	K-FT	HOLD DOWN DESIGN LOAD	<input type="text" value="0"/>	LBS
DL AT ENDS OF WALL	<input type="text" value="1200"/>	LBS	RESISTIVE MOMENT	<input type="text" value="36.6"/>	K-FT	HOLDDOWN CAPACITY	<input type="text" value="0"/>	LBS

**HOLD-DOWN SPECIFICATION**

**NO HOLDOWN REQUIRED**

**SHEARWALL 102: 1ST - SIDE EXT. WALL @ COVERED PATIO**

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H	<input type="text" value="9.1"/>	FT.	MAX WALL OPENING HT, H <sub>c</sub>	<input type="text" value="0.0"/>	FT.		
WALL LENGTH, L	<input type="text" value="6.0"/>	FT.	QUALIFYING WALL LENGTH, L	<input type="text" value="6.0"/>	FT.	SHEARWALL ASSEMBLY	<input type="text" value="P3"/>

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL	<input type="text" value="2700"/>	LBS	<	ALLOWABLE SHEARWALL CAPACITY	<input type="text" value="2701"/>	LBS
--------------------------	-----------------------------------	-----	---	------------------------------	-----------------------------------	-----

**SHEARWALL ASSEMBLY SPECIFICATION**

P3 - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 3"O.C. PANEL EDGES & 12"O.C. PANEL FIELD - EDGES BLOCKED  
**ADEQUATE**

**OVERTURNING EVALUATION:**

RESISTIVE DL	<input type="text" value="356"/>	PLF	OVERTURNING MOMENT	<input type="text" value="45.5"/>	K-FT	HOLD DOWN DESIGN LOAD	<input type="text" value="6080"/>	LBS
DL AT ENDS OF WALL	<input type="text" value="1200"/>	LBS	RESISTIVE MOMENT	<input type="text" value="9.0"/>	K-FT	HOLDDOWN CAPACITY	<input type="text" value="3105"/>	LBS

**HOLD-DOWN SPECIFICATION**

**HOLDOWN INADEQUATE**



**SHEARWALL DESIGN SUMMARY**

M+K PROJECT #: 244-24010  
ENGINEER: RSC

**SHEARWALL 103:** 1ST - SIDE EXT. WALL @ COVERED PATIO

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H	<input type="text" value="9.1"/>	FT.	MAX WALL OPENING HT, H <sub>c</sub>	<input type="text" value="8.0"/>	FT.		
WALL LENGTH, L	<input type="text" value="18.8"/>	FT.	QUALIFYING WALL LENGTH, L	<input type="text" value="5.8"/>	FT.	SHEARWALL ASSEMBLY	<input type="text" value="P3"/>

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL	<input type="text" value="2200"/>	LBS	<	ALLOWABLE SHEARWALL CAPACITY	<input type="text" value="2240"/>	LBS
--------------------------	-----------------------------------	-----	---	------------------------------	-----------------------------------	-----

**SHEARWALL ASSEMBLY SPECIFICATION**

**P3 - 1-SIDE 7/16" OSB**  
FASTENED W/ 8D NAILS AT 3"O.C. PANEL EDGES & 12"O.C. PANEL FIELD - EDGES BLOCKED  
**ADEQUATE**

**OVERTURNING EVALUATION:**

RESISTIVE DL	<input type="text" value="247"/>	PLF	OVERTURNING MOMENT	<input type="text" value="40.2"/>	K-FT	HOLD DOWN DESIGN LOAD	<input type="text" value="0"/>	LBS
DL AT ENDS OF WALL	<input type="text" value="1200"/>	LBS	RESISTIVE MOMENT	<input type="text" value="44.0"/>	K-FT	HOLDDOWN CAPACITY	<input type="text" value="0"/>	LBS

**HOLD-DOWN SPECIFICATION**

**NO HOLDOWN REQUIRED**

**SHEARWALL 104:** 1ST - SIDE EXT. WALL @ PDR - MECH

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H	<input type="text" value="4.0"/>	FT.	MAX WALL OPENING HT, H <sub>c</sub>	<input type="text" value="0.0"/>	FT.		
WALL LENGTH, L	<input type="text" value="18.3"/>	FT.	QUALIFYING WALL LENGTH, L	<input type="text" value="18.3"/>	FT.	SHEARWALL ASSEMBLY	<input type="text" value="P1"/>

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL	<input type="text" value="3500"/>	LBS	<	ALLOWABLE SHEARWALL CAPACITY	<input type="text" value="4397"/>	LBS
--------------------------	-----------------------------------	-----	---	------------------------------	-----------------------------------	-----

**SHEARWALL ASSEMBLY SPECIFICATION**

**P1 - 1-SIDE 7/16" OSB**  
FASTENED W/ 8D NAILS AT 6"O.C. PANEL EDGES & 12"O.C. PANEL FIELD - EDGES BLOCKED  
**ADEQUATE**

**OVERTURNING EVALUATION:**

RESISTIVE DL	<input type="text" value="117"/>	PLF	OVERTURNING MOMENT	<input type="text" value="14.0"/>	K-FT	HOLD DOWN DESIGN LOAD	<input type="text" value="0"/>	LBS
DL AT ENDS OF WALL	<input type="text" value="1200"/>	LBS	RESISTIVE MOMENT	<input type="text" value="27.7"/>	K-FT	HOLDDOWN CAPACITY	<input type="text" value="0"/>	LBS

**HOLD-DOWN SPECIFICATION**

**NO HOLDOWN REQUIRED**



**SHEARWALL DESIGN SUMMARY**

M+K PROJECT #: 244-24010  
ENGINEER: RSC

**SHEARWALL 105: 1ST - SIDE EXT. WALL @ GAME RM**

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H	<input type="text" value="4.0"/>	FT.	MAX WALL OPENING HT, H <sub>c</sub>	<input type="text" value="0.0"/>	FT.		
WALL LENGTH, L	<input type="text" value="26.3"/>	FT.	QUALIFYING WALL LENGTH, L	<input type="text" value="26.3"/>	FT.	SHEARWALL ASSEMBLY	<input type="text" value="P1"/>

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL	<input type="text" value="3000"/>	LBS	<	ALLOWABLE SHEARWALL CAPACITY	<input type="text" value="6296"/>	LBS
--------------------------	-----------------------------------	-----	---	------------------------------	-----------------------------------	-----

**SHEARWALL ASSEMBLY SPECIFICATION**

P1 - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 6" O.C. PANEL EDGES & 12" O.C. PANEL FIELD - EDGES BLOCKED  
**ADEQUATE**

**OVERTURNING EVALUATION:**

RESISTIVE DL	<input type="text" value="117"/>	PLF	OVERTURNING MOMENT	<input type="text" value="12.0"/>	K-FT	HOLD DOWN DESIGN LOAD	<input type="text" value="0"/>	LBS
DL AT ENDS OF WALL	<input type="text" value="1200"/>	LBS	RESISTIVE MOMENT	<input type="text" value="47.7"/>	K-FT	HOLD DOWN CAPACITY	<input type="text" value="0"/>	LBS

**HOLD-DOWN SPECIFICATION**

**NO HOLDOWN REQUIRED**

**SHEARWALL : BASEMENT - NOT USED**

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H	<input type="text" value="0.0"/>	FT.	MAX WALL OPENING HT, H <sub>c</sub>	<input type="text" value="0.0"/>	FT.		
WALL LENGTH, L	<input type="text" value="0.0"/>	FT.	QUALIFYING WALL LENGTH, L	<input type="text" value="0.0"/>	FT.	SHEARWALL ASSEMBLY	<input type="text" value="P0"/>

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL	<input type="text" value="0"/>	LBS	###	ALLOWABLE SHEARWALL CAPACITY	<input type="text" value="#DIV/0!"/>	LBS
--------------------------	--------------------------------	-----	-----	------------------------------	--------------------------------------	-----

**SHEARWALL ASSEMBLY SPECIFICATION**

P0 - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 6" O.C. PANEL EDGES & 12" O.C. PANEL FIELD - UNBLOCKED  
**#DIV/0!**

**OVERTURNING EVALUATION:**

RESISTIVE DL	<input type="text" value="0"/>	PLF	OVERTURNING MOMENT	<input type="text" value="#DIV/0!"/>	K-FT	HOLD DOWN DESIGN LOAD	<input type="text" value="0"/>	LBS
DL AT ENDS OF WALL	<input type="text" value="0"/>	LBS	RESISTIVE MOMENT	<input type="text" value="0.0"/>	K-FT	HOLD DOWN CAPACITY	<input type="text" value="0"/>	LBS

**HOLD-DOWN SPECIFICATION**

**NO HOLDOWN REQUIRED**



**SHEARWALL DESIGN SUMMARY**

M+K PROJECT #: 244-24010  
ENGINEER: RSC

**SHEARWALL** : BASEMENT - NOT USED

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H  FT.      MAX WALL OPENING HT, H<sub>c</sub>  FT.  
WALL LENGTH, L  FT.      QUALIFYING WALL LENGTH, L  FT.      SHEARWALL ASSEMBLY

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL  LBS      ALLOWABLE SHEARWALL CAPACITY  LBS  
#DIV/0!

**SHEARWALL ASSEMBLY SPECIFICATION**

PO - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 6" O.C. PANEL EDGES & 12" O.C. PANEL FIELD - UNBLOCKED  
#DIV/0!

**OVERTURNING EVALUATION:**

RESISTIVE DL  PLF      OVERTURNING MOMENT  K-FT      HOLD DOWN DESIGN LOAD  LBS  
DL AT ENDS OF WALL  LBS      RESISTIVE MOMENT  K-FT      HOLDOWN CAPACITY  LBS

**HOLD-DOWN SPECIFICATION**

NO HOLDOWN REQUIRED

**SHEARWALL** : BASEMENT - NOT USED

**SHEARWALL PROPERTIES:**

WALL HEIGHT, H  FT.      MAX WALL OPENING HT, H<sub>c</sub>  FT.  
WALL LENGTH, L  FT.      QUALIFYING WALL LENGTH, L  FT.      SHEARWALL ASSEMBLY

**CAPACITY EVALUATION:**

TOTAL SHEAR LOAD ON WALL  LBS      ALLOWABLE SHEARWALL CAPACITY  LBS  
#DIV/0!

**SHEARWALL ASSEMBLY SPECIFICATION**

PO - 1-SIDE 7/16" OSB  
FASTENED W/ 8D NAILS AT 6" O.C. PANEL EDGES & 12" O.C. PANEL FIELD - UNBLOCKED  
#DIV/0!

**OVERTURNING EVALUATION:**

RESISTIVE DL  PLF      OVERTURNING MOMENT  K-FT      HOLD DOWN DESIGN LOAD  LBS  
DL AT ENDS OF WALL  LBS      RESISTIVE MOMENT  K-FT      HOLDOWN CAPACITY  LBS

**HOLD-DOWN SPECIFICATION**

NO HOLDOWN REQUIRED