

El Dorado Pier Repair

Project Narrative

Repair an existing pier by re-framing and re-decking with Thruflow grated decking (43% open space). Splice forty-four pier piles and replace two pier piles. Remove an existing boat lift. The project will be completed with a barge and hand tools.

The project is exempt from substantial development per WAC 173-27-040 (2)(b), normal maintenance and repair of an existing structure. The proposed project is categorically exempt from SEPA per WAC 197-11-800 (3) as it is repair of an existing structure.